

LS

WEST
ASSOCIATES
ENVIRONMENTAL ENGINEERS, INC

97 NOV 20 PM 3:54

November 18, 1997

Alameda County Health Care Services Agency
Department of Environmental Health
1131 Harbor Bay Parkway, Suite 250
Alameda, CA 94502-6577
Attn: Ms. Juliet Shin
Hazardous Materials Specialist

**SUBJECT: SUBMITTAL OF QUARTERLY GROUNDWATER MONITORING REPORT,
WEYERHAEUSER PAPER COMPANY, ALAMEDA CORRUGATED BOX FACILITY,
1801 HIBBARD STR., STID 1202**

Dear Ms. Shin,

West & Associates Environmental Engineers, Inc. respectfully submits the third quarter 1997 groundwater monitoring report for the Weyerhaeuser Paper Company, Alameda Corrugated Box Facility. The monitoring report is submitted in accordance with the interim groundwater monitoring plan proposed in our Site Investigation Report of January 1995.

Groundwater samples were analyzed in accordance with the new analytical schedule defined in your May 14, 1996 response letter.

We look forward to your review of the attached report. Should you require any additional information please contact me at (707) 451-1360.

Yours truly,



Brennan Mahoney CPSS
Project Manager
West & Associates Environmental Engineers, Inc.

Enclosure: Groundwater Monitoring Report

cc: Ed Granados, Weyerhaeuser Office of the Environment, Tacoma
John Hipner, WPC Alameda

ENVIRONMENTAL
HEALTH SERVICES
STANDARD FORM 64

**QUARTERLY GROUNDWATER MONITORING REPORT
FORMER UNDERGROUND TANK SITES
JULY - SEPTEMBER 1997**

**WEYERHAEUSER PAPER COMPANY
ALAMEDA CORRUGATED BOX FACILITY
1801 Hibbard Street
Alameda, California
STID 1202**

Submitted to:

**ALAMEDA COUNTY
HEALTH CARE SERVICES AGENCY
DEPARTMENT OF ENVIRONMENTAL HEALTH
Alameda**

Prepared for:

**THE WEYERHAEUSER CORPORATION
OFFICE OF THE ENVIRONMENT
TOXIC/SOLID WASTE TEAM
Tacoma, Washington**

Prepared by:

**WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC.
Vacaville**

October 1997

EXECUTIVE SUMMARY

The Weyerhaeuser Paper Company (WPC) Alameda containerboard facility, at 1801 Hibbard Str., is a corrugated box manufacturing plant. The facility was originally constructed in 1946. Underground fuel tanks had been historically installed at the facility for vehicle, generator and boiler fuel storage. Both gasoline and diesel fuels were formerly stored underground. The last remaining underground tank was removed from the WPC site in January 1994.

The WPC facility is located on Alameda island in San Francisco Bay. The site is less than 0.25 miles west of the Oakland Inner Harbor. Site soils are predominantly sand with minor clay stringers. Unconfined groundwater is 3-6 feet below ground surface and tidally influenced.

There are two separate groundwater study areas at the WPC Alameda site. A former diesel tank site is monitored by one groundwater well (MW-7) on the east side of the property. A former gasoline tank cluster is monitored by seven monitoring wells on west side of the property. Monitoring wells MW-1 through MW-7 were installed by Soil Tech Engineers. Monitoring wells MW-9 through MW-12, MW-3B and MW-4B were installed by West & Associates.

Site investigation at the WPC Alameda facility was concluded in January 1995 with the submittal of a comprehensive report covering all work dating back to 1990. Activity at the site has now shifted to remedial action. In October and November of 1995 contaminated soil was excavated from the site around the former gasoline tank cluster and air sparging lines were installed in the open excavations prior to backfill. A pilot test was performed to evaluate the effectiveness of the newly installed sparging system. Based on results of the pilot test, continuous operation of the sparging system was initiated on March 29, 1996.

During the remedial excavation program monitoring wells MW-1, MW-2, MW-3, MW-4 and MW-9 were removed. In December 1995 two new wells MW-3B and MW-4B were installed in two locations within the newly backfilled excavation area, near the former locations of MW-3 and MW-4, respectively. A total of eight monitoring wells now exist at the site.

A groundwater monitoring program is in effect at the WPC Alameda site. Groundwater monitoring, which consists of depth to groundwater measurements and collection of groundwater samples for chemical analysis, is conducted quarterly. Third quarter groundwater monitoring activities for 1997 were conducted on September 5, 1997.

In correspondence dated May 14, 1996, Alameda County, Environmental Health Services (ACEHS) approved a modified analytical schedule proposed by West & Associates in the March 1996 Quarterly Groundwater Monitoring Report. The frequency of EPA Method 624 and 625 analysis for groundwater samples has been revised from quarterly to semi-annual. Groundwater samples were analyzed by EPA Method 624 and 625 this quarter.

ACKNOWLEDGEMENTS

This report was prepared under authorization of the Weyerhaeuser Corporation, Office of the Environment, Toxic/Solid Waste Team, Tacoma, Washington. The Weyerhaeuser project officer is Mr. Ed Granados, mail stop CH 1K29, Tacoma, WA 98477; (206) 924-6511.

At the WPC plant, both Mr. John Hipner, Plant Engineer and Mr. Tom Muncell, Maintenance Manager, have environmental compliance responsibilities related to this project. The Alameda plant address is 1801 Hibbard Street, PO Drawer X, Alameda, CA 95601; (510) 814-1167.

The lead regulatory agency for the Weyerhaeuser Alameda plant is the Alameda County Health Care Agency, Department of Environmental Health. Ms. Juliet Shin, Hazardous Materials Specialist, is the staff person assigned. The Department of Environmental Health is located at 1131 Harbor Bay Parkway, Suite 250, Alameda, CA 94502-6577; (510) 567-6763.

In the preparation of this quarterly report reliance was made on past site work performed by Soil Tech Engineering, Inc. Soil Tech Engineering is located at 298 Brokaw Road, Santa Clara, CA 95050; (408) 496-0265.

Analytical work performed for this quarters monitoring was sub-contracted to Excelchem Environmental Labs located in Roseville, California. Excelchem is certified by the State Department of Health Services for the analyses performed.

This quarterly groundwater monitoring report was prepared by West & Associates Environmental Engineers, Inc. West & Associates is located at 490 Merchant St., Suite 104, Vacaville, CA 95688; mailing address, PO Box 5891, Vacaville 95696; (707) 451-1360. Principal authors are Mr. Brennan Mahoney CPSS and Mr. Brian W. West PE. (Registered California Civil Engineer No. 32319 - expires 12/31/00).



TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
EXECUTIVE SUMMARY	i
ACKNOWLEDGEMENTS	ii
TABLE OF CONTENTS	iii
1.0 INTRODUCTION	1
1.1 Scope	1
1.2 Summarized Background	1
2.0 FLOATING PRODUCT	5
3.0 GROUNDWATER SAMPLING	5
3.1 Sampling Protocol	5
3.2 Sample Analyses	6
3.3 Conclusions	7
4.0 HYDROLOGIC MONITORING	19
4.1 Conclusions	19
5.0 SUMMARY	20
5.1 Remedial Status	20

APPENDICES

Purge Data Forms
Chain of Custody &
Original Laboratory Report Forms

1.0 INTRODUCTION

Groundwater conditions are periodically monitored at the Weyerhaeuser Paper Company Alameda Containerboard plant based on a schedule proposed to the Alameda County Environmental Health Agency in January 1995 (and amended in May 1996). This report presents results of groundwater monitoring performed during the third quarter (July - September) of 1997.

This quarter, groundwater monitoring was performed on September 5, 1997. During groundwater sampling activities, all eight of the existing monitoring wells were inspected for the presence of floating product, measured for depth to groundwater and samples collected for chemical analysis.

In the following Sections, monitoring procedures are described, monitoring data is summarized and a discussion of results are presented. Technical data is included in the appendix.

1.1 Scope

The scope of this project included performing quarterly groundwater monitoring at Weyerhaeuser Paper Company (WPC) Alameda property, 1801 Hibbard Str., in Alameda. Figure 1 illustrates the WPC Alameda regional setting. Figure 2 depicts the site location. Specific scope items include:

- Check eight existing monitoring wells for floating product
- Measure depth to groundwater in all monitoring wells
- Determine the groundwater gradient profile
- Collect groundwater samples from all eight monitoring wells
- Analyze groundwater samples for contaminants of interest
- Prepare a written report of findings
- Properly manage sampling residues

1.2 Summarized Background

The Weyerhaeuser Paper Company (WPC) Alameda facility located at 1801 Hibbard Str. manufactures corrugated cardboard boxes. The facility was originally constructed in 1946. Underground fuel tanks (UGT) had been historically installed at the facility for vehicle, generator and boiler fuel storage. Both gasoline and diesel fuels were formerly stored. The last remaining UGT was removed from the WPC site in January 1994.

At the end of 1990 the WPC facility was equipped with five underground fuel storage tanks. The five tanks were distributed in three separate installations located along the northwestern side of the facility.

In early 1991 Weyerhaeuser removed a cluster of three, 1,000 gallon gasoline tanks and one, 10,000 gallon diesel tank. Upon removal, the 10,000 gallon diesel tank installation was found to be virtually uncontaminated, however, significant soil and groundwater contamination was encountered at the gasoline tank cluster location.

WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC.

PO Box 5891, Vacaville, California 95696


Project Name: Weyerhaeuser Paper Company - Alameda

Date: Jan. 1995

Location: 1801 Hibbard Str., Alameda, California 94501

Drawing By: BWB

Scale: 1" = 2.5 miles




LEGEND

Figure 1

WPC ALAMEDA FACILITY - REGIONAL SETTING

○ SITE LOCATION



WEST & ASSOCIATES ENVIRONMENTAL ENGINEERS, INC.

PO Box 5891, Vacaville, California 95696



Project Name: Weyerhaeuser Paper Company - Alameda

Date: Jan. 1995

Location: 1801 Hibbard Str., Alameda, California 94501

Drawing By: BWB

Scale: 1" = 0.4 Miles



LEGEND

Figure 2
WPC ALAMEDA FACILITY - SITE LOCATION
○ SITE LOCATION

WEST & ASSOCIATES

The tank removal contractor performed overexcavation at the gasoline tank cluster location in an attempt to remediate soil contamination. Between February and April 1991 the tank excavation was enlarged from 460 ft² to 640 ft² and then to 930 ft².

Four soil samples were collected from the gasoline tank cluster pit sidewalls at the conclusion of overexcavation. Only one endpoint sidewall soil sample (Sample No. 11) was non-detectable for all tested chemical constituents. One of the sidewall soil samples (Sample No. 9) was found to contain only trace levels of toluene. The other two endpoint soil samples (Sample No.'s 8 & 10), were found to contain low levels of TPH and BTXE compounds.

During the time the gasoline tank cluster excavation was open, the standing groundwater level in the pit was observed to rise from greater than 8 feet to less than 4 feet below ground surface. The file record indicates endpoint soil samples were collected from higher on the pit sidewalls as the water level rose.

Both the gasoline tank cluster and diesel tank excavations were backfilled with clean fill. Contaminated soil was transported to off-site disposal.

In December 1991 and again in April 1992, Soil Tech Engineering performed soils and groundwater investigations near the former gasoline tank cluster. A total of six groundwater monitoring wells were installed. Soil samples for laboratory analysis were collected during monitoring well installation. Between December 1991 and July 1993 Soil Tech performed groundwater monitoring on six occasions.

In December 1992, Soil Tech constructed one monitoring well (MW-7) adjacent to the former underground diesel tank, increasing the total number of site wells to seven. STE monitored MW-7 a total of 3 times.

Soil Tech's investigations revealed significant remaining soil contamination as well as widespread groundwater contamination in the vicinity of the former gasoline tank cluster. The six soil borings and monitoring wells completed by STE did not fully define the total extent of either soil or groundwater contamination around the former gasoline tank cluster.

In January 1994 the last remaining underground fuel storage tank, (20,000 gallon diesel) was removed from the WPC property. No evidence of any leakage from the diesel tank was encountered, however, soil contamination from the 1991 gasoline tank cluster was observed on the east sidewall of the diesel tank pit.

West & Associates Environmental Engineers submitted a proposed workplan for additional site investigation to the Alameda County Health Care Agency in November 1993. Site investigations were performed in January and February 1994. In May 1994 a supplemental workplan was submitted to conduct further investigation under the main plant building. In June 1994 an interim report of findings was submitted and in October 1994

clarifications to the May supplemental workplan were submitted to the County. Final site investigation field work took place in September and December 1994.

In October and November 1995 contaminated soil was excavated from the site around the former gasoline tank cluster and air sparging lines were installed in the open excavations prior to backfill. Some of the contaminated soil was aerated on site and reused as backfill material and some was transported to a local landfill for disposal.

During the remedial excavation program monitoring wells MW-1, MW-2, MW-3, MW-4 and MW-9 were removed. In December 1995 two new wells MW-3B and MW-4B were installed in two locations within the newly backfilled excavation area, near the former locations of MW-3 and MW-4, respectively. Subsequent to completion of a pilot test, operation of the groundwater sparging system began in late March 1996.

2.0 FLOATING PRODUCT

This quarter, each monitoring well was visually inspected for the presence of floating product. Prior to well purging, a column of groundwater was bailed from the water surface in a transparent bailer suitable for capture of light hydrocarbons.

No floating product or sheen was detected in any of the groundwater wells inspected this quarter. No floating product has been observed in any WPC Alameda wells on previous monitoring occasions.

3.0 GROUNDWATER SAMPLING

A quantity of groundwater is purged from each monitoring well prior to collecting a sample for chemical analysis. A description of equipment and procedures employed for groundwater purging and sample collection is presented in the following paragraphs.

3.1 Sampling Protocol

All the WPC Alameda monitoring wells are equipped with a 0.5 inch OD polyethylene tube extending the full depth of the well. Well purging is accomplished by attaching an Accuwell PTP-150 peristaltic pump at the well head to draw groundwater from the well. This procedure eliminates the need for any downhole equipment.

As groundwater is extracted from the well, 20ml samples are periodically collected for measurement of pH, temperature and conductivity using a Hydac instrument. Groundwater data is recorded on purge data forms (presented in the Appendix). At the conclusion of purging, the well is allowed to recharge to at least 80% of its initial water level prior to sample collection.

Purge water is contained in 55 gallon drums during the sampling process. At the conclusion of sampling, purge water drums are sealed, labeled and stored on-site in a secure area pending chemical analysis and arrangements for proper disposal.

Groundwater sample collection is performed by lowering a new, disposable, bailer into the well. Sample water is transferred to a laboratory supplied 40 ml VOA bottle containing a suitable preservative. The sample bottles are only opened during sample transfer, are completely filled and are not re-opened again by field personnel.

All samples are immediately labeled, sealed in zip lock bags and placed in a cooler containing crushed ice. The samples remain chilled, sealed and undisturbed during transport to the testing laboratory, usually within no more than 48 hours. All samples are entered on a chain of custody form which accompanies the sample set at all times.

Chemical analysis was performed by Excelchem Environmental Labs, located in Roseville, California. Excelchem is certified by the Department of Health Services for the analyses performed.

Quality assurance and quality control measures include:

- Utilizing State WQCB approved sampling methods
- Assigning trained, experienced personnel for sample collection
- Utilizing laboratory supplied sample containers
- Employing extraction methods not requiring downhole equipment
- Using new, disposable bailers
- Sampling wells sequentially from cleanest to most contaminated
- Maintaining sample chain of custody documentation
- Keeping samples in a chilled state until laboratory delivery
- Storing high concentration samples in a separate container
- Prompt delivery of the sample set to the testing laboratory
- Utilizing a DHS certified laboratory

3.2 Sample Analyses

The present analytical schedule for the site was proposed by West & Associates in the March 1996 Quarterly Groundwater Monitoring Report and approved by the ACEHS in correspondence dated May 14, 1996. The frequency of EPA Method 624 and 625 analysis for groundwater samples has been changed from quarterly to semi-annual. Analysis of groundwater samples by EPA Methods 624 and 625 was conducted this quarter.

Each groundwater sample except MW-7 was analyzed for Total Petroleum Hydrocarbons in the gasoline range (TPH-g) by modified EPA method 8015 and organic volatiles by EPA method 624. Groundwater from monitoring well MW-7 was analyzed for TPH in the diesel range by modified EPA method 8015. Groundwater from well MW-3B was analyzed for Naphthalene by EPA method 625.

All analyses were performed using EPA approved test methods. Minimum detection limits for all analyses were within Tri-regional guidelines and are indicated on each original laboratory report form.

Results

This quarters analytical results for TPH-g and BTXE contamination are presented in Table 1. Copies of original laboratory data sheets and chain of custody forms are presented in the appendix.

Results of laboratory analysis indicate that TPH as diesel was detected in groundwater sample MW-7 at a concentration of 0.412 mg/l.

TABLE 1
PETROLEUM CONTAMINATION ANALYSES - GROUNDWATER
September 5, 1997
All Values in ug/l

WELL ID	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
MW-3B	2,140	33.7	31.6	108	28.1
MW-4B	156	2.1	ND	0.9	ND
MW-5	ND	1.2	ND	ND	ND
MW-6	ND	ND	ND	ND	ND
MW-10	ND	ND	ND	ND	ND
MW-11	ND	ND	ND	ND	ND
MW-12	ND	ND	ND	ND	ND

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

TPH: Total Petroleum Hydrocarbons

3.3 Conclusions

A slightly higher TPH-g concentration was detected in the water sample from MW-3B this quarter relative to last quarter. TPH-g was detected at a slightly lower concentration in well MW-4B this quarter relative to last quarter. Benzene concentrations were lower in monitoring wells MW-3B, MW-4B and MW-6, and slightly higher in well MW-5 this quarter, compared to last quarter.

TPH-g was not detected in wells MW-5, MW-6, MW-10, MW-11 or MW-12 this quarter. Benzene was not detected in wells MW-6, MW-10, MW-11 or MW-12 this quarter.

Contaminant concentrations detected in all contaminated wells this quarter are within the range of previous fluctuation observed at the site, during recent monitoring events. Benzene concentrations detected in MW-3B this quarter are the lowest levels detected in this well since it was installed.

TPH-gas and BTXE concentrations remain very low in all existing monitoring wells except for MW-3B.

A continued decreasing trend in TPH-g and BTXE concentrations in MW-3B has been observed since air sparging activities began.

Table 2 presents the percent reduction in TPH-gas and benzene concentrations in well MW-3B compared to the previous six quarters. MW-3B has historically been the most contaminated well at the site.

TABLE 2
GROUNDWATER CONTAMINANT COMPARISON: WELL MW-3B
FIRST QUARTER 1996 THRU THIRD QUARTER 1997
All Values in ug/l

Date	TPH (gas)	BENZENE	PERCENT REDUCTION TPH-gas (since 2/96)	PERCENT REDUCTION BENZENE (since 2/96)
2/96	19,000	2,100	NA	NA
6/96	11,000	1,300	42%	38%
9/96	6,000	840	68%	60%
11/96	5,500	440	71%	79%
2/97	12,000	1,000	37%	52%
6/97	2,030	293	89%	86%
9/97	2,140	33.7	88%	98%

ABBREVIATIONS

ug/l: Micrograms per liter

TPH: Total Petroleum Hydrocarbons

Figure 3 graphically depicts the declining trend of benzene in well MW-3B. Since the second quarter of 1995, benzene concentrations in well MW-3B have been reduced 98%.

A summary of historic TPH-g and BTXE contaminant concentrations in groundwater is presented in Table 3.




FIGURE 3

Results of organic volatile analysis this quarter are consistent with previous findings. A summary of historic organic volatile contaminant concentrations in groundwater is presented in Table 4.

Naphthalene was not detected above laboratory detection limits in the water sample from MW-3B this quarter. A summary of historic naphthalene contaminant concentrations in groundwater is presented in Table 5.

TABLE 3
SUMMARY OF PETROLEUM CONTAMINATION ANALYSES
All Values in ug/l

MONITORING WELL MW-2

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
12/23/91	2,300	720	66	240	1.5
4/27/92	1,100	9.4	5.3	24	2
7/31/92	1,500	3.3	5.3	26	10
1/8/93	70	ND	ND	1.4	0.5
4/6/93	ND	ND	ND	ND	ND
7/12/93	1,600	1.4	2.3	8.2	2.5
2/94	200	390	25	50	7.1
6/94	1,300	370	44	170	100
12/94	3,400	1,100	86	190	28
3/7/95	6,500	2,300	240	310	120
9/26/95	440	140	26	46	52

TABLE 3 CONTINUED - MONITORING WELL MW-3
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
12/23/91	14,000	3,000	540	1,200	370
4/27/92	9,400	57	50	220	4.6
7/31/92	1,400	1.9	5.1	23	8.3
1/8/93	15,000	38	40	140	64
4/6/93	21,000	62	76	200	84
7/12/93	22,000	22	41	120	42
2/94	5,400	3,900	680	840	390
6/94	23,000	8,500	1,700	3,800	1,600
12/94	41,000	9,900	2,900	3,500	1,400
3/7/95	42,000	9,900	3,000	4,100	1,600
9/26/95	24,000	5,300	1,200	2,200	940

TABLE 3 CONTINUED - MONITORING WELL MW-3B
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
2/7/96	19,000	2,100	380	1,200	480
6/5/96	11,000	1,300	250	860	370
9/4/96	6,000	840	98	410	140
11/21/96	5,500	440	31	140	50
2/13/97	12,000	1,000	210	690	120
6/6/97	2,030	293	14	11	23
9/5/97	2,140	33.7	31.6	108	28.1

TABLE 3 CONTINUED - MONITORING WELL MW-4
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
4/27/92	790	7.7	2.6	11	2
7/31/92	1,300	6.1	4.3	21	7.3
1/8/93	860	1.5	4.5	17	9.6
4/6/93	2,500	5.2	6.3	17	11
7/12/93	2,000	1.8	3.8	11	3.9
2/94	1,000	54	2.7	4.7	1.4
6/94	460	46	0.8	8.4	1.1
12/94	2,400	200	7.5	28	7.5
3/7/95	3,800	360	14	49	33
9/26/95	2,900	90	ND	5.7	8.9

TABLE 3 CONTINUED - MONITORING WELL MW-4B
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
2/7/96	520	3	2.4	1.0	1.6
6/5/96	350	ND	ND	ND	1.6
9/4/96	71	3.3	ND	0.70	1.8
11/21/96	170	1.5	ND	ND	1.0
2/13/97	220	ND	ND	ND	ND
6/6/97	177	3.5	4.3	6.7	1.0
9/5/97	156	2.1	ND	0.9	ND

TABLE 3 CONTINUED - MONITORING WELL MW-5
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
4/27/92	ND	ND	ND	ND	ND
7/31/92	ND	ND	ND	ND	ND
1/8/93	ND	ND	ND	ND	ND
4/6/93	ND	ND	ND	ND	ND
7/12/93	0.27	ND	ND	1.4	0.6
2/94	ND	1.8	ND	ND	ND
6/94	ND	1.0	ND	ND	ND
12/94	93	3.0	0.9	3.0	0.8
3/7/95	79	2.9	ND	ND	ND
9/26/95	67	ND	ND	ND	ND
2/7/96	120	7	ND	ND	ND
6/5/96	100	ND	ND	ND	ND
9/4/96	ND	2.4	ND	ND	ND
11/21/96	62	ND	ND	ND	ND
2/13/97	26	0.58	ND	ND	ND
6/6/97	ND	0.7	ND	0.5	ND
9/5/97	ND	1.2	ND	ND	ND

TABLE 3 CONTINUED - MONITORING WELL MW-6
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
4/27/92	ND	ND	ND	ND	ND
7/31/92	ND	ND	ND	ND	ND
1/8/93	ND	ND	ND	ND	ND
4/6/93	ND	ND	ND	ND	ND
7/12/93	NA	NA	NA	NA	NA
2/94	ND	2.6	ND	ND	ND
6/94	ND	2.2	ND	ND	ND
12/94	ND	1.3	ND	ND	ND
3/7/95	72	2.5	ND	ND	ND
9/26/95	ND	ND	ND	ND	ND
2/7/96	60	0.84	ND	ND	ND
6/5/96	45	1.2	ND	ND	ND
9/4/96	40	0.80	ND	ND	ND
11/21/96	ND	ND	ND	ND	ND
2/13/97	25	0.54	ND	ND	ND
6/6/97	ND	0.5	ND	ND	ND
9/5/97	ND	ND	ND	ND	ND

TABLE 3 CONTINUED - MONITORING WELL MW-7
All Values in ug/l

DATE	TPH diesel	TPH gas	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
1/8/93	ND	NA	ND	ND	ND	ND
4/6/93	190	NA	ND	ND	ND	ND
7/12/93	80	NA	ND	ND	ND	ND
2/94	ND	ND	ND	ND	ND	ND
6/94	ND	ND	ND	ND	ND	ND
12/94	3.9	ND	ND	ND	ND	ND
3/7/95	1,400	NA	NA	NA	NA	NA
9/26/95	1,100	NA	NA	NA	NA	NA
2/7/96	1,200	NA	NA	NA	NA	NA
6/5/96	1,100	NA	NA	NA	NA	NA
9/4/96	ND	NA	NA	NA	NA	NA
11/21/96	2.2	NA	NA	NA	NA	NA
2/13/97	3.8	NA	NA	NA	NA	NA
6/6/97	318	NA	NA	NA	NA	NA
9/5/97	412	NA	NA	NA	NA	NA

TABLE 3 CONTINUED - MONITORING WELL MW-9
All Values in ug/l

DATE	TPH (gas)	BENZENE	TOLUENE	XYLENES	ETHYL BENZENE
2/94	1,900	63	4.3	14	22
6/94	5,300	150	20	110	380
12/94	12,000	600	20	55	120
3/7/95	9,900	820	22	78	230
9/26/95	5,900	340	ND	20	53

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

NA: Not Analyzed

TPH: Total Petroleum Hydrocarbons

TABLE 4 - SUMMARY OF VOLATILE ORGANIC ANALYSES RESULTS
All Values in ug/l

MONITORING WELL MW-3

DATE	VINYL CHLORIDE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	CARBON DISULFIDE
2/94	ND	130	95	120
3/7/95	81	110	150	ND
9/26/95	ND	100	ND	ND

TABLE 4 CONTINUED - MONITORING WELL MW-3B
All Values in ug/l

DATE	VINYL CHLORIDE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	1,1,2-TRICHLORO-ETHANE
2/7/96	ND	ND	ND	ND
9/4/96	ND	30	5.0	ND
2/13/97	ND	21	33	60
9/5/97	ND	21.4	ND	ND

TABLE 4 CONTINUED - MONITORING WELL MW-4
All Values in ug/l

DATE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	TRICHLORO-ETHENE	CARBON DISULFIDE	CHLORO-ETHANE
2/94	22	18	2.1	4.7	1.9
3/7/95	11	15	ND	ND	ND
9/26/95	10	6.6	ND	ND	ND

TABLE 4 CONTINUED - MONITORING WELL MW-4B
All Values in ug/l

DATE	1,1-DICHLORO-ETHANE	1,2-DICHLORO-ETHANE	TETRACHLORO-ETHENE	TRICHLORO-ETHENE
2/7/96	7.4	6.2	ND	ND
9/4/96	15	13	ND	1.2
2/13/97	12	10	1.8	1.48
9/5/97	9.3	6.3	0.6	ND

TABLE 4 CONTINUED - MONITORING WELL MW-5
All Values in ug/l

DATE	1,1-DICHLORO-EHTANE	1,2-DICHLORO-ETHANE	1,1-DICHLORO-ETHENE	TETRA-CHLORO-ETHENE	TRICHLORO-ETHENE
2/94	11	ND	ND	1.1	ND
3/7/95	24	ND	ND	ND	ND
9/26/95	31	ND	ND	ND	ND
2/7/96	31	ND	ND	ND	ND
9/4/96	28	2.5	1.1	3.5	1.4
2/13/97	17	1.4	ND	1.1	ND
9/5/97	19.5	1.5	ND	0.6	0.7

TABLE 4 CONTINUED - MONITORING WELL MW-6
All Values in ug/l

DATE	1,1-DICHLORO-EHTANE	1,2-DICHLORO-ETHANE	TETRA-CHLORO-ETHENE	TRICHLORO-ETHENE	1,2-DICHLORO-ETHENE
2/94	2.6	1.1	1.3	ND	2.1
3/7/95	9.4	ND	ND	ND	ND
9/26/95	12	ND	ND	ND	ND
2/7/96	7.6	ND	ND	ND	ND
9/4/96	16	5.4	1.5	2.0	ND
2/13/97	16	4.1	1.6	1.7	ND
9/5/97	10.9	2.7	0.7	0.9	ND

TABLE 4 CONTINUED - MONITORING WELL MW-9
All Values in ug/l

DATE	1,1-DICHLORO-EHTANE	1,2-DICHLORO-EHTANE
3/7/95	12	14
9/26/95	8.7	ND

TABLE 4 CONTINUED - MONITORING WELL MW-12
All Values in ug/l

DATE	1,1-DICHLOROETHANE	1,2-DICHLOROETHANE	TETRACHLOROETHENE
3/7/95	11	ND	ND
9/26/95	9.6	ND	ND
9/4/96	2.4	ND	ND
2/13/97	ND	3.2	4.3
9/5/97	2.2	ND	ND

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

TABLE 5
SUMMARY OF SEMI-VOLATILE ORGANIC ANALYSES RESULTS
All Values in ug/l

MONITORING WELL MW-2

DATE	NAPHTHALENE
2/94	19
3/7/95	2.4
9/26/95	ND

TABLE 5 CONTINUED - MONITORING WELL MW-3
All Values in ug/l

DATE	NAPHTHALENE	METHYLNAPHTHALENE
2/94	19	45
3/7/95	120	ND
9/26/95	310	ND

TABLE 5 CONTINUED - MONITORING WELL MW-3B
All Values in ug/l

DATE	NAPHTHALENE
2/7/96	130
9/4/96	100
2/13/97	260
9/5/97	ND

ABBREVIATIONS

ug/l: Micrograms per liter

ND: Not Detected (See Appendix for minimum detection limits)

4.0 HYDROLOGIC MONITORING

Depth to groundwater (DTGW) was measured in all eight of the WPC Alameda monitoring wells on September 5, 1997 this quarter. DTGW was measured using a Solinst electronic sounding meter. Measurement accuracy was +/- 0.01 feet.

Table 6 presents depth to groundwater measurements (DTGW) and groundwater elevations (GW) as measured on September 5, 1997. The change in groundwater elevation in each well relative to the most recent previous measurement (June 6, 1997) is also indicated in Table 6.

Figure 4 illustrates groundwater contours under the site extrapolated from the September 5, 1997 groundwater elevation data. The groundwater gradient direction measured this quarter was toward the west. This groundwater gradient direction is consistent with previous groundwater gradient observations at the WPC site.

4.1 Conclusions

Groundwater elevations were lower in all monitoring wells this quarter as compared to last quarter. The decrease in groundwater elevations relative to last quarter is consistent with the historical fluctuations observed previously at the site. The groundwater gradient direction was measured to be toward the west this quarter, which is within the range of previous recordings.

TABLE 6 - HYDROLOGIC MEASUREMENTS
September 5, 1997
(All measurements in feet)

WELL ID	TOC	DTGW	GWE	CHANGE ¹
MW-3B	9.81	6.44	3.37	-0.28
MW-4B	9.59	6.80	2.79	-0.26
MW-5	9.77	6.71	3.06	-0.26
MW-6	10.04	7.41	2.63	-0.23
MW-7	7.68	3.25	4.43	-0.33
MW-10	9.37	6.22	3.15	-0.26
MW-11	8.78	5.26	3.52	-0.23
MW-12	12.32	8.85	3.47	-0.33

ABBREVIATIONS

TOC: Top of Casing

DTGW: Depth to Groundwater

GWE: Groundwater Elevation

¹ Relative to last available DTGW measurement: June 6, 1997

5.0 SUMMARY

- All eight WPC groundwater wells were monitored on September 5, 1997.
- No floating product was observed in any groundwater well this quarter.
- Continued improvement in groundwater quality was observed this quarter.
- Groundwater levels have decreased under the entire site as compared to the last quarter of monitoring (June 6, 1997).

5.1 Remedial Status

In November 1995 contaminated soil was excavated in the vicinity of the former underground fuel tank cluster. The area was backfilled with clean soil.

Construction of a groundwater sparging/soil vapor extraction system was completed in February 1996.

Pilot testing was completed on the newly installed groundwater sparging/soil vapor extraction system on March 19, 1996. Findings of the pilot test were presented in the March 1996 Air Sparging and Vapor


Extraction System Test Report prepared by West & Associates Environmental Engineers.

Full scale operation of the sparging system began at the end of March 1996 under permit from the Bay Area Air Quality Management District. Activated carbon adsorption is used to prevent volatile emissions to the atmosphere. While in operation, the remedial system is monitored at least weekly.

A decrease in soil vapor volatile concentration has been observed since start up of the sparging system. There has also been a decrease in groundwater contaminant concentrations observed since start up of remedial activities. The benzene concentration measured in groundwater samples collected from well MW-3B since the start of remedial activities is presented graphically in Figure 3. TPH-gas and benzene concentrations in MW-3B are approximately 88% and 98% lower, respectively, than prior to the start up of groundwater sparging.

LEDGEND

- ▲ Soil Boring
- ⊕ Monitoring Well
- Pit Sidewall or Bottom



WEYERHAEUSER - ALAMEDA		
SCALE: 1" = 10'	APPROVED BY:	DRAWN BY BWV
DATE: SEPT. '97		REVISED
GROUNDWATER CONTOURS - SEPT. '97		
1801 HIBBARD ST.		DRAWING NUMBER FIG. 4

PURGE DATA FORMS

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: FORMER REMEDIAL EXCAVATION AREA

Monitoring Well ID: MW-3B Sampler: BWW BGM

Date: SEPT. 5, 1997 Time: 10:54 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: GASOLINE ODOR PRESENT / CLEAR

$$\frac{16'}{\text{WELL DEPTH}} - \frac{6.44'}{\text{DTGW}} \times \left(\frac{2''}{17} \right)^4 = \frac{1.6}{\text{WELL VOLUME (GALS)}}$$

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 10 ⁶	PH
10:54	0	0	69.8	12.93	6.53
10:56	1.6	1.6	70.1	12.72	6.46
10:58	1.6	3.2	70.1	13.01	6.46
11:00	1.6	4.8	70.1	13.04	6.49

REMARKS: D.O. - 0.3 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: NORTHWEST OF FORMER REMEDIAL EXCAVATION

Monitoring Well ID: MW-4B Sampler: ~~BWV~~ BGM

Date: SEPT. 5 1997 Time: 1:44 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO APPARENT GAS ODOR / CLEAR

16' 6.80' 2" 4" 1.5
WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 10 ⁶	PH
1:44	0	0	74.5	9.05	6.66
1:45 ³⁰	1.5	1.5	76.1	9.32	6.61
1:47	1.5	3.0	76.2	9.79	6.57
1:48 ³⁰	1.5	4.5	76.4	9.62	6.58

REMARKS: D.O. - 0.2 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: WEST OF FORMER REMEDIAL EXCAVATION

Monitoring Well ID: MW-5 Sampler: ~~BWW~~ BGM

Date: SEPT. 9, 1997 Time: 11:06 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO APPARENT GAS ODOR / CLEAR

17.5' 6.71' 2" ~~4"~~ 1.8
WELL DEPTH - DTGW x .17 ~~.66~~ = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
11:06	0	0	70.2	7.79	6.88
11:08	1.8	1.8	70.8	7.45	6.88
11:10	1.8	3.6	70.0	7.75	6.78
11:12	1.8	5.4	69.7	7.78	6.76

REMARKS: D.O. - 0.4 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: WEST END OF SITE

Monitoring Well ID: MW-6 Sampler: ~~BWW~~ BGM

Date: SEPT. 5, 1997 Time: 1:36 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO APPARENT GAS ODOR / CLEAR

19.65' 7.41' 2" 4" 2.0
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
1:36	0	0	73.1	6.54	6.95
1:38	2	2	74.6	4.44	7.05
1:40	2	4	73.4	6.28	6.84
1:42	2	6	73.3	7.62	6.76

REMARKS: D.O. - 0.9 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: EAST END OF SITE

Monitoring Well ID: MW-7 Sampler: ~~BWW~~ BGM

Date: SEPT. 5, 1997 Time: 12:04 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO HYDROCARBON ODOR / YELLOWISH - CLEAR

17.86' 3.25' 2" 4" 2.5
WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
12:04	0	0	73.5	19.07	7.08
12:07	2.5	2.5	72.7	15.50	6.64
12:10	2.5	5.0	70.8	15.91	6.36
12:13	2.5	7.5	69.7	17.44	6.21

REMARKS: D.O. - 0.4 mg / l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: IN STREET, NORTH OF SITE

Monitoring Well ID: MW-10 Sampler: ~~BWW~~ BGM

Date: SEPT. 5, 1997 Time: 1.00 AM PM

Floating Product: Y (N) Petroleum Sheen: Y (N)

ODOR / APPEARANCE: NO GASOLINE ODOR / SILTY → CLEAR

$$\frac{17.05'}{WELL\ DEPTH} - \frac{6.22'}{DTGW} \times .17 \cdot \frac{2''}{.66} \cdot \frac{4''}{7.1} = \frac{7.1}{WELL\ VOLUME\ (GALS)}$$

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
1:00 P	0	0	73.6	5.99	7.28
1:07	7.1	7.1	73.7	5.53	7.27
1:14	7.1	14.2	73.1	5.44	7.01
1:24	9.0	23.2	73.0	5.12	6.93

REMARKS: D.O. - 1.2 mg/l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: EAST OF FORMER GAS UST CLUSTER

Monitoring Well ID: MW-11 Sampler: ~~JWW~~ BGM

Date: SEPT. 3, 1997 Time: 12:25 AM PM

=====

Floating Product: Y N Petroleum Sheen: Y N

ODOR / APPEARANCE: NO GASOLINE ODOR / CLEAR

18.40' 5.26' 2" 4" 8.6
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

=====

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
12:25	0	0	71.5	8.17	6.95
12:34	8.6	8.6	72.3	7.89	6.99
12:42	8.6	17.2	71.1	7.66	7.06
12:52	8.6	25.8	70.1	7.80	6.95

REMARKS: D.O. - 4.4 mg / l

WEST & ASSOCIATES ENGINEERS

GROUNDWATER SAMPLING - PURGE DATA FORM

Project: WEYERHAEUSER ALAMEDA

Location: INSIDE BUILDING (SHOP AREA)

Monitoring Well ID: MW-12 Sampler: ~~BWW~~ BGM

Date: SEPT. 5, 1997 Time: 11:22 AM ~~PM~~

=====
 Floating Product: Y N Petroleum Sheen: Y N
APPARENT
 ODOR / APPEARANCE: NO GAS ODOR / CLEAR

15.90' 8.85' 2" 4" 4.6
 WELL DEPTH - DTGW x .17 .66 = WELL VOLUME (GALS)

PURGE MEASUREMENTS

TIME	PURGE VOLUME GALLONS	CUMULATIVE GALLONS	TEMP. °F	CONDUCT umhos x 100	PH
11:22	0	0	70.1	12.87	6.68
11:27	4.6	4.6	71.5	12.97	6.54
11:34	4.6	9.2	71.3	12.61	6.52
11:39	4.6	13.8	71.3	12.84	6.51

REMARKS: D.O. - 0.7 mg/l

Excelchem
Environmental Labs

500 Giuseppe Court, Suite 9
Roseville, Ca. 95678
(916) 773-3664

CHAIN-OF-CUSTODY RECORD AND ANALYSIS REQUEST

Project Manager: **BRENNAN MAHONEY** Phone #: **(707) 451-1360**

ANALYSIS REQUEST **997026** **TAT**

Company/Address: **WEST & ASSOCIATES** FAX #: **(707) 448-6998**
P.O. Box 5891, VACAVILLE, CA 95696

Project Number: P.O.#: Project Name: **WPC ALAMEDA**

Project Location: **ALAMEDA** Sampler Signature: *[Signature]*

Sample ID	Sampling		Container				Method Preserved				Matrix		BTEX (602/802C)	BTEX/TPH as Gasoline (602/8020/8015)	TPH as Diesel (8015)	TPH as Oil (8015)	Total Oil & Grease (5520 B/E,F)	Total Oil & Grease IR (5520 B/E,F,C)	96 - Hour Fish Bioassay	EPA 601/8010	EPA 602/8020	EPA 615/8150	EPA 608/8080 - Pesticides	EPA 608/8080-PCBs	EPA 624/8240	EPA 625/8270 NAPHTHALENE	ORGANIC LEAD	Reactivity, Corrosivity, Ignitibility	W.E.T. (✓)		RUSH SERVICE (12 hr) or (24 hr)	EXPEDITED SERVICE (48 hr) or (1 wk)	STANDARD SERVICE (2wk)				
	DATE	TIME	VOA	SLEEVE	1L GLASS	1L PLASTIC	HCl	HNO3	ICE	NONE	WATER	SOIL																	TOTAL (✓)								
MW-3B	9/5		4	1			✓		✓		✓		✓																								
MW-4B			4				✓		✓		✓		✓																								
MW-5			4				✓		✓		✓		✓																								
MW-6			4				✓		✓		✓		✓																								
MW-7				1			✓		✓		✓		✓																								
MW-10			4				✓		✓		✓		✓																								
MW-11			4				✓		✓		✓		✓																								
MW-12	9/5		4				✓		✓		✓		✓																								

Relinquished by: <i>[Signature]</i>	Date: 9/8/97 Time: 9:00	Received by: <i>[Signature]</i>	Remarks:
Relinquished by: <i>[Signature]</i>	Date: Time:	Received by:	
Relinquished by: <i>[Signature]</i>	Date: 9/8/97 Time: 9:00	Received by Laboratory: <i>[Signature]</i>	

**EXCELICHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
BTEX Analyzed: 09-11-97
TPHg Analyzed: 09-11-97

Project : WPC Alameda Matrix: Water

	Benzene	Toluene	Ethyl- benzene	Total Xylenes	TPHg
	<u>PPB</u>	<u>PPB</u>	<u>PPB</u>	<u>PPB</u>	<u>PPB</u>
Reporting Limit:	5.0	5.0	5.0	5.0	500

SAMPLE

Laboratory Identification:

MW-3B	33.7	31.6	28.1	108	2140
W0997052					

ppb= Parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

ANALYTICAL PROCEDURES


BTEX-- Benzene, toluene, ethylbenzene, and total xylene isomers (BTEX) are analyzed by using EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID).

TPHg-- Total petroleum hydrocarbons as gasoline (low-to-medium boiling points) are analyzed by using modified EPA Method 8015, which utilizes a GC equipped with an FID.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention:	Mr. Brennan Mahoney	Date Sampled:	09-05-97
	West & Associates	Date Received:	09-08-97
	490 Merchant St, Ste 104	BTEX Analyzed:	09-11,12-97
	Vacaville, CA 95688	TPHg Analyzed:	09-11,12-97

Project : WPC Alameda Matrix: Water

	Benzene <u>PPB</u>	Toluene <u>PPB</u>	Ethyl- benzene <u>PPB</u>	Total Xylenes <u>PPB</u>	TPHg <u>PPB</u>
Reporting Limit:	0.5	0.5	0.5	0.5	50

SAMPLE

Laboratory Identification:

MW-4B W0997053	2.1	ND	ND	0.9	156
MW-5 W0997054	1.2	ND	ND	ND	ND
MW-6 W0997055	ND	ND	ND	ND	ND
MW-10 W0997057	ND	ND	ND	ND	ND
MW-11 W0997058	ND	ND	ND	ND	ND
MW-12 W0997059	ND	ND	ND	ND	ND


ppb= Parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

ANALYTICAL PROCEDURES


BTEX-- Benzene, toluene, ethylbenzene, and total xylene isomers (BTEX) are analyzed by using EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID).

TPHg--Total petroleum hydrocarbons as gasoline (low-to-medium boiling points) are analyzed by using modified EPA Method 8015, which utilizes a GC equipped with an FID.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention:	Mr. Brennan Mahoney West & Associates 490 Merchant St, Ste 104 Vacaville, CA 95688	Date Sampled:	09-05-97
		Date Received:	09-08-97
		TPHd Analyzed:	09-15-97

Project : WPC Alameda Matrix: Water

TPHd

PPB

Reporting Limit: 50

SAMPLE

Laboratory Identification


MW-7 412
W0997056

PPB = Parts per billion = ug/L = microgram per Liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.


ANALYTICAL PROCEDURES

TPHd--Total petroleum hydrocarbons as diesel (high boiling points) are measured by extraction using EPA Method 3510 followed by modified EPA Method 8015 with direct sample injection into a GC equipped with an FID.


Laboratory Representative

09-18-97
Date Reported

**EXCELICHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
Date Analyzed: 09-09-97

Project : WPC Alameda
Sample ID: MW-3B
Lab ID: W0997052

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	5.0	ND	2-Butanone	5.0	ND
Chloromethane	5.0	ND	Bromodichloromethane	5.0	ND
Vinyl Chloride	5.0	ND	Cis-1,3-Dichloropropene	5.0	ND
Bromomethane	5.0	ND	Trans-1,3-Dichloropropene	5.0	ND
Chloroethane	5.0	ND	1,1,2-Trichloroethane	5.0	ND
Trichlorofluoromethane	5.0	ND	Trans-1,4-dichloro-2-butene	5.0	ND
Acetone	50	ND	Toluene	5.0	24.4
1,1-Dichloroethene	5.0	ND	Tetrachloroethene	5.0	ND
Methylene Chloride	110	ND	2-Hexanone	5.0	ND
Carbon disulfide	5.0	ND	4-Methyl-2-pentanone	5.0	ND
Trans-1,2-Dichloroethene	5.0	ND	Chlorobenzene	5.0	ND
1,1-Dichloroethane	5.0	21.4	Ethylbenzene	5.0	19.4
Chloroform	5.0	ND	M+P-Xylene	5.0	32.4
1,2-Dichloroethane	5.0	ND	O-Xylene	5.0	34.6
Iodomethane	5.0	ND	Styrene	5.0	ND
Dibromochloromethane	5.0	ND	Bromoform	5.0	ND
1,1,1-Trichloroethane	5.0	ND	1,1,2,2-Tetrachloroethane	5.0	ND
Carbon Tetrachloride	5.0	ND	1,3-Dichlorobenzene	5.0	ND
Benzene	5.0	163	1,4-Dichlorobenzene	5.0	ND
Trichloroethene	5.0	ND	1,2-Dichlorobenzene	5.0	ND
1,2-Dichloropropane	5.0	ND			


ppb = parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	108%
	Toluene-d8	103%
	4-Bromofluorobenzene	101%


ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative

09-18-97
Date Reported

EXCELCHEM ENVIRONMENTAL LABS



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
Date Analyzed: 09-09-97

Project : WPC Alameda
Sample ID: MW-4B
Lab ID: W0997053

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	16	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	0.6
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	9.3	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	6.3	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dbromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	1.4	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	ND	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			


ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	105%
	Toluene-d8	104%
	4-Bromofluorobenzene	100%

ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
Date Analyzed: 09-09-97

Project : WPC Alameda
Sample ID: MW-5
Lab ID: W0997054

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	5.0	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	0.6
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	19.5	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	1.5	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dibromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	0.9	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	0.7	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			


ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	107%
	Toluene-d8	104%
	4-Bromofluorobenzene	100%

ANALYTICAL PROCEDURES


Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative

09-18-97
Date Reported

EXCEL CHEM

ENVIRONMENTAL LABS



500 Giuseppe Court, Suite 9
 Roseville, CA 95678
 Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
 West & Associates
 490 Merchant St, Ste 104
 Vacaville, CA 95688

Date Sampled: 09-05-97
 Date Received: 09-08-97
 Date Analyzed: 09-09-97

Project : WPC Alameda
 Sample ID: MW-6
 Lab ID: W0997055

Matrix: Water

	Reporting Measured			Reporting Measured	
	Limit	Value		Limit	Value
624 GCMS	(ug/L)	(ug/L)	624 GCMS	(ug/L)	(ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	5.0	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	0.7
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	10.9	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	2.7	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dibromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	ND	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	0.9	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			


ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	108%
	Toluene-d8	105%
	4-Bromofluorobenzene	100%

ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


 Laboratory Representative

09-18-97
 Date Reported

**EXCELICHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
Date Analyzed: 09-09-97

Project : WPC Alameda
Sample ID: MW-10
Lab ID: W0997057

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	5.0	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	ND
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	ND	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	ND	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dibromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	ND	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	ND	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			


ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	109%
	Toluene-d8	105%
	4-Bromofluorobenzene	100%


ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
Date Analyzed: 09-09-97

Project : WPC Alameda
Sample ID: MW-11
Lab ID: W0997058

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	5.0	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	ND
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	ND	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	ND	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dibromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	ND	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	ND	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			


ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	108%
	Toluene-d8	105%
	4-Bromofluorobenzene	100%


ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative

09-18-97
Date Reported

EXCELCHEM ENVIRONMENTAL LABS



500 Giuseppe Court, Suite 9
Roseville, CA 95678

Phone#: (916) 773-3664 Fax#: (916) 773-4784

ANALYSIS REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Sampled: 09-05-97
Date Received: 09-08-97
Date Analyzed: 09-09-97

Project : WPC Alameda
Sample ID: MW-12
Lab ID: W0997059

Matrix: Water

624 GCMS	Reporting Measured		624 GCMS	Reporting Measured	
	Limit (ug/L)	Value (ug/L)		Limit (ug/L)	Value (ug/L)
Dichlorodifluoromethane	0.5	ND	2-Butanone	0.5	ND
Chloromethane	0.5	ND	Bromodichloromethane	0.5	ND
Vinyl Chloride	0.5	ND	Cis-1,3-Dichloropropene	0.5	ND
Bromomethane	0.5	ND	Trans-1,3-Dichloropropene	0.5	ND
Chloroethane	0.5	ND	1,1,2-Trichloroethane	0.5	ND
Trichlorofluoromethane	0.5	ND	Trans-1,4-dichloro-2-butene	0.5	ND
Acetone	5.0	ND	Toluene	0.5	ND
1,1-Dichloroethene	0.5	ND	Tetrachloroethene	0.5	ND
Methylene Chloride	5.0	ND	2-Hexanone	0.5	ND
Carbon disulfide	0.5	ND	4-Methyl-2-pentanone	0.5	ND
Trans-1,2-Dichloroethene	0.5	ND	Chlorobenzene	0.5	ND
1,1-Dichloroethane	0.5	2.2	Ethylbenzene	0.5	ND
Chloroform	0.5	ND	M+P-Xylene	0.5	ND
1,2-Dichloroethane	0.5	ND	O-Xylene	0.5	ND
Iodomethane	0.5	ND	Styrene	0.5	ND
Dibromochloromethane	0.5	ND	Bromoform	0.5	ND
1,1,1-Trichloroethane	0.5	ND	1,1,2,2-Tetrachloroethane	0.5	ND
Carbon Tetrachloride	0.5	ND	1,3-Dichlorobenzene	0.5	ND
Benzene	0.5	ND	1,4-Dichlorobenzene	0.5	ND
Trichloroethene	0.5	ND	1,2-Dichlorobenzene	0.5	ND
1,2-Dichloropropane	0.5	ND			


ppb = parts per billion = ug/L = micrograms per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit

Surrogate Recoveries -	1,2-Dichloroethane-d4	108%
	Toluene-d8	105%
	4-Bromofluorobenzene	99%

ANALYTICAL PROCEDURES

Organic Volatiles are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass spectrometer.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**

500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784



QA/QC REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 09-09-97
Matrix: Water

Project : WPC Alameda

	Benzene	Toluene	Ethyl- benzene	Total Xylenes
	<u>PPB</u>	<u>PPB</u>	<u>PPB</u>	<u>PPB</u>
Reporting Limit:	0.5	0.5	0.5	0.5

QA/QC PARAMETER

Matrix Blank	ND	ND	ND	ND
--------------	----	----	----	----

PERCENT RECOVERIES


Matrix Spike	86%	88%	89%	89%
Matrix Spike Duplicate	90%	91%	92%	93%

ppb = parts per billion = ug/L = microgram per liter
ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

All surrogate recoveries were within 30% of target values.
Spikes & Spike Duplicates were each spiked with 250 ng BTEX standard.

ANALYTICAL PROCEDURES


BTEX-- Benzene, toluene, ethylbenzene, and total xylene isomers (BTEX) are measured by extraction using EPA Method 5030 followed by analysis using EPA Method 602 which utilizes a gas chromatograph (GC) equipped with a photoionization detector (PID) .


Laboratory Representative

09-18-97
Date Reported

**EXCELICHEM
ENVIRONMENTAL LABS**

500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784



QA/QC REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 09-17-97
Matrix: Water

Project : WPC Alameda

	TPHd
	PPB
Reporting Limit:	50

QA/QC PARAMETER

Matrix Blank	ND
--------------	----

PERCENT RECOVERIES

Laboratory Control Spike	62%
--------------------------	-----

Laboratory Control Spike Duplicate	56%
------------------------------------	-----


ppb = parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.

Spikes & Spike Duplicates were each spiked with 5000 ug of diesel standard.

ANALYTICAL PROCEDURES

TPHd--Total petroleum hydrocarbons as diesel (high boiling points) are measured by extraction using EPA Method 3510, followed by modified EPA Method 8015 with direct sample injection into a GC equipped with an FID.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**

500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784



QA/QC REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 09-09-97
Matrix: Water

Project : WPC Alameda


<u>Compound</u>	<u>Matrix Spike % Recovery</u>	<u>Matrix Spike Duplicate % Recovery</u>
1,1-Dichloroethene	94%	96%
Benzene	94%	98%
Trichloroethene	96%	104%
Toluene	99%	104%
Chlorobenzene	101%	105%

ppb = parts per billion = ug/L = microgram per liter.

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.


ANALYTICAL PROCEDURES

Organic Volatile are measured using EPA Method 624 which utilizes a purge and trap interfaced to a gas chromatograph (GC) equipped with a mass selective detector.


Laboratory Representative

09-18-97
Date Reported

**EXCELCHEM
ENVIRONMENTAL LABS**



500 Giuseppe Court, Suite 9
Roseville, CA 95678
Phone#: (916) 773-3664 Fax#: (916) 773-4784

QA/QC REPORT

Attention: Mr. Brennan Mahoney
West & Associates
490 Merchant St, Ste 104
Vacaville, CA 95688

Date Analyzed: 09-11-97
Matrix: Water

Project : WPC Alameda

MS/MSD RECOVERIES

Unit = ug/L

Element	Sample Conc.	Spike Conc.	MS	MS% Recovery	MSD	MSD% Recovery	RPD	QC Limits	
								RPD	% REC
Phenol	ND	200	50	25%	59	29%	17%	42	12-110
2-Chlorophenol	ND	200	71	35%	90	45%	24%	40	27-123
1,4-Dichlorobenzene	ND	100	45	45%	44	44%	1%	28	36-97
N-Nitroso-di-n-propylamine	ND	100	83	83%	91	91%	10%	38	41-116
1,2,4-Trichlorobenzene	ND	100	51	51%	53	53%	4%	28	39-98
4-Chloro-3-Methylphenol	ND	200	94	47%	111	56%	16%	42	23-97
Acenaphthene	ND	100	76	76%	82	82%	8%	31	46-118
4-Nitrophenol	ND	200	69	34%	78	39%	12%	50	10-80
2,4-Dinitrotoluene	ND	100	87	87%	89	89%	2%	38	24-94
Pentachlorophenol	ND	200	120	60%	126	63%	5%	50	9-103
Pyrene	ND	100	80	79%	77	77%	3%	31	26-127

ppb = parts per billion = ug/L = microgram per liter

ND = Not detected. Compound(s) may be present at concentrations below the reporting limit.


Laboratory Representative

09-18-97
Date Reported