Ross7 Clasen CHAIHIL TRANSMITTAL Regional Water FROM ΑΠΝ DATE RE WE ARE SENDING YOU ☐ ATTACHED ☐ UNDER SEPARATE COVER VIA \_ DOCUMENTS ☐ SHOP DRAWINGS ☐ TRACINGS PRINTS ☐ SPECIFICATIONS ☐ CATALOGS COPY OF LETTER DESCRIPTION QUANTITY IF MATERIAL RECEIVED IS NOT AS LISTED, PLEASE NOTIFY US AT ONCE REMARKS \_\_ COPY TO \_

**REV 1/87 FORM 6** 

MONITORING WELL INSTALLATION AND SAMPLING

LONGVIEW FIBRE COMPANY OAKLAND, CALIFORNIA FACILITY

FOR
LONGVIEW FIBRE COMPANY
P.O. BOX 639
LONGVIEW, WASHINGTON 98632

Prepared by: CH2M HILL OF CALIFORNIA, INC.

JULY 1988



July 29, 1988

SF024103.B1

Mr. David N. Mendenhall Water Quality Engineer Longview Fibre Company P.O. Box 639 Longview, Washington 98632

Dear David:

Enclosed is a copy of our report entitled, "Monitoring Well Installation and Sampling, Longview Fibre Company, Oakland, California, Facility." A copy of this report has been sent directly to Worth Cornelius in Oakland and to the Regional Water Quality Control Board.

Should you have any questions regarding this report, please contact either Jack Payne at (503) 224-9190 or me at (415) 652-2426.

Sincerely,

Deanne Fischer, P.E.

Project Manager

Enclosure

CC: Worth Cornelius, Longview Fibre Co., Oakland Facility Jack Payne, CH2M HILL/PDX Greg Zentner, California Regional Water Quality Control Board, San Francisco Bay Region

#### CONTENTS

Introduction

Background Gasoline Tank Diesel Tanks

Field Methods

Equipment Decontamination and Waste Storage Sample Preservation and Chain-of-Custody Procedures Monitoring Well Installation and Development Soil Sampling Groundwater Sampling

Results of Investigation

Conclusions and Recommendations

References

Appendix: Well Permit, Well Log, Chain-of-custody Forms, Laboratory Reports

#### INTRODUCTION

Following the removal of four underground fuel storage tanks from the Longview Fibre Company's Oakland facility, CH2M HILL recommended that a groundwater monitoring well be installed and soil and water samples be collected in accordance with guidelines issued by the California Regional Water Quality Control Board (RWQCB). A description of the field activities and a discussion of the results of the groundwater investigation are presented in this report. CH2M HILL's February 1988 report entitled "Report on the Removal of Underground Storage Tanks and Sump Closure, Longview Fibre Company, Oakland, California Facility" contains details of the underground storage tank removal and associated soil sampling.

## BACKGROUND

The Longview Fibre Company has operated a cardboard box manufacturing facility at 8511 Blaine Avenue in Oakland, California since the early 1950s. (See Figure 1, Site Location). Four underground fuel storage tanks were installed at the facility to provide reserve diesel fuel for the plant's boilers and to supply gasoline fuel to the emergency fire protection water pump. The three diesel tanks were located beneath the courtyard at the north side of the plant and the gasoline tank was located on the Western Pacific Property on the south side of the facility. Figure 2, Site Plan, shows the general plant layout and the locations of the four underground tanks.

Longview Fibre initiated a national underground tank program in the spring of 1987 with the goal of eliminating potential future environmental problems by removing and disposing of their single-walled underground storage tanks. CH2M HILL was retained to provide engineering services for the removal and disposal of the four underground tanks at the Longview Fibre Oakland facility. All four tanks were removed in accordance with state and local regulatory requirements. CH2M HILL obtained the necessary permits from the Oakland Fire Department and submitted a closure plan to the Alameda County Department of Environmental Health.

#### GASOLINE TANK

The gasoline tank had been installed in a sandy backfill within a bottomless concrete vault. After removal of the tank, two soil samples were collected from the backfill/native soil interface at the bottom of the vault and were analyzed for total petroleum hydrocarbons-gasoline (TPH-gasoline). Both samples contained concentrations of less

than 5 parts per million (ppm) of TPH-gasoline. No ground-water was encountered during the removal of the gasoline tank. The vault was backfilled using the excavated material and clean sand (CH2M HILL, 1988).

#### DIESEL TANKS

The three diesel storage tanks had been placed in a sandy backfill. At the time of excavation, the three tanks were sitting in groundwater, which was encountered at approximately 9 feet below the ground surface. After removing the tanks, samples were collected from the water in the excavation, and soil samples were taken from the walls of the pit immediately above the groundwater level. Groundwater present in the excavation during the tank removal had an oily sheen.

Analytical results of the initial soil sampling indicated that total petroleum fuel hydrocarbons-diesel (TPH-diesel) concentrations exceeded 1000 ppm in the southeastern and southwestern margins of the excavation. In accordance with RWQCB regulations, these areas were further excavated until soil samples with TPH-diesel concentrations less than 1,000 ppm had been obtained. Analytical results of the grab samples of groundwater from the excavation contained TPH-diesel concentrations ranging from 170 ppm to 160,000 ppm (CH2M HILL, 1988).

CH2M HILL developed a remedial action plan and submitted it to the Alameda County Department of Environmental Health. The plan called for the installation of a down-gradient monitoring well and the collection of groundwater samples for volatile organic aromatics (EPA Method 602) and soil samples for TPH-diesel (CH2M HILL, 1988).

#### FIELD METHODS

The site investigation included the following field activities:

- o Installation of one shallow monitoring well
- o Collection of one soil sample from the borehole drilled during monitoring well construction and one sample of the drill cuttings
- Measurement of fuel product thickness in the well and the collection of one groundwater sample after purging the well

The methods followed are described in the following paragraphs.

# EQUIPMENT DECONTAMINATION AND WASTE STORAGE

Prior to sampling, the brass sleeves and plastic end caps (for soil sampling), and teflon bailer and associated teflon spigot (for water sampling) were washed with a detergent and water solution, rinsed in tap water, rinsed with distilled water, spray-rinsed with isopropanol, and spray-rinsed with distilled, deionized water (laboratory-grade water). The split-spoon sampler and trowel (for soil sampling), the clear bailer and steel tape (for groundwater measurements), and the bailer and suction hose (for well development) were washed with the detergent and water solution and rinsed in tap water.

Drill cuttings were placed in a barrel next to the well, which was secured with a lid and bolt ring when drilling was concluded. On May 9, a grab sample of the drill cuttings was collected by removing the upper 6 inches of material in the barrel with a trowel and pushing a 6-inch brass sleeve into the cuttings. This sample was labelled, documented, preserved, and analyzed following procedures identical to those used for the soil sampling that are discussed below.

The total of 120 gallons of water produced during well development was stored next to the well in barrels with secured bolt rings and lids. All groundwater that was discarded during sampling was also poured into these barrels.

# SAMPLE PRESERVATION AND CHAIN-OF-CUSTODY PROCEDURES

Once filled, sample containers for both soil and water were labelled, sealed in a zip lock plastic bags, secured with custody seals, and placed in an ice-filled cooler. Chain-of-custody forms were generated for each shipment of samples, enclosed in zip lock plastic bags, and packed inside the cooler with the samples. Copies of the chain-of-custody forms are included in the appendix. Custody seals were affixed to the front and rear of the cooler's lid before shipment to the laboratory via an air courier service.

#### MONITORING WELL INSTALLATION AND DEVELOPMENT

The shallow monitoring well is located approximately 5 feet south of an aboveground starch tank (Figure 2, Site Plan). In accordance with guidelines issued by the San Francisco Bay Region of the California Regional Water Quality Control Board (RWQCB, 1985), the location was selected in order to place the monitoring well boring: 1) within the limits of the original tank excavation, 2) within 10 feet of Tank T-3, which was found to have numerous holes, 3) in an area where contaminated soils had been removed, and 4) in the inferred downgradient direction from the site of the excavated tanks. Shallow groundwater beneath the site probably flows in a

westerly direction toward a drainage channel located approximately 500 feet west of the Longview Fibre property (Figure 1).

CH2M HILL developed well construction specifications following RWQCB guidelines and retained Bayland Drilling of Foster City, California to drill and install the monitoring well. CH2M HILL then obtained a Groundwater Protection Ordinance Permit (number 88153) from the Alameda County Flood Control and Water Conservation District (copy included in the appendix).

Prior to drilling, a 14-inch diameter hole was cored through the existing reinforced concrete parking lot pavement at a point about 1} feet from the southern corner of the starch tank foundation. The monitoring well borehole was drilled on May 2, 1988, by Bayland Drilling using a CME 55 drilling rig with 3-3/4-inch I.D. x 8-inch O.D. hollow-stem augers. Geologic logging of the borehole was done by a CH2M HILL hydrogeologist. A copy of the DWR Water Well Driller's Report is included in the appendix. Subsurface materials consist of sand backfill from the recent excavation work from about 1 to 4 feet bgs and gray to yellow-brown silty clay from 4 to 27 feet bgs. Small (1-millimeter diameter) worm borings were evident in a soil sample collected at 8-1/2 to 10 feet bgs. Relatively soft materials were encountered at about 21 feet bgs. Groundwater was first encountered at a depth of approximately 8 feet below the ground surface (bgs).

Monitoring well installation was also completed on May 2. See Figure 3, Monitoring Well Construction Details, and the DWR Water Well Driller's Report in the appendix for details. 5 feet of 2-inch diameter blank schedule 40 PVC casing and 20 feet of 2-inch diameter schedule 40 PVC screen with 0.010-inch slots plus a bottom cap were placed inside the hollow auger stem. The blank casing extended from 3 inches below the ground surface (bgs) to 5.25 feet bgs, and the screen extended from 5.25 to 25.25 feet bgs. Clean sand (12 x 20 sieve size) was slowly poured down the annulus between the well casing and auger stem as the augers were removed from the hole. The elevation of the sand pack was continually sounded as the sand was being added. Bentonite pellets were then added above the sand pack from 2.5 to 3.75 feet bgs. An upper grout seal of neat cement and bentonite was placed from 8 inches to 2.5 feet bgs. surface completion of the well is a concrete traffic box set in cement with a steel lid. The top of the traffic box protrudes approximately 11 inches above the existing concrete pavement ("ground surface") to promote drainage. A locking, watertight well cap and lock were placed on the top of the PVC casing upon completion of the well.

The monitoring well was developed using both a bailer and a hand pump. On May 2, an initial 20 gallons of water were bailed from the well about 4 hours after its installation. On May 4, an additional 100 gallons were pumped from the well with a hand-operated suction pump. The well was pumped dry five times. The total of 120 gallons of development water was stored next to the well in barrels with secured bolt rings and lids. The suction hose was stored on site in a plastic bag for use in purging the well before sampling.

#### SOIL SAMPLING

While drilling the monitoring well borehole on May 2, one soil sample was collected from a depth of 8½ to 10 feet bgs, which was near the bottom of the former fuel tank and slightly above the anticipated water table. The sample was collected using a 2.5-inch diameter, 18-inch long Modified California Split-Spoon sampler and three 6-inch long brass liner sleeves. The upper two of the three sleeves were saved and composited for analysis for total petroleum fuel hydrocarbons-diesel (TPH-diesel). The lowermost sleeve was used to develop a description of the subsurface lithology.

Upon removal of the brass sleeves from the split-spoon sampler, each end of the two sleeves to be retained for analysis were covered with teflon tape followed by a polyethylene plastic cap. The caps were secured by wrapping them with electrical tape. The sleeves were then labelled, sealed in a zip lock plastic bag, secured with custody seals, and placed in an ice-filled cooler which was also secured with custody seals.

The soil sample was analyzed for TPH-diesel in accordance with guidelines issued by the RWQCB. Analytical services were provided by the CH2M HILL laboratory in Redding, California, which is a State of California certified laboratory facility.

#### GROUNDWATER SAMPLING

Before collecting a groundwater sample on May 9, measurements were made of the water elevation and free floating petroleum product thickness in the monitoring well. The water elevation was measured with a steel tape graduated to 0.01 inches, and the product thickness was gauged with a clear acrylic bailer. After purging the well, a water sample was collected with a teflon bailer for analysis for volatile organic aromatics (EPA Method 602).

Standing water was purged from the well by using a handpowered suction pump along with the plastic hose saved from the well development. Approximately 17 gallons were removed from the well before it went dry. (One well casing volume for a 2-inch diameter well with 17 feet of standing water is about 2.8 gallons). Once the well recovered, two bailers full of water were removed from the well with the teflon bailer and were discarded through the bailer's sampling spigot. Three 40 milliliter VOA sample bottles were filled from the third bailer full of water. The sample bottles were filled only after discarding the initial few milliliters of water that first flowed when the spigot was opened, and the bottles were carefully filled to prevent any air bubbles from remaining in the container after sealing. All discarded groundwater was poured into the barrels containing well development water.

The water sample was analyzed for volatile organic aromatics in accordance with EPA Method 602 and guidelines issued by the RWQCB (RWQCB, 1985). Analytical services for the water samples were also provided by the CH2M HILL laboratory in Redding, California.

## RESULTS OF INVESTIGATION

Subsurface materials at the monitoring well site consist of new sand backfill from about 1 to 4 feet bgs and gray to yellow-brown silty clay from 4 to 27 feet bgs. Small (1-millimeter diameter) worm borings were observed in the soil sample from 8½ to 10 feet bgs.

The water level in the monitoring well on May 9 at 8:50 a.m. was 7.97 feet below the top of the casing, or 8.22 feet below ground surface (the concrete pavement). No free fuel product was observed on the surface of water standing in the well, judging from a sample collected with the clear bailer. Analysis of the soil sample from a depth 8½ to 9½ feet in the monitoring well boring contained no detectable amounts of diesel fuel (detection limit 1 milligram/kilogram), but the drill cuttings sample contained 7 milligrams per kilogram (mg/kg) of diesel fuel. The groundwater sample collected on May 9 contained no detectable amounts of benzene, toluene, xylene, ethyl benzene, chlorobenzene, or dichlorobenzene isomers (detection limit 1 microgram/liter). The laboratory reports are included in the appendix.


#### CONCLUSIONS AND RECOMMENDATIONS


Results of the soil sampling and groundwater sampling indicate that there are no detectable concentrations of volatile organic aromatics in the groundwater in the immediate vicinity of the former diesel storage tanks and less than 10 ppm of diesel fuel hydrocarbons in the soils obtained from the monitoring well boring. Additional groundwater sampling to confirm the above results is recommended. SFR155/005


#### REFERENCES

California Regional Water Quality Control Board (RWQCB), San Francisco Bay Region, 1985. Guidelines for Addressing Fuel Leaks, September.

CH2M HILL, 1988. Report on the Removal of Underground Storage Tanks and Sump Closure, Longview Fibre Company, Oakland, California Facility. Unpublished report prepared for Longview Fibre, February.







NOT TO SCALE

FIGURE 3 (MW~1)
LONGVIEW FIBRE COMPANY
MONITORING WELL CONSTRUCTION
DETAILS



# ALAMEDA COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT

5997 PARKSIDE DRIVE

PLEASANTON, CALIFORNIA 94566

(415) 484-2600

GROUNDWATER PROTECTION ORDINANCE PERMIT APPLICATION

	FOR APPLICANT TO COMPLETE
(1)	R511 Blaine Avenue (cross street 85th) Dakland, CA 94621 (415) 569-2616
2)	CLIENT Name Lungview Fibre Co. Address P.O. Box 639 Phone (206) 425-1550 City Lungview WA ZIP 98632
(3)	APPLICANT Name CHZM HILL (ONTacts ) eff Hey re  Ste. 500 Address 6425 Christie Ave Phone (415) 652-2426 City Emeriville, CA ZIP 94608
	DESCRIPTION OF PROJECT Water Weil Construction
(5)	PROPOSED WATER WELL USE  Domestic industrial Irrigation  Municipal Monitoring X Other
(6)	PROPOSED CONSTRUCTION  Drilling Method:  Mud Rotary Air Rotary Auger X  Cable Other
	WELL PROJECTS  Drill Hole Diameter 8 in. Depth 25-30ft.  Casing Diameter 2 in. Number WW- ( Surface Seal Depth 3-8 ft. Total 1  Driller's License No. 374152  Bayland Drilling
	GEOTECHNICAL PROJECTS  Number  Diameter In. Maximum Depth ft.
(7)	ESTIMATED STARTING DATE 05/02/88 ESTIMATED COMPLETION DATE 05/02/88
	hereby agree to comply with all requirements of

IF OR	OFF	I CE	HCE

PERMIT NUMBER	88153
OCATION NUMBE	R

Approved Wyman Hong Date 25 Apr 88

#### PERMIT CONDITIONS

Circled Permit Requirements Apply

- A) GENERAL
  - A permit application should be submitted so as to arrive at the Zone 7 office five days prior to proposed starting date.
  - Notify this office (484-2500) at least one day prior to starting work on permitted work and before placing well seals.
  - 3. Submit to Zone 7 within 60 days after completion of permitted work the original Department of Water Resources Water Well Drillers Report or equivalent for well projects, or bore hole logs and location sketch for geotechnical projects. Permitted work is completed when the last surface seal is placed or the last boring is completed.
  - 4. Permit is void if project not begun within 90 days of approval date.
- B) WATER WELLS, INCLUDING PIEZOMETERS
  - Minimum surface seal thickness is two inches of cement grout placed by tremie, or equivalent.
  - Minimum seal depth is 50 feet for municipal and industrial wells or 20 feet for domestic, Irrigation, and monitoring wells unless a lesser depth is specially approved.
- C. GEOTECHNICAL. Backfill bore hole with compacted cuttings or heavy bentonite and upper two feet with compacted material.
- D. CATHODIC. Fill hole above anode zone with concrete placed by tremie, or equivalent.
- E. WELL DESTRUCTION. See attached.

APPLICANT'S A CONTENT Date 04/70/88

this permit and Alameda County Ordinance No. 73-68.

# CONFIDENTIAL

STATE OF CALIFORNIA DWR WELL COMPLETION REPORT (WELL LOGS)

**REMOVED** 

SAMPLED BY AND THE (SIGNATURE)  SAMPLED BY AND THE (SIGNATURE)  AND DATE TIME  SAMPLED BY AND THE (SIGNATURE)  DATE TIME  SAMPLED BY AND THE SIGNATURE)  SAMPLED BY AND THE SIGNATURE  SAMPLED BY AND THE SIGNATURE	CHA	MHILL	CHA	VN	OF (	CUSTO	DY RECORD			· ;										<i>i</i>	ر
CLENN MANE DEPORT TO: THE COLD IS SCOPY TO:  REQUESTED COMPLETON DATE  ILEGORATORY,  STA  NO  DATE FINANCE  SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME  SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME  DATE/TIME  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  T  ARC  VERIFIED  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  ARC  RECENTED BY: (SIGNATURE)  DATE/TIME  ARE BUS BILL NUMBER	PROJECT NUMBER PROJECT NAME					1	ANALYSES REQUESTED										OR LAB USE ON	LY			
CLENN MANE DEPORT TO: THE COLD IS SCOPY TO:  REQUESTED COMPLETON DATE  ILEGORATORY,  STA  NO  DATE FINANCE  SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME  SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME  DATE/TIME  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  T  ARC  VERIFIED  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECENTED BY: (SIGNATURE)  DATE/TIME  ARC  RECENTED BY: (SIGNATURE)  DATE/TIME  ARE BUS BILL NUMBER	5FC	,2410	3.BI	L	000	grien	itibre-61	oundwest	٠,	Τ	<u> </u>	T			1		TT		110.0	<del></del>	
RECURSIDE COMPLETION DATE  LABORATORY,  STA  NO  DATE  STA  STA  STA  STA  STA  STA  STA	CUENT NAME:						1	-	Į.,				- {						······································		
SAMPLED BY AND ITILE (SIGNATURE)  DATE/TIME  DATE/TIME  TECHNOLIS  SAMPLE SHIPPED VIA  AR BUS BILL NUMBER	REPORT	10: n	~ 11	<u> </u>	<del>7  </del> -	1016	COPY TO:	<del></del>	- 8	36				Ì	l						
SAMPLED BY AND ITILE (SIGNATURE)  DATE/TIME  DATE/TIME  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  A SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)					10			<del></del>	_  ₹	0	} :		{ }		- [			- { <b>!</b>			
SAMPLED BY AND ITILE (SIGNATURE)  DATE/TIME  DATE/TIME  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  A SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)  SAMPLED BY: (SIGNATURE)  DATE/TIME  SAMPLED BY: (SIGNATURE)	REQUES	TED COMP	LETION D	Ate			LABORATORY,	161	9	1											
SAMPLED BY AND ITILE (SIGNATURE)  DATE/TIME  DATE/TIME  TECHNOLIS  SAMPLE SHIPPED VIA  AR BUS BILL NUMBER	<b></b> -	<i>i</i>		<u>_</u>	_		1.00.	<del>]</del>	-   š		<b>-&gt;</b>	4									
SAMPLES BY AND ITTLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME SIZE SELECTION OF CONTROL O		DATE	TIME	8	<b>8</b>	Š	SAMPLE DESCR	IPTION	ŠŠ					ļ				1 1	Dist Osilioi		DATE
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME  RELINGUISHED BY (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  A  RECEIVED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  A  RECEIVED BY: (SIGNATURE)  DATE/TIME  RECEIVED BY: (SIGNATURE)  DATE/TIME  A  RECEIVED BY: (SIGNATURE)  SAMPLING PROGRAM  SAMPLE SHIPPED VIA  AIR BUS BILL NUMBER		<del>    </del>		<del></del>		<del>  `                                   </del>			1/2	X							1-1	_	1		1.46
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER	<sup> </sup>	71210	11.50	}-		LVI	000- 00	JUNITUM	746	+	•	+-		-			+		wintes	<u> 121 an</u>	41. A. 21. 2
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER	}			╂—-	<u> </u>	<u></u>			- -	+-	-	-	$\vdash$				-}}-				
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER				<del> </del>	<del> </del>					-	┼	-	-				++				
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER				<u> </u>	<u> </u>					-	<u> </u>	-									
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER				<u> </u>	<u> </u>	ļ				$\perp$	<u> </u>	<u> </u>					1_1				<del></del>
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER	<u> </u>			<u> </u>						1_	L										<del></del>
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER					}		•														
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER								<del></del>	1												
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER							·	<del></del>	1	1-	_	1	1-1						<del></del>	. <del> </del>	
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER		<del> </del>		-	<del> </del>				+	<del> </del>	-	+	<del>                                     </del>			_	+-+				<del></del>
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER		ļi		<del>  -</del>	<del> </del>	<del> </del>				+-	<del> </del> -	-	+-+				+-+				
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RELINQUISHED BY (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER		<u> </u>	<del></del>	-	<u> </u>	<u> </u>		·····		┼-	<del></del>	-					+				
SAMPLED BY AND TITLE (SIGNATURE)  DATE/TIME RECEIVED BY: (SIGNATURE)  DATE/TIME  SAMPLE SHIPPED VIA AIR BUS BILL NUMBER		<del> </del>	<u> </u>		<del> </del>	<del> </del>				+-	-	-	<del>                                     </del>				+-+				
1 ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) (	ļ		<u> </u>	<del> </del>	<del> </del>	<del> </del>				<del> </del>	_		1_1								
1 ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) (	<u> </u>			<u> </u>							1_	<del> </del>					1-1-				
1 ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) (	ļ	<u> </u>				<u> </u>		<del></del>									1,1				2
RELINQUISHED BY: (SIGNATURE) DATE/TIME RECEIVED BY: (SIGNATURE) DATE/TIME RELINQUISHED BY: (SIGNATURE) DATE/TIME RECEIVED BY LAB: (SIGNATURE) DATE/TIME  4 5 6 7  SAMPLING PROGRAM SAMPLE SHIPPED VIA AIR BUS BILL NUMBER						(SIGN	ATURE	)				DAI	IE/TIME	i	` '						
4 5 6 7  SAMPLING PROGRAM SAMPLE SHIPPED VIA AIR BUS BILL NUMBER						~ ~															
SAMPLING PROGRAM SAMPLE SHIPPED VIA AIR BUS BILL NUMBER							DATE/T	ATE/TIME RELINQUISHED BY: (SIGNATURE			ATURE)				(LAB: (SIGNATURE)	DATE/TIME					
DEMADVC 1	4 5						<del></del>						<u></u>								
L BUMA NEDER KOLKA OMINA LILLUTO LLIBUR KSLEDICA L / / / - 7 (/ / / / / /	REMARKS						Unner none Dune Da														
GPECIFY)   HAND OTHER   67 / 109   50	T I																				

CHAIN OF CUSTODY RECORD PROJECT NUMBER PROJECT NAME FOR LAB USE ONLY **ANALYSES REQUESTED** SFO,24103, BILLonguren Fibre-Oakland PROJ # \_\_\_\_\_ REPORT TO: COPY TO: Jeff Healie 1SFO ACK \_\_\_\_\_\_VERIFIED \_\_\_\_\_ REQUESTED COMPLETION DATE LABORATORY DATE INVOICED \_\_\_\_\_ Redding NO. OF SAMPLES \_\_\_\_\_ pg \_\_\_\_ of \_ DISPOSITION: D R \_\_\_\_\_ STA NO DATE TIME SAMPLE DESCRIPTION LVF-GW-GW-O1 Groundwater 3) Extra spare included 6W-01 0509 0920 1998 55-020569 0945 LVF-GW-SS-BZC Cuttings 1995 SAMPLED BY AND TITLE (SIGNATURE) DATE/TIME RELINQUISHED BY (SIGNATURE) RECEIVED BY: (SIGNATURE) DATE/TIME DATE/TIME RELINQUISHED BY: (SIGNATURE) RECEIVED BY: (SIGNATURE) DATE/TIME DATE/TIME **REUNQUISHED BY: (SIGNATURE)** RECEIVED BY LAB: (SIGNATURE) DATE/TIME DATE/TIME 5 6 SAMPLING PROGRAM SAMPLE SHIPPED VIA AIR BUS BILL NUMBER REMARKS \_ ☐ UPS ☐ BUS ☐ FED-EX **SDWA NPDES RCRA** 6479041310 OTHER . HAND OTHER \_\_\_

П

(SPECIFY)

REPORT TO: LONGVIEW - FIBER

CH2M HILL/SFO

F24103.B1

ATTENTION: JEFF HEGLIE

SAMPLE DESCRIPTION: SDIL-LVF-GW-SS-01-

COMPOSITE

DATE OF SAMPLE: 5-2-88

REFERENCE NUMBER: 19942

PAGE 1 OF 1 DATE: 5-20-88

PHONE:

SAMPLED BY: J. HEGLIE DATE RECEIVED: 5-3-88

TOTAL FUEL **HYDROCARBONS** (DIESEL)

TEST UNITS

mg/kg

RESULT

<1

COMMENTS: mg/kg = milligrams per kilogram

The information shown on this sheet is test data only and no analysis or interpretation is intended or implied.

APPROVED BY: Alaulay

REPORT TO: LONGVIEW FIBER - DAKLAND

CH2M HILL/SFO

SF024103.B1

ATTENTION: JEFF HEGLIE

SAMPLE DESCRIPTION: LVF-GW

DATE OF SAMPLE: 5-9-88

REFERENCE NUMBER: 20005

PAGE 1 OF 1

DATE: 6-10-88

PHONE:

SAMPLED BY: J. HEGLIE DATE RECEIVED: 5-10-88

TEST METHODS: EPA-602-8020

CONSTITUENT	GW-01 WATER	SS-OZC SDIL	بالله الله الله الله الله الله الله الله
Benzene	<1.0		
Toluene	<1.0	-	
Ethyl benzene	<1.0		
Xylene	<1.0		
Chlorobenzene	<1.0		
1,4-Dichlorobenzene	<1.0	<del></del>	
1,3-Dichlorobenzene	<1.0		
1,2-Dichlorobenzene	<1.0	***	
Total Fuel Hydrocarbons	~	7	
(Diesel)			

COMMENTS: Results are in micrograms per liter.

The information shown on this sheet is test data only and no interpretation is intended or implied.

ANALYST: Buan Gloss

APPROVED