

April 7, 1994

IT Project No. 151933

Mr. Scott Seery Alameda County Department of Environmental Health 80 Swan Way, Room 350 Oakland, California 94621

SUBJECT: 2610 NORBRIDGE AV, CASTRO VALEY, CALIFORNIA

Dear Mr. Seery:

On behalf of Pacific Bell, IT Corporation is pleased to present the results of the Preliminary Site Investigation at 2610 Norbridge Avenue, Castro Valley, California. If you have any questions regarding the material presented in this report, please feel free to contact me at your convenience.

Respectully, IT CORPORATION

Michael D. Miller, REA Senior Project Geologist

cc: Ms. Irene Soto, Pacific Bell



PRELIMINARY SITE INVESTIGATION PACIFIC BELL FACILITY 2610 NORBRIDGE AVENUE CASTRO VALLEY, CALIFORNIA

PREPARED FOR:

PACIFIC BELL 2600 CAMINO RAMON ROOM - 3E400Q SAN RAMON, CALIFORNIA

PREPARED BY:

IT CORPORATION 2055 JUNCTION AVENUE SAN JOSE, CALIFORNIA 95131

IT PROJECT NO. 151933

MARCH 1994

Regional Office 2055 Junction Avenue • San Jose, California 95131-2105 • 408-894-1200 • FAX: 408-894-0701

PRELIMINARY SITE INVESTIGATION PACIFIC BELL FACILITY 2610 NORBRIDGE AVENUE CASTRO VALLEY, CALIFORNIA

PREPARED FOR:

PACIFIC BELL 2600 CAMINO RAMON ROOM - 3E400Q SAN RAMON, CALIFORNIA

PREPARED BY:

IT CORPORATION 2055 JUNCTION AVENUE SAN JOSE, CALIFORNIA 95131

IT PROJECT NO. 151933

MARCH 1994

Michael D. Miller Senior Project Geologist

Matthew A. Hopwood

California Registered Geologist No. 5881

TABLE OF CONTENTS

			Page
List of	Tables	List of Figures	iii
1.0	INTR(ODUCTION	
2.0	OBJE	CTIVE AND SCOPE OF WORK	. 2
3.0	3.1 3.2 3.3	NVESTIGATION Summary of Boring and Monitoring Well Installation Subsurface Conditions 3.2.1 Stratigraphy 3.2.2 Shallow Groundwater Groundwater Sample Collection	. 2 . 3 . 3
4.0	LABO 4.1 4.2	Analytical Program Analytical Results 4.2.1 Soil Samples 4.2.2 Groundwater Sample	. 4 . 4 . 4
5.0	SOIL	DISPOSAL	. 5
6.0	DISCU	USSION	. 5
7.0	CONC	CLUSIONS	. 5
8.0	REFE	RENCES	. 6
APPE)	NDIX ANDIX EB.1 B.2 B.3 B.4 B.5 NDIX CONDIX ED.1	SUMMARY OF DRILLING PROGRAM SOIL BORING/MONITORING WELL INSTALLATION PROCEDURES BORING LOGS WELL DEVELOPMENT LOGS WATER LEVEL MEASUREMENT AND SAMPLING PROCEDURES GROUNDWATER SAMPLE COLLECTION LOGS C: SOIL DISPOSAL D: LABORATORY ANALYSIS CHAIN OF CUSTODY	3
	D.2	LABORATORY REPORTS	

LIST OF TABLES

TABLE NO.	TITLE
1	MONITORING WELL CONSTRUCTION DATA
2	GROUNDWATER GRADIENT DATA
3	RESULTS OF LABORATORY ANALYSES OF SOIL SAMPLES
4	RESULTS OF LABORATORY ANALYSES OF GROUNDWATER SAMPLE

LIST OF FIGURES

FIGURE NO. TITLE

- 1 SITE LOCATION MAP
- 2 SITE PLAN WITH BORINGS AND MONITORING WELL LOCATIONS



PRELIMINARY SITE INVESTIGATION PACIFIC BELL FACILITY 2610 NORBRIDGE AVENUE CASTRO VALLEY, CALIFORNIA

1.0 INTRODUCTION

This report presents the results of the installation of one groundwater monitoring well and the completion of three soil borings, performed by IT Corporation (IT) at the 2610 Norbridge Avenue site in Castro Valley, California (Figure 1). This report addresses the issues presented in the letter dated September 27, 1993, from the Alameda County Environmental Health Department, regarding a preliminary site assessment. Field work was performed during February, 1994 in response to the request and authorization of Ms. Rose Cassens of Pacific Bell. This work has been performed as a follow-up to previous work conducted by IT regarding underground storage tank (UST) replacement at the site.

1.1 Background

The site is a Pacific Bell equipment storage and maintenance yard (Figure 2). One 10,000 gallon fiberglass unleaded gasoline UST was used at the site primarily to supply fuel for Pacific Bell vehicles. This fiberglass UST was replaced with a 10,000 gallon double-wall glasteel tank manufactured by Modern Welding (Fresno, California).

On May 4, 1993, Balch Petroleum, a Pacific Bell contractor, removed the UST. The removal was observed by Pacific Bell, IT, the Eden Consolidated Fire Protection District (ECFPD, Inspector Tony Rocha), and the Alameda County Department of Environmental Health (ACDEH, Mr. Amir Gholami).

IT collected and analyzed three soil samples (SOIL-1, SOIL-2, and SOIL-3) from the original excavation sidewalls, approximately 6 feet below ground surface (BGS). Total petroleum hydrocarbons as gasoline (TPH-G) and benzene, toluene, ethyl benzene, and xylenes (BTEX) were not detected within the northern (SOIL-1) and northeastern (SOIL-2) excavation corners. The southern sidewall sample (SOIL-3) contained 12 parts per million (ppm) TPH-G (Figure 2).

A second round of over-excavation was initiated to remove hydrocarbon impacted soil adjacent to the southwest corner of the excavation. This over-excavated area is shown in the attached Figure 2. Three verification samples (SOIL-8, SOIL-9, and SOIL-10) were collected from this over-excavated area. Detectable TPH-G or BTEX were not found in soil sample SOIL-10. Soil sample SOIL-8 collected just above the groundwater interface (7.5 feet BGS) contained 31 ppm TPH-G. BTEX concentrations up to 0.35 ppm ethyl benzene (SOIL-8) were found in soil samples SOIL-8 and SOIL-9 (IT Corporation, 1993). This data is shown on Figure 2.

A groundwater grab sample GRABWATER-1 was collected from standing water within the excavation following the tank removal. This sample contained 7,900 parts per billion (ppb) TPH-G and BTEX concentrations up to 110 ppb ethyl benzene and total xylenes. Approximately 2,300-gallons of standing water within the excavation was pumped out and disposed of at the PRC recycling facility in Patterson, California (IT Corporation, 1993).

2.0 OBJECTIVE AND SCOPE OF WORK

The objective of work presented in this report was to assess the presence and distribution of petroleum hydrocarbons in soil and shallow groundwater beneath the site.

The scope of work developed to meet the objective included the following:

- Workplan preparation;
- Field investigation;
 - Three shallow soil borings and one monitoring well,
 - Soil sample collection from all borings,
 - Groundwater sample collection from the monitoring well,
- Laboratory analysis of soil and groundwater samples; and
- Report preparation.

3.0 FIELD INVESTIGATION

The field investigation was conducted in general accordance with the workplan dated January 3, 1994 (IT Corporation, 1994). The permit to install the borings and monitoring well was obtained from the Zone 7 Water Agency. The workplan to conduct well installation at the site was prepared by IT Corporation (IT Corporation, 1994) on behalf of Pacific Bell and was approved by Mr. Scott Seery of the Alameda County Division of Environmental Health, Division of Hazardous Materials (ACDEH) prior to the issuance of the permit. A copy of the soil boring and well permit is presented in Appendix A.

The field investigation was conducted between February 2 and 15, 1994, and involved the drilling and sampling of four borings with subsequent construction of a monitoring well within one of the borings. Monitoring wells were to be constructed in all borings but three encountered bedrock material and drill rig refusal prior to encountering groundwater. Therefore, one groundwater monitoring well was installed (MW-1). A groundwater sample was collected from the completed well approximately six days after well development. Permits for the project are presented in Appendix A. A description of the procedures used during field work are presented in Appendix B.

3.1 Summary of Soil Borings and Monitoring Well Installation

Four soil borings (SB-1, SB-2, SB-3, and MW-1) were drilled on February 2, 1994, at the locations shown in Figure 2, using a truck-mounted drill rig equipped with ten-inch hollow-stem

augers. The locations of SB-1, SB-2, and SB-3 were selected to obtain soil and groundwater data from the upgradient and downgradient groundwater direction. The fourth boring/well was drilled in the overexcavated area immediately downgradient of the tank pit for monitoring and extraction if necessary. The boring converted to a monitoring well was drilled to a depth of approximately 16 feet below ground surface (BGS). Pea gravel backfill material was encountered to the bottom of the boring and no soil samples were collected. Boring SB-1 was advanced to approximately 30 feet BGS, and soil was sampled at 2.5-foot intervals. The other soil borings (SB-2 and SB-3) were advanced to approximately 16 and 17 feet BGS respectively, and soil samples were collected at five-foot intervals beginning at five feet BGS. Soil samples were collected using a California modified split-barrel sampler for observation of soil lithology, field measurement of organic vapors, and laboratory analyses. Soil samples were retained on ice in an insulated chest for delivery to the laboratory.

dwater
ell was
ng and
epth of
l was
-1 was
e other
tively,
amples

The monitoring well was constructed using four-inch inner diameter, schedule 40 polyvinyl chloride (PVC) well casing with 0.020-inch width machine-slotted screen; a slot size judged appropriate for the material encountered. The monitoring well was screened between 6.0 and 16.0 feet BGS. The monitoring well was completed with blank casing to within 0.5 foot of the ground surface. The annular space around the screened interval in the well was backfilled with No. 3 Lonestar sand filter pack and capped with an approximate six-inch thick zone of hydrated granular bentonite. Neat portland cement grout was placed in the annulus above the bentonite zone, with a well housing and locking device set at ground surface. The monitoring well was developed by pumping and bailing to remove the fine-grained materials from the wells and to increase the hydraulic communication between the formation and the filter pack.

Drilling services were provided by Kvilhaug Well Drilling of Concord, California. During the drilling operations, a summary of the subsurface conditions encountered was recorded on a boring log. General procedures used to drill and log the borings, collect soil samples, and install/develop/sample the well are summarized in Appendix B.1. Boring logs and well construction diagrams are presented in Appendix B.2. The monitoring well construction data is presented on Table 1. The well development log is presented in Appendix B.3.

3.2 Subsurface Conditions

3.2.1 Stratigraphy

Based on the data collected from the soil borings, an assessment of the shallow stratigraphy of the site was performed. A tan, highly sheared, claystone bedrock material underlies the surface of the site from approximately 15 to 30 feet BGS. The bedrock unit was observed to be very hard and dry. The upper surface of this unit is irregular and is overlain by a thin veneer of fine-grained sedimentary cover of silt and clay which varies in thickness.

No hydrocarbon odors were noted in any of the borings. Volatile organic compounds (VOCs) were not detected by the organic vapor meter while drilling. No stained soil cuttings or samples were observed during drilling.

3.2.2 Shallow Groundwater

In borings SB-1, SB-2, and SB-3, groundwater was not encountered during drilling. Standing water was observed within the tank pit bottom during the UST removal in May 1993. Depth to water within the tank pit was 7.5 feet BGS. Water was again encountered in the UST pit during drilling of MW-1. Prior to groundwater sample collection, one week following well installation, the depth to groundwater in MW-1 was measured at 5.2 feet below the top of the casing (Table 2).

3.3 Groundwater Sample Collection

A groundwater sample was collected from monitoring well MW-1 on February 15, 1994 after purging approximately 3 casing volumes of water. The groundwater sample was collected using a disposable bailer in general accordance with the procedures presented in Appendix B.4. The groundwater sample collection log is presented in Appendix B.5. The groundwater sample was placed into laboratory-supplied containers and retained on ice in an insulated chest for delivery to the laboratory on February 15, 1994.

4.0 LABORATORY ANALYSIS

Soil and groundwater samples were submitted to Superior Precision Analytical, Inc. of San Francisco, California, a State-certified hazardous waste laboratory. Chain of custody forms and laboratory reports are presented in Appendix D.

4.1 Analytical Program

The analytical program developed by IT Corporation was based on data obtained from the previous investigation. Selected soil and groundwater samples were analyzed for TPH-G and BTEX. In addition, one soil sample collected from the stockpile was analyzed for soluble lead by Method 6010. The analyses were performed in general accordance with guidelines established in the State Water Resources Control Board Leaking Underground Fuel Tank Manual (SWRCB, 1989).

4.2 Analytical Results

4.2.1 Soil Samples

Soil samples collected from borings SB-1, SB-2, and SB-3 at depths of approximately 7.5 feet BGS were analyzed. These samples were selected because they were thought to be near the water table depth. Laboratory analysis did not detect TPH-G/BTEX in these soil samples. Soluble lead was not detected in the sample from the soil pile. Table 3 summarizes the results of the laboratory analyses performed on soil samples. Laboratory reports are presented in Appendix D.2.

4.2.2 Groundwater Sample

A groundwater sample was collected and retained for laboratory analysis on February 15, 1994 from the newly installed monitoring well (MW-1). Laboratory analysis did not detect TPH-G or BTEX in the groundwater sample. These data are presented in Figure 4 and Table 4. Laboratory reports are presented in Appendix D.2.

5.0 SOIL DISPOSAL

Approximately 10 yards of soil cuttings and drilling material was temporarily stored onsite in a 20-yard³ roll-off bin. After profiling, the material transported by Erickson, Inc. to the Browning Ferris Industries (BFI) disposal facility in Livermore, California as a non-hazardous RCRA waste. The soil disposal receipts are provided in Appendix C.

6.0 DISCUSSION

Based on field and laboratory data, there is a high likelihood that soil containing petroleum hydrocarbons within the unsaturated zone has been removed. Remaining hydrocarbons are located below 7 feet within the capillary fringe. Within the excavation area, soil was removed below the water table. In our opinion, impacted soil removal action (source material) was effectively completed during overexcavation.

There were no petroleum hydrocarbon odors or stained soil noted while drilling of SB-1, SB-2, SB-3, and MW-1 during the preliminary site investigation. Petroleum hydrocarbon sheen was not observed during groundwater monitoring well development and purging. In addition, petroleum hydrocarbons were not detected in soil or groundwater samples.

7.0 CONCLUSIONS

Based on the information presented in this report, current regulatory guidelines, and the professional judgment of IT Corporation, the following conclusions have been made:

- The water within the UST excavation may be a natural expression of the shallow aquifer or an artificial sump collecting surface runoff. Water within MW-1 is approximately 5.2 feet below the ground surface.
- Petroleum hydrocarbons were not detected in the soil and water samples analyzed during this investigation.

8.0 REFERENCES

- IT Corporation, 1993, Report of UST Removal, Pacific Bell Facility 2610 Norbridge Avenue, Castro Valley, California; dated July 16, 1993, 5 p.
- IT Corporation, 1994, Work Plan for Subsurface Characterization, Pacific Bell Facility 2610 Norbridge Avenue, Castro Valley, California; dated January 3, 1994, 5 p.
- SWRCB (State Water Resources Control Board), 1989, Leaking Underground Fuel Tank (LUFT) Field Manual; dated October 1989, 121 p.



TABLE 1
MONITORING WELL CONSTRUCTION DATA

Well No.	Borehole Depth (1)	Casing Depth (2)	Screened Interval (3)	FilterPack Depth (4)	Inner Dia. (5)	Install Date (6)	Drilling Method (7)
MW-1	16.0	16.0	6.0-16.0	5.0-16.0	4	2-2-92	HSA

Notes:

- 1. Depth to bottom of borehole in feet below the ground surface.
- 2. Depth to bottom of casing in feet below the ground surface.
- 3. Depth to top and bottom of well screen in feet below ground surface.
- 4. Depth to top and bottom of sand filter pack in feet below ground surface.
- 5. Well casing inside diameter in inches.
- 6. Monitoring well installed on the date shown.
- 7. HSA = boring drilled by hollow-stem auger.

TABLE 2
GROUNDWATER GRADIENT DATA

Well <u>No.</u>	<u>DTW (1)</u>	SWE (2)	Hydrocarbon Thickness	Groundwater Elevation (3)
MW-1	5.20	NA	0	NA

Notes:

- 1. DTW = depth to water as measured from the top of the well casing with an electric water sensing probe.
- 2. SWE = surveyed wellhead elevation as measured at the top of the well casing in feet above mean sea level.
- 3. The groundwater elevation = SWE minus DTW.
- 4. Measurements were recorded prior to groundwater sample collection on 2-15-94.
- 5. NA = There was no need to survey the wellhead elevation.

TABLE 3

RESULTS OF LABORATORY ANALYSIS

OF SOIL SAMPLES (1)

Sample No.	Depth (2)	Date (ppm)	TPH gasoline (ppb)	Benzene (ppb)	Ethylbenzene (ppb)	Toluene (ppb)	Xylenes (ppb)
SB-1(7.5)	7.5	2-2-94	ND	ND	ND	ND	ND
SB-2(7.5)	7.5	2-2-94	ND	ND	ND	ND	ND
SB-3(7.5)	7.5	2-2-94	ND	ND	ND	ND	ND
SSC-1(2-94)	composite of drill cuttings	2-15-94	ND	ND	ND	ND	ND

Notes:

- 1. Soil samples analyzed for TPH (Total Petroleum Hydrocarbons) as gasoline by LUFT methods utilizing modified EPA Method No. 8015, for benzene, toluene, ethylbenzene, and total xylenes (BTEX) by EPA Method No. 8020.
- 2. Depth given in approximate feet below ground surface.
- 3. ND = Not Detected above reporting limit.

TABLE 4


RESULTS OF LABORATORY ANALYSIS OF GROUNDWATER SAMPLE (1)


Sample No.	Date	TPH gasoline (ppm)	Benzene (ppb)	Ethylbenzene (ppb)	Toluene (ppb)	Xylenes (ppb)
MW-1(2-94)	2-15-94	ND	ND	ND	ND	ND

Notes:

1. Groundwater samples analyzed for TPH (Total Petroleum Hydrocarbons) as gasoline by LUFT methods utilizing modified EPA Method No. 8015, for benzene, toluene, ethylbenzene, and total xylenes by EPA Method No. 8020.







APPENDIX A SOIL BORING/MONITORING WELL PERMIT



PPLICANTS_

SIGNATURE Frank Horal)

ZONE WATER AGENCY

5997 PARKSIDE DRIVE

PLEASANTON, CALIFORNIA 94588

VO/CE (510) 484-2600 FAX (510) 462-3914

91992

DRILLING PERMIT APPLICATION

FOR APPLICANT TO COMPLETE	FOR OFFICE USE
LOCATION OF PROJECT 2610 HORBRIDGE AVE.	PERMIT NUMBER 93455 LOCATION NUMBER
CLIENT Name PACIFIC BELL	PERMIT CONDITIONS
Address 2600 CANING RANK 3E 410 VOICE City SAM RAPOH, CA ZIP 74583	Circled Permit Requirements Apply
APPLICANT Name IT CORP FROM HORTH FAX 40\$ - \$94 - 070 Address 2055 JUNCTION AUF City AR TOTAL OF Zip 9513; TYPE OF PROJECT Well Construction Cathodic Protection Cathodic Protection General Water Supply Contamination Well Destruction PROPOSED WATER SUPPLY WELL USE Domestic Industrial Other Municipal Irrigation PRILLING METHOD: Mud Rotary Air Rotary Auger Cable Other DRILLER'S LICENSE NO. C57 Bayloud Dulling WELL PROJECTS Drill Hole Diameter 8 in. Maximum Casing Diameter 2 in. Depth 20 ft. Surface Seal Depth 4 ft. Number 4 BEOTECHNICAL PROJECTS Number of Borings Maximum Hole Diameter in. Depth ft.	A. GENERAL 1. A permit application should be submitted so as to arrive at the Zone 7 office five days prior to proposed starting date. 2. Submit to Zone 7 within 60 days after completion of permitted work the original Department of Water Resources Water Well Drillers Report or equivalent for well Projects, or drilling logs and location sketch for geotechnical projects. 3. Permit is void if project not begun within 90 days of approval date. B. WATER WELLS, INCLUDING PIEZOMETERS 1. Minimum surface seal thickness is two inches of cement grout placed by tremie. 2. Minimum seal depth is 50 feet for municipal and industrial wells or 20 feet for domestic and irrigation wells unless a lesser depth is specially approved. Minimum seal depth for monitoring wells is the maximum depth practicable or 20 feet. C. GEOTECHNICAL. Backfill bore hole with compacted cuttings or heavy bentonite and upper two feet with compacted material. In areas of known or suspected contamination, tremied cement grout shall be used in place of compacted cuttings. D. CATHODIC. Fill hole above anode zone with concrete placed by tremie. E. WELL DESTRUCTION. See attached.
Hole Diameter in. Depth tt. ESTIMATED STARTING DATE ESTIMATED COMPLETION DATE 1	Approved Myman Hong Date 16 Aug 9
County Ordinance No. 73-68.	Wyman Hong

Date flu 19

ALAMEDA COUNTY HEALTH CARE SERVICES AGENCY



DAVID J. KEARS, Agency Director

RAFAT A SHAHID, ASST AGENCY DIRECTOR

DEPARTMENT OF ENVIRONMENTAL HEALTH State Water Resources Control Board Division of Clean Water Programs UST Local Oversight Program 80 Swan Way, Rm 200 Oakland, CA 94621

510) 271-4530

STID 4092

January 21, 1994

Post-It™ brand fax transmittal memo 76/1 Fot pages > Mike Miller

Mr. Duane Wallace Pacific Bell 2600 Camino Ramon San Ramon, CA 94583

2610 NORBRIDGE AVENUE, CASTRO VALLEY RE:

Dear Mr. Wallace:

This office is in receipt and has completed review of the Revised Subsurface Investigation Work Plan submitted under IT Corporation cover dated January 3, 1994. This revised work plan has been accepted as submitted.

Please contact this office at 510/271-4530 when field work is slated to begin.

sincerel/

Seery, CHICK

Senior Razardous Materials Specialist

Rafat A. Shahid, Assistant Agency Director Gil Jensen, Alameda County District Attorney's Office cc: Mike Miller, IT Corporation, 2055 Junction Avenue San Jose, CA 95131

APPENDIX B SUMMARY OF DRILLING PROGRAM

APPENDIX B.1 SOIL BORING/MONITORING WELL INSTALLATION PROCEDURES

SOIL BORING/MONITORING WELL INSTALLATION PROCEDURES

The procedures that were used for drilling the borings, collecting soil samples, and installing the groundwater monitoring wells were as follows:

- The borings were advanced to a depths ranging from approximately 16 to 30 feet below the ground surface using ten-inch hollow-stem augers; augers were steam cleaned prior to drilling;
- Soil samples were collected using a modified California split-barrel sampler lined with six-inch long stainless steel tubes at approximately 2.5 feet depth intervals;
- The samplers were washed between sampling intervals in a soapy water wash, two tap water rinses, and a final deionized water rinse;
- Stainless steel sample tubes were end-wrapped with teflon and capped with PVC end caps, and retained for laboratory analysis by storing in an insulated chest;
- Soil samples were assigned identification numbers such as SB-1(7.5), where SB-1 indicates soil boring number 1, and (7.5) indicates the sample interval depth, in feet;
- Chain-of-Custody procedures, including the use of Chain-of-Custody forms, were used to document sample handling and transportation to the laboratory;
- An Hnu Systems organic vapor meter (OVM) was used to monitor VOCs during drilling. The monitoring involved "sniffing" the annulus of the hollow-stem augers at the surface at selected depth intervals and also measuring the VOC concentration associated with the soil sample from that depth interval. From each sampling interval, a partially-filled sample tube was capped and set aside to allow for VOCs to accumulate in the headspace above the soil. After approximately 15 to 30 minutes, the VOC concentration was measured with the OVM;
- Four-inch (inside-diameter) threaded, machine-slotted PVC screen and casing were installed in the boring for well construction;
- The monitoring wells were developed by removing approximately ten well casing volumes of water to remove silt from the formation and that had accumulated in the wells during installation; and
- The annular space around the screened interval in the well was backfilled with an appropriately graded sand filter pack (No. 3 Lonestar) and capped with an approximate six-inch thick zone of hydrated granular bentonite. Neat portland cement grout was placed in the annulus above the bentonite zone, with an atgrade well housing and locking device.

APPENDIX B.2

BORING LOGS

BORING NO. MW-1 SAMPLE NUMBER & INTERVAL B COUNT (qdd) FIELD GEOLOGIST: M. MILLER DATE BEGAN: 02/02/94 USCS BORING SUMMARY Z DATE FINISHED: 02/02/94 M. MILLER ۵ CHECKED BY:____ ₩OH 16 FT. GROUND SURFACE EL N/A TOTAL DEPTH: _ ۵ 5.2 FT. DEPTH TO WATER:_ N/A TOP OF CASING EL .: .. 0 Protective -Box Asphalt and concrete. GΡ Pea gravel - tank fill. 4" Dia. Sch. 40 coaing Collecting first sample from first native material. Neat Cement Bentonite Pallets encountered water at 6.5 feet (BGS) #12 Cilica Sond ----Threaded Cap TOTAL DEPTH 16 FT. COMMENTS: Location is within excavated area of tankpit. Lots of water and gravel inside auger. No sample collected because native material was not encountered.

PAGE 1 OF 1

DRILLING CO.: Kvilhaug Drilling DRILL METHOD: Hollow Stem Auger

SAMPLING METHOD: Modified California Split Spoon Sampler

PROJECT NO.: 151933 CLIENT: Pacific Bell



FEET	WBER VAL	JNT	(x)	(pdd)	······································			ы	BORING NO. SB-1
O DEPTH IN FEET	SAMPLE NUMBER & INTERVAL	BLOW COUNT	RECOVERY (%)	9) O 1 d	BORING SUMMARY		NSCS	PROFILE	FIELD GEOLOGIST: M. MILLER CHECKED BY: M. MILLER GROUND SURFACE EL: N/A TOP OF CASING EL: N/A DATE BEGAN: U2/02/94 DATE FINISHED: 02/02/94 TOTAL DEPTH: 30 Feet DEPTH TO WATER: HOT FOUND
H = ° -						1 1 1	FILL		2" Asphalt, 10" Roadbase fill.
							ML		Silt: moderate yellowish brown (10YR 5/4), dry.
g							CL		CLAY; olive gray (5Y 3/2), damp, very silty.
					Cement				becomes grayish clive (10YR 4/2) at 7.0 feet.
<u> </u>		27	85	٥	grout				
E =	SB-1-5'								
						1 1 31 3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			
_	SB-1-7.5'	65	90	0		1 1 2			
F =									
— 10—				0		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			
F =	SB-1-10'	85		٦					
						An analysis frankrit in a set allegere planer and a set allegere and a set allegere and a set allegere and a s The control of the control of	CL		CLAYSTONE; moderate yellowish brown (10YR 5/4), dry
_ _	SB-1~12.5	65		0			ŲĹ		hard, highly sheared.
L =									
 15-									
- "-	SB-1-15'	72		0		100			
					i I				
F =									
	ţ								
_ 20_]								becoming bedrock, very hard drilling, very dry.
- ⊢	1								
F =]					1			
 - 25-						<u>4-</u> w			
£"-						***			COMMENTS:
F -]								No water found. Boring terminated at 30 feet.
	1					4			Backfilled with grout.
L =						-1			
	1					. इंद्रेशीय - इंद्र			Hit bedrock Refusal
– 30 –	<u> </u>					لمشت		7777	TOTAL DEPTH 30 FEET

PAGE 1 OF 1

DRILLING CO.: Kvilhaug Drilling DRILL METHOD: Hollow Stem Auger SAMPLING METHOD: Modified California Split Spoon Sampler

PROJECT NO.: 151933 CLIENT: Pacific Bell



DEPTH IN FEET	SAMPLE NUMBER & INTERVAL	BLOW COUNT	RECOVERY (X)	P 1 D (ppb)	BORING Summary		USCS	PROFILE	BORING NO. SB-2 FIELD GEOLOGIST: M. MILLER CHECKED BY: M. MILLER GROUND SURFACE EL:: N/A TOP OF CASING FI - N/A DEPTH TO WATER: NOT FOUND
MANUA 144-42010 104-4200 10	35	8	R		Cement	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	FILL CL ML		TOP OF CASING EL: N/A DEPTH TO WATER: NOT FOUND Gravelly base-rock fill. CLAY; dark gray (N3), stiff. SILT; moderate yellowish brown (10YR 5/4), damp.
5	SB-2-7.5'	70	80	0	grout —		CL		CLAY; alive gray (5Y 3/2), damp, stiff.
- 10-									becomes moderate yellowish brown at 11.0 feet. becoming bedrock
15	SB-2-15'	85	50	0		1944 1945 1945			hit claystone bedrock; drill rig refusal.
20-									TOTAL DEPTH 16 FEET COMMENTS: No water found. Boring terminated at 16 feet. Backfilled with grout.

PAGE 1 OF 1

DRILLING CO.: Kvilhaug Drilling DRILL METHOD: Hollow Stem Auger

SAMPLING METHOD: Modified California Split Spoon Sampler

PROJECT NO.: 151933 CLIENT: Pacific Bell



CLAY; olive gray (N3), damp, stiff. CLAY; olive gray (SY 3/2), damp, very stiff. CLAY; olive gray (SY 3/2), damp, very stiff. becomes moderate brown at 12 ft. hard drilling, becomes bedrock. TOTAL DEPTH 17 FEET COMMENTS: No water found. Boring terminated at 17 feet. Backfilled with grout.	ALTER ISHNAFOR	SAMPLE NUMBER & INTERVAL	BLOW COUNT	RECOVERY (%)	P D (ppb)	BORING SUMMARY	nscs	PROFILE	BORING NO. SB-8 FIELD GEOLOGIST: M. MILLER CHECKED BY: M. MILLER GROUND SURFACE EL.: N/A TOP OF CASING EL.: N/A DEPTH TO WATER: MOT FOUND
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1					Cement grout	CL		CLAY; dark gray (N3), damp, stiff. CLAY; olive gray (5Y 3/2), damp, very stiff. becomes moderate brown at 12 ft. hard drilling, becomes bedrock. hit claystone bedrock; drill rig refusal. TOTAL DEPTH 17 FEET COMMENTS: No water found. Boring terminated at 17 feet.

PAGE 1 OF 1

DRILLING CO.: Kvilhaug Drilling DRILL METHOD: Hollow Stem Auger SAMPLING METHOD: Modified California Split Spoon Sampler

PROJECT NO.: 151933 CLIENT: Pocific Bell



APPENDIX B.3 WELL DEVELOPMENT LOGS



WELL DEVELOPING LOG

Conductance	roject Name:	9 3 3 Introl No.: DI No.:		Sample Location or:				
Several Column Seve								
Asing ID (a) (in.)	urging Method/Equipmo	ent: <u>FLEC</u>	T. PUMP AND	WISP. TUR	SING-			
asing ID (a) (in.)	* Diameter = 1.5 gal/ft		4" Diameter	0.67 gal/ft	2" Diamete	r = 0.17 g		
(6AL.) (F.) (X/000) (Color, Turbidity, Odor, Oil) 25 58.9 1.57 10:58 BROWN, SLTY, CDOR-255 8.1 10.0 59.8 1.73 11:05 NO SHEEN 8.4 20.0 62.1 189 11:09 TAN, " " 8.6 30.0 62.7 1.97 11:14 SLIGHTLY TAN, V 8.6 40.0 63.1 1.96 11:19 QLEAR, SLIGHTLY YCLIDWISH 8.4	ength of Static Water Co asing Water Volume (f)	>lumn in Casing (- (b) × (θ)	(e) = (c) - (d) = ×	13.75 - 10.2	25 6.86	(/0.		
.25 58.9 1.57 10.58 BROWN, SLTY, CDOR-255 8.1 10.0 59.8 1.73 11:05 NO SHEEN 8.4 20.0 62.1 189 11:09 TAN, " " 8.6 30.0 62.7 1.97 11:14 SLIGHTLY TAN, V 8.6 HO.C 63.1 1.96 11:19 CLEAR, SLIGHTLY YELLOWISH 8.4	ising volumes =		<u>×</u> ×	(f) =	54.94	(6.8 (
10.0 59.8 (.73 11:05 NO SHEEN 8.4 20.0 62.1 189 11:09 TAN, " " 8.6 30.0 62.7 1.97 11:14 SLIGHTLY TAN, V 8.6 40.0 63.1 1.96 11:19 QLEAR, SLIGHTLY YCLIDWISH 8.4						(6.2 (
10.0 57.8 1.73 11.09 TAN, " " 8.6 20.0 62.1 1.97 11.14 SLIGHTLY TAN, " 8.6 HO.C 63.1 1.96 11.19 CLEAR, SLIGHTLY YELLOWISH 8.4	Volume Purged	Temp.	Conductance		Water Description (Color, Turbidity, Odor, Oil)	· · · · · · · · · · · · · · · · · · ·		
30.0 62.7 1.97 11:14 SLIGHTLY TAN, V 8.6 HO.C 63.1 1.96 11:19 CLEAR, SLIGHTLY YELLOWISH 8.4	Volume Purged (GAL・)	Temp.	Conductance (×/000)	Time 10:58	Water Description (Color, Turbidity, Odor, Oil) BROWN, SLTY, CDOR-255	pH		
40.0 63.1 1.96 11.19 CLEAR, SLIGHTLY YELLOWISH 8.4	Volume Purged (GAL·)	Temp. (F.) 58.9	Conductance (×/000) 1.57 (.73	10:58 11:05	Water Description (Color, Turbidity, Odor, Oil) BROWN, SLTY, CDOR-255 NO SHEEN	9.13 8.48		
70.C OFFICE OF THE PROPERTY OF	Volume Purged (6AL·) . 25 . 10.0 20.0	Temp. (F.) 58.9 59.8 62.1	Conductance (×/000) /.57 (.73 /89	10:58 11:05 11:09	Water Description (Color, Turbidity, Odor, Oil) BROWN, SLTF, CDOR-255 NO SHEEN TAN, " "	9.13 8.48 8.66		
55.0 63.C 7.17 11.23 C 7 6BCRIES B.C	Volume Purged (&AL·) . 25 . 10.0 . 20.0 . 30.0	Temp. (F.) 58.9 59.8 62.1 62.7	Conductance (×/000) 1.57 (.73 189 1.97	10:58 11:05 11:09 11:14	Water Description (Color, Turbidity, Odor, Oil) BROWN, SLTP, CDOR-255 NO SHEEN TAN, " " SLIGHTLY TAN, "	9.13 8.48 8.66 8.60		
	Volume Purged (&AL·) .25 .10.0 .10.0 .30.0 .0	Temp. (F.) 58.9 59.8 62.1 62.7 63.1	Conductance (X/000) 1.57 (.73 1.89 1.97 1.96	10:58 11:05 11:09 11:14 11:19	Water Description (Color, Turbidity, Odor, OH) BROWN, SLTF, CDOR-255 NO SHEEN TAN, "" SLIGHTLY TAN, " CLEAR, SLIGHTLY YELLOWSH	9.13 8.48 8.66 8.60 8.40		
	Volume Purged (&AL·) .25 .10.0 .10.0 .30.0 .0	Temp. (F.) 58.9 59.8 62.1 62.7 63.1	Conductance (X/000) 1.57 (.73 1.89 1.97 1.96	10:58 11:05 11:09 11:14 11:19	Water Description (Color, Turbidity, Odor, OH) BROWN, SLTF, CDOR-255 NO SHEEN TAN, "" SLIGHTLY TAN, " CLEAR, SLIGHTLY YELLOWSH	9.13 8.48 8.66 8.60		
	Volume Purged (&AL·) .25 .10.0 .10.0 .30.0 .0	Temp. (F.) 58.9 59.8 62.1 62.7 63.1	Conductance (X/000) 1.57 (.73 1.89 1.97 1.96	10:58 11:05 11:09 11:14 11:19	Water Description (Color, Turbidity, Odor, OH) BROWN, SLTF, CDOR-255 NO SHEEN TAN, "" SLIGHTLY TAN, " CLEAR, SLIGHTLY YELLOWSH	9.13 8.48 8.66 8.60 8.40		

NOTES:

Total Volume Purged:

APPENDIX B.4

WATER LEVEL MEASUREMENT AND GROUNDWATER SAMPLING PROCEDURES

WATER LEVEL MEASUREMENT AND GROUNDWATER SAMPLING PROCEDURES

The procedures used to measure water levels and collect the groundwater samples are presented below:

- Field activities and equipment utilization were recorded on field report forms;
- The water level and depth to the bottom of the well were measured using an electrical conductance probe to approximately 0.01 foot. The probe was rinsed in a solution of Alconox followed by a deionized water rinse prior to each use;
- The volume of water contained in the well casing was estimated using the following equation: Casing Volume = $\pi r^2 h$, where r equals the radius of the well casing, and h equals the height of the water column in the well;
- Measurement of the electrical conductivity and pH were performed on samples
 of the groundwater utilizing a "Hydac" digital temperature/electrical
 conductivity/pH meter;
- Groundwater recovered from the wells was placed in labeled drums for on-site storage;
- A disposable bailer was used for collecting the groundwater samples;
- Nylon rope was used to lower the bailer into the monitoring well for sampling. The nylon rope was discarded after use;
- Groundwater samples were discharged from the bailer to laboratory-supplied sample vials at a controlled rate intended to minimize bubbling and agitation of the liquid. The container was filled to the top to minimize the headspace;
- Groundwater samples were capped and secured with evidence tape, and placed on ice in an insulated chest cooled to a temperature of approximately 40 to 50 degrees Fahrenheit; and
- Groundwater samples were delivered to the laboratory immediately after collection. Sample handling, transport, and delivery to the laboratory were documented using Chain-of-Custody forms.

APPENDIX B.5 GROUNDWATER SAMPLE COLLECTION LOG



Page	- 1	of /	/
raye		OI	

	GROUND	WATER SAMPL	ECOLLEC	TION LUG	
Project Name: Paci Project No.: 1519 Request-for-Analysis Cor	<u> 33</u> ntrol No.: <u>_ 35</u>	<u> 5009 </u>	Sample Location or: Well ID (attach map if necessary): Date and Time Collected: Sample Collected by: LJM.		
Chain-of-Custody Contro Sample No.:A	1 No.: 1 (2-94	<u>()</u>		fice)/Date:	
EQUIPMENT				(الم	
Purging Method/Equipme Sampling Equipment/ID I	ent: <u>ELECTA</u> No.: <u>DISP</u> - A	BAILER AND DI	SP. TWIN		
6" Diameter = 1.5 gal/ft		4"Diameter = 0.	67 gai/ft	2" Diameter	= 0.17 gal/f
PURGING INFORM	ATION				
Casing ID (a) (in.) Depth to Well Bottom (c) Length of Static Water Co Casing Water Volume (f) Casing Volumes =	7 /5. plumn in Casing = (b) × (e) = _ 3	Unit Casin $\frac{43}{6} = (c) - (d) = \frac{1}{2}$	Depth to Wate (6) $\frac{6.43}{0.3}$ $\frac{10.37}{0}$	er (d) $\frac{5.12}{5.12}$ = $\frac{10.31}{6.907}$ = $\frac{20.72}{20.72}$	(,67) (5,12) (0,31) (6,90) (20.8)
Volume Purged	Temp.	Conductance	Time	Water Description	рН
(CALI)	(F.)	(x1660)		(Color, Turbidity, Odor, Oil)	
.25	62.6	3.69	10:40	BROWNISH TAN, ODORLESS, NO SHEEN, SLIGHTLYSLIY.	6.51
4.0	64.7	2.59	10:43		7-29
8.0	64.1	2.32	10:49	13 0	8-00
12.0	63.8	2.24		SLIGHTLY TAN, N	8.10
16.0	63.6	2 23	10:57	CLEAR, ODORLESS, U	8.17
21,0	63.7	2.26	11:00		8.20
	21.0	Time: []:CO		Purged Dry (Y/N): NO	
Total Volume Purged:		1000		• , , ,	

SAMPLE PACKAGING

Container(s) Type and Volume	Filtered (Y/N)	Preservatives	Parameters
3x4Cml VCA	NO.	HCL	TPH-G/BTEX
	1		
<u></u>			
	-		
		<u> </u>	722 15

APPENDIX C SOIL DISPOSAL

255 Per Styd., Flohmond, CA 94801 (510) 235-1388	and the state of t	TO A COLOR OF THE STATE OF THE	Carline Designation 1888
]	Driver Daily Time Shee		
19738 Stover Ave., Fortam, CA 92335 (909) 305-8001	Mikrun No yes	Det	
1300 E. Greg St., See 3, Sperie, NV 89431 (702) 308—5581 803 W. 400 South, Sek Lake City, UT 84101 (801) 359—68		6	Shift: GY D \$
Detver Name: CHARLEY FLI	MORIE SAMPARTO	168 Manifest No.1	Bc-730144
Customer Name: 1941- T	T. CORP	Customer O	der No. 248958
Jobelte Name JOBSTTE-26	10 NORBRIDGE AVE		And the second second second
A Address: PACIFIC BE		· · · · · · · · · · · · · · · · · · ·	
	LEY, CA 94546	Comes rum	MIKE MILLER
0900 ONSITE!			WE 408 7 894 1200
Services Performed: SERVICES T	A DRAWING A PATTARE		
			- Commence of the second of th
	bin (5 yards)	to Keller	Conyon For
Additional Information: ABDOSA			
A CONTRACTOR OF THE STATE OF TH			
	YD OPEN TOP W/LINER		the state of the s
Driver's Comments:			
The same and			
Waste			
Meterial:	Profile/ W.	S.#:	
Today's	Today's	, , , , , , , , , , , , , , , , , , ,	
Origin: 🌿	Destination:	= Jan 6 4 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Our P,O.#
Disposal Site: Keller Canyon	Date & Time:	No. of Loads:	No. of Drume:
		OFFICE (IS)	
Truck No. 3032 Trailer No.	Truck EMS #	Payrol	Gling - Got & Different From Payed
	Sadas Total	Miles Class SI O	OT MAN CAME ST OT BY
Hub Reading: Begin	Ending Total: AM		
	Stop PM Total:		
		300000000000000000000000000000000000000	
		Diena	tchar's Anorrael
Job Site: Anive 915 PM	Depart 920 PM Total:	Diepa	scher's Approved
Job Site: Anthe 915 PM AM Disposal Site: Arrive PM	Depart 930 PM Total: Depart PM Total:		
lob Site: Antwe 915 PM AM Naposal Site: Arrive PM Stop#1	Depart 920 PM Total:	Clid you perform	
Job Site: Anthre 9/5 PM ANA Disposal Site: Arrive PM Stop#1 Meals: Start#1	Depart 930 PM Total: Depart PM Total: Stop#2	Did you perform pre-trip equipm	your
Job Site: Antwe 915 PM AM Disposal Site: Arrive PM Stop#1 Meale: Start#1	Depart 920 PM Total: AM Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB:	Did you perform pre-trip equipm	your
Job Site: Antre 915 PM AM Disposal Site: Arrive PM Stop#1 Menie: Start#1	Depart 920 PM Total: Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION	Did you perform pre-trip equipm	your
Job Site: Antwe 915 PM AM Disposal Site: Arrive PM Stop#1 We ale: Start#1 TO ROLL OFF Container No. Container Pick Up Point	Depart 930 PM Total: AM Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION Disposal Site Container	Did you perform pre-trip equipm Ins. ST OT Drop Off Point EMS # 85016	your
lob Site: Antre 915 PM ANA Naposal Site: Arrive PM Stop#1 Acale: Start#1 TO	Depart 920 PM Total: Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION	Did you perform pre-trip equipm	your
Iob Site: Antive 915 PM AM Asposal Site: Arrive PM Stop#1 Start#1 TO ROUL OFF Container No. Container Pick Up Point	Depart 930 PM Total: AM Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION Disposal Site Container	Did you perform pre-trip equipm Ins. ST OT Drop Off Point EMS # 5010 97200 99152 99280	your
Iob Site: Antive 915 PM AM Asposal Site: Arrive PM Stop#1 Start#1 TO ROUL OFF Container No. Container Pick Up Point	Depart 930 PM Total: AM Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION Disposal Site Container	Did you perform pre-trip equipm Nrs. ST OT Drop Off Point EMS # 85010 97200 99152 99260 2016	your
Job Site: Anthre 9/5 PM AMA Disposal Site: Arrive PM Stop#1 We ale: Start#1 TO ROLL OFF: Container No. Container Pick Up Point JOHN PAC BALL	Depart 930 PM Total: AM Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION Disposal Site Container	Did you perform pre-trip equipm Nrs. ST OT Drop Off Point EMS # 85010 97200 99152 99260 2016 2017	your
Job Site: Antive 9/5 PM AM Disposal Site: Arrive PM Stop#1 Menie: Start#1 TO PIOLL OFF: Container No. Container Pick Up Point JOHN PAC BALL CUSTOMER BIGNATURE ACKNOWLEDGES WORK PERFORMED AT JOB SITE ONLY.	Depart 930 PM Total: Depart PM Total: Stop#2 Start#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION Disposal Site Container BF VASPOR OS Customs Representative Signature Walter Age	Did you perform pre-trip equipm hrs. ST OT Drop Off Point EMS # 85010 97200 90152 90260 2016 2017 90218 90218	your
Job Site: Antive 915 PM Manual Site: Arrive PM Stop#1 Menule: Start#1 TO PIOLL OFF: Container No. Container Pick Up Point Joyn PAC BALL	Depart 930 PM Total: AM Depart PM Total: Stop#2 Sturt#2 Total: (TAL PAY - THIS JOB: CONTAINER INFORMATION: Disposal Site Container BF= VASIO IZ J OS	Did you perform pre-trip equipm Nn. ST OT Drop Off Point EMS # 85010 97200 99152 99260 2016 2017 99218 99218	your

000.00

NON-HAZARDOUS SPECIAL WAS IE MANIES GENERATOR Senerator Name Description of Waste I hereby certify that the above named material does not contain free liquid as defined by 40 CFR Part 260-10 (1941) A DOI Cable state law, is not a hazardous waste as defined by 40 CFR Part 261 or any applicable state law, has desired per condition for transportation according to approache revulation. TRANSPORTER Truck No. 3R3 ransporter Name Vehicle License No /State · 经过来等层过滤 Vehicle Certification hereby certify that the above named material was picked up I hereby certify that the above named material was delivered without incident to the destination listed below. t the generator site listed above. Driver Signature DESTINATION Site Name ddress hereby certify that the above named material has been accepted and to the best of my knowledge the foregoing is true and accurate. ume of Authorized Agent

APPENDIX D LABORATORY ANALYSES

APPENDIX D.1

CHAIN-OF-CUSTODY



ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD*

Reference	Document No.	355009
Page 1 of		

CORPORATION FAIL BELL		. 450 . 0
Project Name/No. 1 /5/433	Samples Shipment Date 7 2-15-44	Bill to:5 IT CCRP.
Sample Team Members 2 2/1/	Lab Destination 8 SUPERICE	<u> 4545 PNC</u> MARTINE &
Profit Center No. 3 2724	Lab Contact 9 FRITIP (CRTIS	
Project Manager 4 LIKE MILLEY	Project Contact/Phone 12 HIKE HILLIE F	Report to: 10 / T. CCRP
Purchase Order No. 6 24 20 73	Carrier/Waybill No. 13	2655 JL NC
Required Report Date 11 LIFUNC	ONE CONTAINER PER LINE	ATNI HIKE

		<
Bill to	5 IT CCRP.	Vhite
	4545 PROPLEC BLLD	.
	MARTINEZ, CA 9-1553	_ 0.
Report to	:10 IT CERP	company sample
		س د

						I had to had to be the	THE JEILSE FL	
Sample ¹⁴ Number	Sample ¹⁵ Description/Type	Collected	Container ¹⁷ Type	Sample ¹⁸ Volume	Pro ¹⁹ servative	Requested Testing ²⁰ Program	Condition on ²¹ Receipt	Disposal ²² Record No.
MW-1 (2-94)	GROUNDU MIER	11:10	3740ml	12cm1	HCL	TPH-G/BTEX		
550-1(2-94)	SCIL	2-15-94 @ 10°10	273 in- 36455		NUNE	TPH-G/BTEX		
							San San San	
						Tage in the	· · · ·	
						rgestavi i		
							3 90 900 23	
								foc !
/								
Special Instruction	ons: ²³							
Possible Hazard Non-hazard	Identification: 24 Iammable 🔟 Skin Irri	itant 🔟 Poi	son B	Unknowi		Sample Disposal: 28 Return to Client Disp	osal by Lab 🛂 🗸 Archive	e (mos.)
Turnaround Time Normal 🕍 Rush	Required: ²⁶		1.12	C Level: 2		Project/Specific (specify):		//
Relinquished by (Signature/Affiliation)	28 km M. Mit	Dat Tirr	ie: <u>2-/5-</u> ne:	940,	1. Rece (Signature/	ived by 28	Date: ())(0)0 AEEO Time:	2/15/94
2. Relinquished by (Signature/Affiliation)	Harron Tonos	Dat Asso Tim	ie: 2-15 ie: 4.40	-94 VS	2. Rece (Signeture/	ived by	Date:	
3. Relinquished by (Signature/Affiliation)		Dat Tirr	e:		3. Rece	ived by Ahl W/	// / / 0 Date:	2/15/94 4:40/m
Comments: 29					L			7. 10 (2)

. [INTERNAT TECHNOLO CORPORAT	TION PACIFIC B
	-	No. 1 1519
9	Sample Team Memb	ers 2 2 M/M/
	Profit Center	No.3 2224
	Project Mana	ager 4 MIKE, MIC
		No. 6 2489 79
	Required Report C	
	Sample ¹⁴ Number	Sample ¹⁵ Description/Type
		Sample 15 Description/Type
	Number 5B-1(7.5)	Description/Type
	Number	Description/Type

51649	ANALYSIS REQUE	
151933	Samples Shipment Date 7	2-9-94

Samples Shipment D	late ⁷	2-9	-94
Campines culpinent r			

Lab Destination 8 SUPERIOR

Lab Contact 9 KRISTEN KURTIS

Project Contact/Phone 12 MIKE MILLER
Project Contact/Phone 12 MIKE MILLER
Report to: 10 /T CORPORATION

Carrier/Waybill No. 13 UENDOR

Reference Document No. 355008 Page 1 of ____

Bill to:5	IT CORPORATION
	HS85 PACHECO BLVD.
	MARTINEZ CA 94553

2055 JUNCTION AV

SAN NOSF, CA 95/3/

Required Report D	ate 11 NORMAL		ONE	CONT	AIMED	PER LINE	SAN NOSE, (CA 45/3/
Sample ¹⁴ Number	Sample ¹⁵ Description/Type	Date/Time 16		Sample 18			Condition on 21 Receipt	Disposal ²² Record No.
SB-1(7.5)	501し	2-2-94 @	3×6 IN Brass		NONE	TPH-G/BTEX		
SB-2(7.5)	SOIL	2-2-94@	1/		1)	U	TUK!	44
SB-3(7.5)	501-	2-2-94@	11		۱۱	To stone laborate	- Juge w	
						Steren Steren	1//02	
						pleo pysiene i	The same of the sa	
$\overline{}$							KO AZE	RITY
								** *** *
		*	\ \	<u> </u>	>			
Special Instructio	ns: ²³							
Possible Hazard I Non-hazard 🖫 🗡 F	dentification: 24 lammable 🔟 Skin Im	ritant 🗓 Po	ison B 🔟	Unknowi		Sample Disposal: ²⁵ Return to Client Dis	posal by Lab 🌃 Archiv	e (mos.
Turnaround Time Normai 💆 Rushi	Required: ²⁶		1. 2	Level: 2	7 III. _	Project Specific (specify):		
1. Relinquished by Signature/Affiliation)	28 faw M. M	Ole Dat Tim	te: <u>2-9-9</u> ne:	140	1. Recei	ived by 28 ffiliation)	Date:	2/7/94 1723
2. Relinquished by (Signeture/Affiliation)	865		te: <i>2/10 /</i> ne: <i>1</i> 75 c		2. Rece (Signature/A		Date:	
3. Relinquished by Signature/Affiliation)		Da Tin	te: ne:		3. Rece		Date: Time:	
Comments: ²⁹		-			<u> </u>	Superity		

						TAP		7/77	
INTERNATITECHNOLA COPPORA		CHA	NALYS!	USTO	DY REC	AND CORD*	Refe Pag	erence Document e 1 of	,
	No. 1 [51933	Samp	oles Shipma				Bill to	5 IT (org 4585 Pacheco	0, 1
Sample Team Memb	pers 2 MillER					P.DR.		Martinez, CA	
Profit Center	No. 3 2224	 	Lab	Contact	9 Kich	1 PHALER			94553
Project Mana	ager4M. MILLER	Proje	ect Contact	t/Phone	12 MIKE	EMILLER BAY-1200 Rep	cort to	10 IT Corp	
Purchase Order	No. ⁶		Carrier/W	aybill No.	13روي <u>مي</u>			2055 Junet	ion Au
Required Report D	Date 11 NORMAL		ONE	CONT	AINER	PER LINE		San Jose Co Mike Miller	95131
Sample ¹⁴ Number	Semple ¹⁵ Description/Type	Date/Time Collected	Container 17 Type				ng 20	Candition on ²¹ Receipt	Disposal ²² Record No.
ISSC-1(2-94)	Soil	2-15-94	ZEASS	_	ಗಂಗ€	STLC; Pb	i		
57664-2						ikl			
						y	عع	SUZ	Reserved
						ÿ	SIA		
									森 野
					-		-/-		
Special Instruction	ons: 23 SAMPLE 15	S AT LA	BORATO	RY					<u> </u>
Possible Hazard				Unknow	n 🗓	Sample Disposal: Return to Client	25 Dispe	osal by Lab 🖺 🛮 Archive	:(mos.)
Turnaround Time Normal & Rush			GC 1. <u>2</u>	C Level: 2	7 III	Project Specific (sp	ecify):		
Relinquished by [Signature/Affiliation]	28 Mike Miller	Oat Tim			1. Rece	ived by 28 Affiliation)		Date: Time:	
2. Relinquished by	'	Dat			2. Rece			Date:	
3. Relinquished by		Tim Dat		<u> </u>	3. Rece			Time:	3/2/5x
[Signature/Affiliation]		Tim			(Signature/		10-	Time:	10,00 hm
Comments; 29							0		

APPENDIX D.2 LABORATORY REPORTS



1555 Burke, Unit 1 • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

IT Corp (SJ)
Attn: MICHAEL MILLER

Project PACIFIC BELL 151933 Reported 15-February-1994

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES by EPA SW-846 Methods 5030/8015M/8020.

Chronology	Laboratory	Number	57649			
Identification	Sampled	Received	Extracted	Analyzed	Run #	Lab #
SB-1(7.5) SB-2(7.5) SB-3(7.5)	02/02/94	02/10/94 02/10/94 02/10/94	02/14/94 02/15/94 02/15/94	02/14/94 02/15/94 02/15/94		1 2 3

Page 1 of 3



1555 Burke, Unit I • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

IT Corp (SJ)
Attn: MICHAEL MILLER

Project PACIFIC BELL 151933 Reported 15-February-1994

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES

Laboratory Number	Sample Identification	Matrix
57649- 1	SB-1(7.5)	Soil
57649- 2	SB-2(7.5)	Soil
57649- 3	SB-3(7.5)	Soil

RESULTS OF ANALYSIS

Laboratory	Number:	57649- 1	57649-	2	57649-	3
Laboratury	MAINDEL	J/VIJ I	9,042	_		-

Gasoline: Benzene: Toluene: Ethyl Benzene: Total Xylenes:	ND<1 ND<.005 ND<.005 ND<.005 ND<.005	ND<1 ND<.005 ND<.005 ND<.005 ND<.005	ND<1 ND<.005 ND<.005 ND<.005 ND<.005	
Concentration:	mg/kg	mg/kg	mg/kg	
Surrogate % Recov Trifluorotoluene (SS		119	113	



1555 Burke, Unit I • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES Quality Assurance and Control Data - Soil

Laboratory Number 57649

Compound	Method Blank (mg/kg)	RL (mg/kg)	Spike Recovery (%)	Limits (%)	RPD (%)	
Gasoline:	ND<1	1	89/89	75-125	0%	
Benzene:	ND<.005	.005	125/125	75-125	0%	
_ Toluene:	ND<.005	.005	95/92	75-125	3%	
Ethyl Benzene:	ND<.005	.005	95/95	75-125	0%	
Total Xylenes:	ND<.005	.005	92/95	75-125	3%	

Definitions:

ND = Not Detected

RPD = Relative Percent Difference

RL = Reporting Limit

mg/kg = Parts per million (ppm)

QC File No. 57649

Senior Chemist 2/16/94

Senior Chemist Account Manager

Page 3 of 3



1555 Burke, Unit I • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

IT Corp Attn: MICHAEL MILLER Project PACIFIC BELL 151933 Reported 21-February-1994

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES by EPA SW-846 Methods 5030/8015M/8020.

Chronology				Laboratory	Number	57664	
Identification	Sampled	Received	Extracted	Analyzed	Run #	Lab #	
MW-1 (2-94) SSB-1 (2-94)		02/15/94 02/15/94	02/16/94 02/21/94	02/16/94 02/21/94		1 2	

Page 1 of 4



1555 Burke, Unit I • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

IT Corp Attn: MICHAEL MILLER Project PACIFIC BELL 151933 Reported 21-February-1994

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES

Laboratory Number	Sample Identification	Matrix	
57664- 1	MW-1 (2-94)	Water	
57664- 2	SSB-1 (2-94)	Soil	

RESULTS OF ANALYSIS

57664-1 57664-2 Laboratory Number:

Gasoline: ND<50 ND<1 ND<.005 ND<0.5 Benzene: ND<0.5 ND<.005 Toluene: ND<0.5 ND<.005 Ethyl Benzene: Total Xylenes: ND<0.5 ND<.005 mg/kg

Concentration: ug/L

-- Surrogate % Recoveries --Trifluorotoluene (SS): 96 113



1555 Burke, Unit I • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES Quality Assurance and Control Data - Water

Laboratory Number 57664

Compound	Method Blank (ug/L)	RL	Spike Recovery (%)	Limits (%)	RPD (%)	
Gasoline: Benzene: Toluene: Ethyl Benzene:	ND<50 ND<0.5 ND<0.5 ND<0.5	50 0.5 0.5 0.5	94/98 76/82 85/94 89/96	60-134 60-140 75-125 75-125	4% 8% 10% 8%	
Ethyl Benzene: Total Xylenes:	ND<0.5 ND<0.5	0.5 0.5	89/96 96/105	75-125 75-125	8% 9%	

Definitions:

ND = Not Detected

RPD = Relative Percent Difference

RL = Reporting Limit

ug/L = Parts per billion (ppb)

QC File No. 57664

Page 3 of 4



1555 Burke, Unit I • San Francisco, California 94124 • (415) 647-2081 / fax (415) 821-7123

ANALYSIS FOR GASOLINE, BENZENE, TOLUENE, ETHYLBENZENE, AND XYLENES Quality Assurance and Control Data - Soil

Laboratory Number 57664

Compound	Method Blank (mg/kg)	RL (mg/kg)	Spike Recovery (%)	Limits (%)	RPD (%)	
Gasoline: Benzene: Toluene: Ethyl Benzene: Total Xylenes:	ND<1 ND<.005 ND<.005 ND<.005 ND<.005	1 .005 .005 .005	108/110 105/100 100/113 100/110 104/115	59-141 68-133 75-125 75-125 75-125	2% 5% 12% 10% 10%	

Definitions:

ND = Not Detected

RPD = Relative Percent Difference

RL = Reporting Limit

mg/kg = Parts per million (ppm)

QC File No. 57664

Senior Chemist Account Manager

Page 4 of 4



825 Arnold Drive, Suite 114 • Martinez, California 94553 • (510) 229-1512 / fax (510) 229-1526

IT Corp (SJ)
Attn: MICHAEL MILLER

Project 151933 Reported 08-March-1994

ANALYSIS FOR SOLUBLE LEAD by California Administrative Code Title 22 & SW-846 Method 6010

Chronology				Laboratory	Number	91226
Identification	Sampled	Received	Extracted	Analyzed	Run #	Lab #
SSC-1(2-94)	02/15/94	03/02/94	03/03/94	03/08/94		1

Page 1 of 3



825 Arnold Drive, Suite 114 • Martinez, California 94553 • (510) 229-1512 / fax (510) 229-1526

IT Corp (SJ) Attn: MICHAEL MILLER

Project 151933 Reported 08-March-1994

ANALYSIS FOR SOLUBLE LEAD

Laboratory Number

Sample Identification

Matrix

91226- 1

SSC-1(2-94)

Soil

RESULTS OF ANALYSIS

Laboratory Number: 91226-1

Soluble Lead

(Pb): ND<0.5

Concentration:

mg/L

Page 2 of 3

ANALYSIS FOR SOLUBLE LEAD Quality Assurance and Control Data - Extract

Laboratory Number 91226

Compound		Method Blank (mg/L)	Blank RL		Limits (%)	RPD (%)	
Soluble Lead	(Pb):	ND<0.5	0.5	102/101	75-125	1%	

Definitions:

ND = Not Detected

RPD = Relative Percent Difference

RL = Reporting Limit

mg/L = Parts per million (ppm)

QC File No. 91226

Senior Chemist Account Manager

Page 3 of 3