Audrey K. Bell
Certified Public Accountant
401 Felton Street 91 SEP 20 PH 6: 20
San Francisco, California 94134

(415) 468-1234

September 20, 1991

Mr. Larry Seto Division of Hazardous Materials Dept. of Environmental Health 80 Swan Way, Room 200 Oakland, CA 94621

REFERENCE: 33 La Salle Avenue

Piedmont, California

Dear Mr. Seto:

Enclosed, for your review, is a "Soil Sampling Report" for the above referenced property, prepared by Environmental Bio-Systems, Inc..

To the best of my knowledge, the information contained in this report is accurate.

Cordially,

Attorney in fact for

Dorothy F. Coates

Encl

cc: D F Coates

Hand delivered: 9-20-91

# SOIL SAMPLING REPORT: PROJECT #060-180-01

COATES PROPERTY 33 LA SALLE AVE. PIEDMONT, CALIFORNIA

PREPARED BY ENVIRONMENTAL BIO-SYSTEMS, INC.

**FOR** 

MRS. DOROTHY COATES 33 LA SALLE AVE. PIEDMONT, CA

> Timothy M. Babcock Project-Manager

> > Hebrul Anam Staff Engineer

SEPTEMBER 9, 1991

October 2, 1991

TO WHOM IT MAY CONCERN

SUBJ:

SOIL SAMPLING REPORT FOR

PROJECT #060-180-01

COATES PROPERTY 33 LA SALLE AVE. PIEDMONT, CA

#### Gentlemen:

Please attach this addendum letter onto the existing title page of the subject report dated September 9, 1991. California Registered Geologist, James A. Jacobs, R.G. #4813, did not sign the original report, however, this date he has reviewed and approved this report pursuant to Sections 6735, 7835, and 7835.1 of the Business and Professions Code.

Sincerely,

ENVIRONMENTAL BIO-SYSTEMS, INC.

Timothy M. Babeock

Project Manager

Hayward, CA 94544

# SOIL SAMPLING REPORT: PROJECT #060-180-01

# COATES PROPERTY 33 LA SALLE AVE. PIEDMONT, CALIFORNIA

### PREPARED BY ENVIRONMENTAL BIO-SYSTEMS, INC.

#### **FOR**

MRS. DOROTHY COATES
33 LA SALLE AVE.
PIEDMONT, CA

Timothy M. Babcock Environmental Scientist

> Hebrul Anam Staff Engineer

Reviewed by:

James A. Jacobs Registered Geologist #4815 NO. 4815

October 2, 1991

## TABLE OF CONTENTS

1.0)	INTRODUCTION	page 1
2.0)	PURPOSE AND SCOPE OF WORK	page 1
3.0)	SITE DESCRIPTION	page 2
4.0)	PREVIOUS ENVIRONMENTAL WORK	page 3
5.0)	FIELD PROCEDURES	page 3
6.0)	SAMPLING METHODOLOGY	page 5
7.0)	SAMPLE ANALYSIS	page 5
8.0)	RESULTS OF ANALYSES	page 6
9.0)	CONCLUSIONS	page 6
10.0)	RECOMMENDATIONS	page 8
11.0)	LIMITATIONS	page 10
TABL	ES Table 1 - Analytical results for soil samples	page 11
FIGUI	RES Figure 1- Site Location Map Figure 2- Site Diagram	page 12 page 13
APPE	NDIX A - Logs of Borings	
APPE	NDIX B - Laboratory Reports and Chain of Custody Docu for Soil Samples	mentation



#### 1.0) INTRODUCTION

This document contains information regarding soil sampling conducted at a residential Property located at 33 La Salle Ave. in Piedmont, California (the Site) by Environmental Bio-Systems, Inc. (EBS), on August 29, and August 30, 1991.

The site is owned by Mrs. Dorothy Coates and is currently occupied by the owner. The principal site contacts are:

Client Contact - Ms. Audrey Bell, (415) 468-1234.

Property Owner - Ms. Dorothy Coates, 33 La Salle Avenue, Piedmont, CA 94611, (510) 420-1744.

Consultant - Environmental Bio-Systems, Inc., 30028 Industrial Parkway Southwest, Suite C, Hayward, CA 94544, (510) 429-9988. Project Manager - Timothy M. Babcock.

### 2.0) PURPOSE AND SCOPE OF WORK

This report has been requested by the client to gain information concerning the possibility of hydrocarbon impact in the subsurface of the site. The scope of work encompassed in this report included the collection and analysis of soil samples from the subsurface of the site. The reported work included the following tasks:

- Extraction of 7 continuously driven soil cores using a split spoon sampler in conjunction with a hydraulic impact hammer mounted on a Bobcat.
- 2. Collection and analysis of soil samples taken from the cores at a laboratory certified by the State of California to perform the necessary analyses.
- 3. Submission of a report documenting the results of analyses and field observations.

#### 3.0) SITE DESCRIPTION

The site is located at 33 La Salle Avenue in the City of Piedmont and County of Alameda. A Site Location Map has been presented as Figure 1. A Site Diagram showing the locations of samples as well as relevant site structures and references, has been included in this report as Figure 2.

At the time of sampling, one single family residence was present on the site. The topography of the site slopes sharply from the back (northeast) of the property toward La Salle Avenue.

#### 4.0) PREVIOUS ENVIRONMENTAL WORK

On July 25, 1990, the client contracted Accutite to remove one 550 gallon underground storage tank (UST) from the site. Sampling of soil beneath the tank was performed by the contractor at the time of sampling. Soil samples collected from beneath the tank showed detectable concentrations of total petroleum hydrocarbons (TPH) as diesel and total oil and grease (TOG). No written documentation showing the location of the UST or subsequently collected soil samples was prepared by the contractor.

#### 5.0) FIELD PROCEDURES

On August 29, and August 30, 1991, EBS personnel extracted 7 continuously samples soil cores at the site using a Bobcat mounted impact coring device. The cores were designated EB1, EB2, EB3, EB4, EB5, EB6, and EB7. Descriptions of the subsurface stratigraphy recorded during coring are included in Appendix A as the Logs of Borings.

<u>EB1</u> was completed at a depth of 2-1/2 feet. Approximately 1/2-foot of Gravel with Silt was found above a fine to medium grained, light brown, weathered Sand Stone bed rock. The Sand Stone bed rock was moderately jointed and showed the presence of dark brown oxidation rinds. No hydrocarbon odor was noted in the soil and no sample was collected from this location. No sample was retained in the sampler.

EB2 was advanced to a maximum depth of 8 feet. Field observations indicated 1/4-foot of Gravel with Silt above a light brown, fine to medium Sandy fill. Absence of any jointing or oxidation rinds and the visual observation at the site confirmed the presence of sandy fill. No hydrocarbon odor was noted in the soil. Soil sample EB3-2-1/4' was collected at a depth of 7-1/2 to 8 feet.

EB3 was advanced to a depth of 4-1/4 feet. The log of core EB3 showed 1/4-foot of dark gray Clayey Silt followed by a fine to medium, whitish brown to light brown Sandy fill with traces of clay. A grayish brown to light greenish brown, fine to coarse, weathered Sand Stone bed rock underlies this. Soil sample EB2-8' was collected at a depth of 3-3/4 to 4-1/4 feet.

<u>EB4</u> was advanced only 1-1/2 feet through 1/2-foot of dark gray Clayey silt into light brown fine to medium weathered Sand Stone bed rock. No hydrocarbon odor was noted and no sample was collected. No sample was retained in the sampler.

EB5 was completed at a depth of 3-3/4 feet. Approximately 1/4-foot of dark gray, Clayey Silt was found above a 2-1/2-foot layer of fine to medium grained, light brown, Sandy fill. The Sandy fill was underlain by a grayish brown to light brown, fine to medium grained weathered Sand Stone bed rock. The Sand Stone bed rock was moderately jointed and showed the presence of dark brown oxidation rinds. No hydrocarbon odor was noted. Soil sample EB5-3-3/4 was collected at a depth of 3-1/4 to 3-3/4 feet.

<u>EB6</u> was advanced to a depth of 2 feet. Approximately 1/4-foot of cement concrete was found above a 1/2-foot layer of fine to medium, Sandy fill, which was underlain by the fine to medium weathered Sand Stone bed rock. No hydrocarbon odor was noticed and no sample was collected. No sample was retained within the sampler.

<u>EB7</u> was advanced only to a depth of 1-3/4 feet. Approximately 1/4-foot of cement concrete was found above 1/4-foot of dark gray clayey silt. A fine to medium, light brown weathered Sand Stone bed rock underlies it. No hydrocarbon odor was noticed and no sample was collected. No sample was retained within the sampler.

#### 6.0) SAMPLING METHODOLOGY

Soil samples were collected using a California-modified split-barrel sampler. Samples were removed from the sampler as soon as it was opened, and the ends of the brass liners containing soil designated for laboratory analysis were wrapped with aluminum foil and sealed with plastic caps. Duct tape was wrapped around the cap at its join with the liner to reduce the loss of volatile constituents. The sample tubes were labelled, stored on ice, maintained, transferred, and delivered to a certified analytical laboratory in keeping with chain of custody procedures. The sampler was washed with phosphate free detergent and rinsed with distilled water between the collection of samples.

#### 7.0) SAMPLE ANALYSIS

The chosen samples were analyzed at Anametrix, Inc., a certified hazardous materials testing laboratory (HMTL #151). Samples EB2-8', EB3-2-1/4', and EB5-3-1/4' were subsequently analyzed for TPH calculated as diesel using a modified EPA method 8015, and TOG using method 5520 B&F.

**Coates Property** 

33 La Salle Ave. Piedmont, CA

Analytical methods used by Anametrix, Inc. were consistent with the San Francisco Regional Water Quality Control Board (SFRWQCB) guidelines and approved analytical methodologies specified in EPA document SW-846.

#### 8.0) RESULTS OF ANALYSES

Copies of the laboratory reports and chain of custody documentation maintained during transportation of the samples are included in Appendix B. The results of analyses are presented in this section and summarized in Table 1.

Sample EB2-8' was found to contain 150 ppm of TPH as heating oil and 250 ppm of Total Oil & Grease.

Sample EB3-3-3/4' was not found to contain any of the constituents analyzed for at levels exceeding the stated laboratory detections limits.

Sample EB5-3-1/4' was not found to contain any of the constituents analyzed for at levels exceeding the stated laboratory detections limits.

#### 9.0) CONCLUSIONS

The upper 1-1/2-feet of the cores extracted during progression of this scope of work showed a loose soil with gravel and/or asphalt pieces throughout. Below this layer, to a depth of 8 feet, were less porous zones consisting of various degrees of silty sand with clay bindings, clayey silts, silty clays, and sandy silts interlaced with gravel.

The results of analyses performed on soil sample EB2-8', taken from core EB3, indicated that concentrations of impacting constituents in excess of typically enforced action limits exist in the subsurface of the site. Field observations made at the time of coring advancement and sample collection support the analytical results. A strong to moderate hydrocarbon odor was noted in the sandstone bedrock reclaimed from at this depth.

The exploration initiated at the location of EB1, placed in an obvious downslope position from the approximated previous position of the removed
UST. Bedrock was encountered and penetrated to the deepest depth
accessible with the available equipment. When no apparent signs of
hydrocarbon impact were discovered, vertical coring and sampling was
continued in an up-slope direction as far as EB3 where possible indications
of the presence of fuel hydrocarbons were encountered. Coring EB4
resulted in refusal at a depth of only 1-1/2 feet. The presence of an
overhead structure prevented the placement of further up-slope sample
locations. In an attempt to access soil in from the subsurface in this
direction, the angle of coring was adjusted to slant from the position of EB5
to an estimated location of approximately 4 feet further up-slope from EB4.
No obvious signs of hydrocarbon impact were noted in the observed core
prior to refusal without a retained sample at an estimated maximum depth of
3-3/4 feet.

Two corings were placed on the neighboring property to the north and east of the property line (EB6 and EB7). Bedrock was encountered resulting in refusal at a depth of 2 feet in EB6 and at 1-1/2 feet in EB7. No sample was retained from either core. No obvious signs of impact from heating oil were observed at either location. Subsequent attempts at probing the depth to bedrock along the property line, using a hand-auger and digging-bar, resulted in solid refusal at depths of less than 2 feet in several locations to the southeast of EB7.

#### 10.0) RECOMMENDATIONS

The scope of the exploration outlined in this report was performed to attempt definition of the vertical and lateral limits of hydrocarbon impact exerted by a previously removed UST used to contain heating oil. From the gathered sampling data, it appears that a limited volume of hydrocarbon impacted material remains to the northwest (up-slope side) of the former UST location. The observed impact was noted in the upper layer of the sandstone bedrock from the location of core EB3 only. Sample locations from both up-slope and down-slope, as well as from the adjacent neighboring property failed to replicate this result.

We recommend that excavation be performed in the area indicated by core EB3. If the results of this exploration are representative, it is likely that the lateral extent of impact is extremely limited. The vertical extent of impact remains undefined at this time. Excavation of this area would present the possibility of observing fuel migration patterns, if any, and would allow an evaluation of the influence exerted on these patterns by the subsurface portion of the adjacent wall of the residence.

Since no documentation exists concerning the collection and analysis of soil samples taken at the time of the removal of the tank, we suggest that excavation and sampling be expanded to include the tank pit area. Although analysis of soil sample EB3-2-1/4', taken from within what was approximated to have been the tank depression (EB2), revealed no detectable concentrations of impacting constituents, we believe that further analyses are warranted in view of the alleged undocumented results forwarded by Accutite.

We recommend that you forward copies of this report to the regulatory agencies and representatives listed below. Copies of this report have been included for this purpose. It is important that a signed cover letter from you be included with each forwarded report.

California Regional Water Quality Control Board San Francisco Bay Region 1800 Harrison Street, Suite 3 Oakland, CA 94559 ATTN: Richard C. Hiett

Alameda County Health Agency Division of Hazardous Materials Dept. of Environmental Health 80 Swan Way, Room 200 Oakland, CA 94621 ATTN: Larry Seto

#### 11.0) LIMITATIONS

The recommendations in this report were developed in accordance with generally accepted standards of current environmental practice in Northern California. These recommendations are time-dependant and should not be considered valid after one year from the date of issue of this report. After the one year period, site conditions and these recommendations should be reviewed.

This exploration was done solely for the purpose of evaluating environmental conditions of the soil related to hydrocarbon product contamination at the subject site. No soil engineering or geotechnical references are implied or should be inferred.

Evaluation of the conditions of the site, for the purposes of this study, was made from a limited number of observation points. Subsurface conditions may deviate away from these points. Additional work, including further study of the subsurface, can reduce the inherent uncertainties associated with this type of study.


This study was performed and the report was prepared for the sole use of our client, Ms. Dorothy Coates. It is the responsibility of the Client to convey these recommendations to regulatory agencies and other parties, as appropriate.

The recommendations herein are professional opinions that our firm has endeavored to provide with competence and reasonable care. We are not able to eliminate the risks associated with environmental work. No guarantees or warrants, express or implied, are provided regarding our recommendations.

TABLE 1 - ANALYTICAL RESULTS FOR SOIL SAMPLES (results in mg/L)

CORE #	SAMPLE #	TPH AS HEATING OIL	TOTAL OIL AND GREASE
EB2	EB3-2-1/4'	ND	ND
EB3	EB2-8'	150	250
EB5	EB5-3-1/4'	ND	ND

\* ND = Analyte not detected. Note: Detection limits used - TPH as diesel = 10 mg/L, TOG = 30 mg/L.



Source: USGS Topographic Map SW/4 Concord Quandrangle

SCALE - 1:24000



#### ENVIRONMENTAL BIO-SYSTEMS, INC.

Innovative Solutions for a Better Environment


30028 Industrial Pkwy., S.W. Suite C Hayward, CA 94544 **DATE: AUG 1991** 

DRWN BY: SLS

APPRVD: TMB

FIGURE 1: SITE LOCATION MAP

Coates Property 33 LaSalle Ave. Piedmont, CA



## **EXPLANATION**

EB7 - Location of Core Sample

NOTE: All property boundaries not shown.



SCALE - 1'' = 15'



ENVIRONMENTAL BIO-SYSTEMS, INC.

Innovative Solutions for a Better Environment

30028 Industrial Pkwy., S.W. Suite C Hayward, CA 94544 DATE: 9/10/91

DRWN BY: HA

APPRVD: TMB

FIGURE 2- Site Diagram

Coates Property 33 La Salle Ave. Piedmont, CA

Apx. A

APPENDIX A

LOGS OF BORINGS

				SO	IL BO	RING I	LOG		
ນວ	RING DESI	IGNATIO	N: <u>E</u> F	B1		MONITORING WELL INSTALLED:			
DA	TE OF DRI	iLLING:	8/	29/91		WELL DIAMETER:			
CV	SING TYPE	š:				SLOT SIZ	LE:		
LO	GGED BY:		AII	<u> </u>		SIGNATU	IRE:		
RE	GISTRATIC	)N:				EXPIRAT	ION:		
DEPTH (FEET)	SAMPLE NO.	BLOW CNT.	P.I.D.	GRAPHIC LOG	SOIL TYPE	WELL CONST.	DESCRIPTION AND REMARKS	-	
-0-					GM		Gravel with Silt, grayish brown, loose, hydrocarbon odor, Gravelly fill.	no	
-1-					SAND STN.	{	Fine to medium Sand with traces of clay		
-2-							bindings, grayish brown to light brown, presence of dark brown oxidation rinds,		
-3-							jointed, slightly moist, dense, no hydrocarbon odor, weathered Sand Ston		
-4-	,			}			bed rock.	<del></del>	
-5-				,			BOTTOM OF BORING AT 2-1/2'		
-6-									
-7-									
-8-	ļ							İ	
-9-								,	
-10-								İ	
-11-			. <b>[</b>					ļ	
-12-			}						
-13-		}		i					
-14-			Í						
-15-			}					ļ	
-16-			{			,		j	
-17-									
-18-					i				
-19-									
-20-									
EB5	ENVIRON Innovative : 30028 In	Solutions l	for a Bette	/STEMS, INC. er Environment /.	j Job		N: 9/4/91 SITE:  Coates Property 33 LaSalle Ave. Pledmont, CA		

APP'D BY: TMB

30028 Industrial Pkwy., S.W. Suite C

Hayward, CA 94544

#### SOIL BORING LOG EB2 MONITORING WELL INSTALLED: \_\_\_\_\_ BORING DESIGNATION: \_\_\_\_ DATE OF DRILLING: <u>8/29/91</u> WELL DIAMETER: \_\_\_\_\_\_ \ CASING TYPE: SLOT SIZE: LOGGED BY: HA SIGNATURE: EXPIRATION: \_\_\_\_\_ REGISTRATION: \_\_\_\_\_ SAMPLE GRAPHIC SOIL DEPTH BLOW WELL P.I.D. DESCRIPTION AND REMARKS TYPE LOG CONST. NO. CNT. (FEET) -0-GM Gravel with Silt, grayish brown, loose, no hydrocarbon odor, Gravelly fill. -1-SP Fine to medium Sand with traces of clay bindings, occasional presence of Gravel -2sized rocks, grayish brown to light brown, absence of oxidation rinds and joints, -3slightly moist, medium dense, no hydrocarbon odor, Sandy fill. -4--5--6--7--8-BOTTOM OF BORING AT 8' -9--10--11--12--13--14--15--16--17--18--19--20-

and the same	
留字	

ENVIRONMENTAL BIO-SYSTEMS, INC.

Innovative Solutions for a Better Environment

30028 Industrial Pkwy., S.W. Sulte C Hayward, CA 94544 DATE DRAWN: 9/4/91

JOB NO: 060-180-01

DRAWN BY: HA

APP'D BY: TMB

SITE:

Coates Property 33 LaSalle Ave. Piedmont, CA

					SO	L BO	RING I	LOG
во	RING	DESI	GNATIO	N:	EB3		MONITOR	RING WELL INSTALLED:
DΛ	TE OF	DRI	LLING:	8/	29/91	·	WELL DI	AMETER:
Сл	SING T	TYPE	:	····			SLOT SIZ	E:
Lo	GGED	BY:		НА			SIGNATU	RE:
RE	GISTR	ATIO	N:				EXPIRAT	ION:
DEPTH (FEET)	SAMP NO		BLOW CNT.	P.I.D.	GRAPHIC LOG	SOIL TYPE	WELL CONST.	DESCRIPTION AND REMARKS
-0-						ML		Clayey Silt, dark gray, moist, slightly cohesive, topsoil.
-1-						an l		Fine to medium Sand with traces of clay
-2-						SP		bindings, occasional presence of Shale
-3-		 				 		fragments, whitish brown to light brown, absence of oxidation rinds and joints, slightly moist, medium dense, no
-4-								hydrocarbon odor, Sandy fill.
-5-		<u> </u> 				SAND STN.		Fine to coarse Sand with traces of clay bindings, grayish brown to light greenish brown, presence of dark brown oxidation
-6-								rinds, jointed, moist, dense, presence of hydrocarbon odor at 3-3/4', weathered Sand
-7-						}		Stone bed rock.
-8-	İ							BOTTOM OF BORING AT 4-1/4'
-9-								
-10-								,
-11-								
-12-								
-13-								
-14-								
-15-								
-16-	ļ				II.			
-17-								
-18-	 		}					
-19-								
-20-	.			ļ			!	



# ENVIRONMENTAL BIO-SYSTEMS, INC.

Innovative Solutions for a Better Environment

30028 Industrial Pkwy., S.W. Sulle C Hayward, CA 94544

DATE DRAWN: <u>9/4/91</u>

JOB NO: 060-180-01

HA DRAWN BY: \_\_\_

APP'D BY: \_\_\_\_ TMB SITE:

Coates Property 33 LaSalle Ave. Piedmont, CA

#### SOIL BORING LOG BORING DESIGNATION: \_\_\_EB4 MONITORING WELL INSTALLED: \_\_\_\_\_ DATE OF DRILLING: 8/29/91 WELL DIAMETER: CASING TYPE: \_\_\_\_\_ SLOT SIZE: LOGGED BY: HA SIGNATURE: EXPIRATION: REGISTRATION: \_\_\_\_ GRAPHIC SOIL DEPTH SAMPLE BLOW WELL P.I.D. DESCRIPTION AND REMARKS TYPE CONST. LOG (FEET) NO. CNT. -0-ML Clayey Silt, dark gray, moist, slightly cohesive, some rootlets, topsoil. SAND -1-STN. Fine to medium Sand with traces of clay bindings, gravish brown to light brown, -2presence of dark brown oxidation rinds, jointed, slightly moist, dense, no -3hydrocarbon odor, weathered Sand Stone -4bed rock. -5-BOTTOM OF BORING AT 1-1/2' -6--7--8--9--10--11--12--13--14--15--16--17--18--19--20-



# ENVIRONMENTAL BIO-SYSTEMS, INC.

Innovative Solutions for a Better Environment

30028 Industrial Pkwy., S.W. Sulle C Hayward, CA 94544 DATE DRAWN: <u>9/4/91</u>

JOB NO: 060-180-01

DRAWN BY: HA

APP'D BY: TMB

SITE:

Coates Property 33 LaSalle Ave. Piedmont, CA

BC	ORING DESI	GNATIO	א: <u>F</u>	JB5		MONITOF	RING WELL IN	STALLED:		
	ATE OF DRI					WELL DIAMETER:				
C	ASING TYPE	::		····		SLOT SIZ	SIS:			
L	OGGED BY:		НА	<u> </u>		SIGNATU	RE:			
. RI	EGISTRATIO	)N:			· · · · · · · · · · · · · · · · · · ·	EXPIRATION:				
DEPTH (FEET)	SAMPLE NO.	BLOW CNT.	P.I.D.	GRAPHIC LOG	SOIL TYPE	WELL CONST.	DESCRI	IPTION AND REMARKS		
-0-					ML			dark gray, moist, slightly		
-1-			1					me rootlets, topsoil.		
-2-					SP		bindings, gray absence of ox	orn Sand with traces of clay yish brown to light brown, kidation rinds and joints,		
-3-					SAND STN.		slightly moist	t, medium dense, no odor, Sandy fill.		
-4-				1	}	!		~ 1 11		
-5-							bindings, gra	um Sand with traces of clay syish brown to light brown, lark brown oxidation rinds,		
-0- -7-			ľ	1			jointed, slight hydrocarbon	odor, weathered Sand Stone		
-8-				1			bed rock.			
-9-							воттом ог	F BORING AT 3-3/4'		
-10-			1	1						
-11-										
-12-		1	, }	1	1	1				
-13-										
-14-				1		, }				
-15-						i		ļ		
-16-		1		1		,				
-17-										
-18-			ļ	i						
-19-										
-20-										
CDI				YSTEMS, INC. er Environment	DA?	re drawn	N: <u>9/4/91</u> )-180-01	SITE: Coates Property		

SOIL BORING LOG



30028 industrial Pkwy., S.W. Sulle C Hayward, CA 94544

DRAWN BY: HA

TMB APP'D BY: \_\_\_\_

33 LaSalle Ave. Piedmont, CA

					SOI	L BO	RING I	LOG		
ВС	DRING	DESI	GNATIO	N:E	EB6		MONITORING WELL INSTALLED:			
D/	ATE OF	DRI	LLING:	8/	29/91		WELL DI	AMETER:		
								E:		
								RE:		
								ION:		
			·	<del></del>	<u> </u>					
EPTH EET)	SAMI NO		BLOW CNT.	P.I.D.	GRAPHIC LOG	SOIL TYPE	WELL CONST.	DESCRIPTION AND REMARKS		
-0-		ļ	ļ			SP		Cement Concrete.		
-1-				<b></b>		SAND STN.		Fine to medium Sand with traces of clay bindings, grayish brown to light brown, absence of oxidation rinds and joints,		
-2-								slightly moist, medium dense, no hydrocarbon odor, Sandy fill.		
-4-								Fine to medium Sand with traces of clay bindings, grayish brown to light brown, presence of dark brown oxidation rinds,		
-5- -6-								jointed, slightly moist, dense, no hydrocarbon odor, weathered Sand Stone bed rock.		
-7-								BOTTOM OF BORING AT 2'		
-8-	]   									
-9- -10-										
-11-										
-12-										
-13-										
-14-				İ						
-15-				:						
-16-							:			
-17- -18-							;			
-19-		!				ļ				
-20-	· .		Í				Ì			
v · 1										



# ENVIRONMENTAL BIO-SYSTEMS, INC.

Innovative Solutions for a Better Environment

30028 Industrial Pkwy., S.W. Sulte C Hayward, CA 94544 DATE DRAWN: 9/4/91

JOB NO: 060-180-01

DRAWN BY: HA
APP'D BY: TMB

SITE:

Coates Property 33 LaSalle Ave. Piedmont, CA

					SO	IL BO	RING I	LOG
вс	RING	DESI	GNATIO	N: <u>E</u>	EB7	MONITOR	RING WELL INSTALLED:	
DA	DATE OF DRILLING: 8/29/91							AMETER:
CA	SING '	TYPE	:				SLOT SIZ	E:
LO	GGED	BY:		НА			SIGNATU	RE:
. RI	EGISTR	OITA	N:				EXPIRAT	ION:
DEPTH FEET)	SAMI N		BLOW CNT.	P.I.D.	GRAPHIC LOG	SOIL TYPE	WELL	NUCCHINATON AND DIMENTIC
-0-						ML		Cement Concrete.
-1-						SAND STN.		Clayey Silt, dark gray, moist, slightly cohesive, some rootlets, topsoil.
-2-								Fine to medium Sand with traces of clay bindings, grayish brown to light brown,
-4-							la la la la la la la la la la la la la l	presence of dark brown oxidation rinds, jointed, slightly moist, dense, no hydrocarbon odor, weathered Sand Stone
-5-								bed rock.
-6- -7-	l							BOTTOM OF BORING AT 1-3/4'
-8-							!	
-9-								
-10-							li:	
-11-								
-12-								
-13-								
-14-								
-15-								
-16-	;							
-17- -18-	1							
-19-							;	
-20-					!		ļ	
		k	···				717 D.D. 4 3 EV	s. 9/4/91 SITE:

anni	١
EB5	,

ENVIRONMENTAL BIO-SYSTEMS, INC. Innovative Solutions for a Better Environment

30028 Industrial Pkwy., S.W. Sulfe C Hayward, CA 94544

JOB NO: 060-180-01

ΗА DRAWN BY: \_\_

TMB APP'D BY: \_\_\_\_

Coates Property 33 LaSalle Ave. Piedmont, CA

### APPENDIX B

LABORATORY REPORTS &
CHAIN OF CUSTODY DOCUMENTATION
FOR SOIL SAMPLES

# REPORT SUMMARY ANAMETRIX, INC. (408)432-8192

MR. TIM BABCOCK ENVIRONMENTAL BIO-SYSTEMS

30028 INDUSTRIAL PARKWAY.S.W., SUITE C

HAYWARD, CA 94544

Workorder # : 9108335 Date Received : 08/30/91 Project ID : 060-180-01

Purchase Order: N/A
Department : GC
Sub-Department: TPH

#### SAMPLE INFORMATION:

ANAMETRIX SAMPLE ID	CLIENT SAMPLE ID	MATRIX	DATE SAMPLED	METHOD
9108335- 1	EB2-8 '	SOIL	08/30/91	TPHd
9108335- 2	EB3-2.25'	SOIL	08/30/91	TPHd
9108335- 3	EB5-3.25'	SOIL	08/30/91	TPHd

# REPORT SUMMARY ANAMETRIX, INC. (408)432-8192

MR. TIM BABCOCK ENVIRONMENTAL BIO-SYSTEMS 30028 INDUSTRIAL PARKWAY.S.W., SUITE C HAYWARD, CA 94544

Workorder # : 9108335
Date Received : 08/30/91
Project ID : 060-180-01

Purchase Order: N/A
Department : GC
Sub-Department: TPH

#### QA/QC SUMMARY :

- Samples EB2-8', EB3-2.25', and EB5-3.25' were analyzed using a diesel standard calibration. Due to the similarities between heating oil and diesel fuel, the response factors for both standards should be very similar. The hydrocarbon pattern seen in the chromotogram for sample EB2-8' appears to be that of heating oil, not diesel fuel.

Department Supervisor Date

Acces Stor 9/4/9/
Chemist Date

#### ANALYSIS DATA SHEET - TOTAL PETROLEUM HYDROCARBONS AS DIESEL ANAMETRIX, INC. (408) 432-8192

Anametrix W.O.: 9108335 Matrix : SOIL Date Sampled : 08/30/91 Matrix Date Extracted: 09/03/91

Project Number: 060-180-01 Date Released: 09/04/91

Instrument I.D.: HP23

Anametrix I.D.	Client I.D.	Date Analyzed	Reporting Limit (mg/Kg)	Amount Found (mg/Kg)
9108335-01	EB2-8 *	09/03/91	10	150
9108335-02	EB3-2.25'	09/03/91	10	ND
9108335-03	EB5-3.25'	09/03/91	10	ND
DSBL090391	METHOD BLANK	09/03/91	10	ИD

Note: Reporting limit is obtained by multiplying the dilution factor times 10mg/Kg.

ND - Not detected at or above the practical quantitation limit for the method.

TPHd - Total Petroleum Hydrocarbons as diesel is determined by GCFID following sample extraction by EPA Method 3550.

All testing procedures follow California Department of Health Services (Cal-DHS) approved methods.

Lucia Suga Analyst

#### TOTAL EXTRACTABLE HYDROCARBON METHOD SPIKE REPORT EPA METHOD 3550 WITH GC/FID ANAMETRIX, INC. (408) 432-8192

Sample I.D. : 060-180-01 EB5-3.25'
Matrix : SOIL
Date Sampled : 08/30/91
Date Extracted: 09/03/91

Date Analyzed: 09/03/91

Anametrix I.D.: 9108335-02
Analyst: IS
Supervisor: CF3
Date Released: 09/04/91
Instrument I.D.: HP 23

COMPOUND	SPIKE AMT. (mg/Kg)	MS (mg/Kg)	%REC MS	MSD (mg/Kg)	%REC MSD	RPD	%REC LIMITS
Diesel	125	110	888	110	88%	0%	38-123

<sup>\*</sup> Limits established by Anametrix, Inc.

#### REPORT SUMMARY ANAMETRIX, INC. (408)432-8192

MR. TIM BABCOCK ENVIRONMENTAL BIO-SYSTEMS

30028 INDUSTRIAL PARKWAY.S.W., SUITE C

HAYWARD, CA 94544

Workorder # : 9108335
Date Received : 08/30/91
Project ID : 060-180-01
Purchase Order: N/A
Department : PREP

Sub-Department: PREP

#### SAMPLE INFORMATION:

ANAMETRIX SAMPLE ID	CLIENT SAMPLE ID	MATRIX	DATE SAMPLED	METHOD
9108335- 1	EB2-8'	SOIL	08/30/91	5520EF
9108335- 2	EB3-2.25'	SOIL	08/30/91	5520EF
9108335- 3	EB5-3.25'	SOIL	08/30/91	5520EF

# REPORT SUMMARY ANAMETRIX, INC. (408)432-8192

MR. TIM BABCOCK ENVIRONMENTAL BIO-SYSTEMS 30028 INDUSTRIAL PARKWAY.S.W., SUITE C HAYWARD, CA 94544 Workorder # : 9108335
Date Received : 08/30/91
Project ID : 060-180-01

Purchase Order: N/A
Department : PREP
Sub-Department: PREP

QA/QC SUMMARY :

- No QA/QC problems encountered for samples.

ersorbitu.

Supt, 4th 1991.

Department Supervisor

Date

t. Relet

201-04-91

Date

PREP/PREP - PAGE 2

# ANALYSIS DATA SHEET - TOTAL OIL AND GREASE ANAMETRIX, INC. (408) 432-8192

Project # : 060-180-01
Matrix : SOIL
Date sampled : 08/30/91
Date ext. TOG: 09/03/91
Date anl. TOG: 09/03/91

Anametrix I.D. : 9108335
Analyst : 100 : 9108335
Supervisor : 100 : 9108335
Supervisor : 100 : 9108335

  Workorder #	Sample I.D.	Reporting Limit (mg/Kg)	Amount Found (mg/Kg)
9108335-01	EB2-8'	30	250
9108335-02  .	EB3-2.25'	30	ир [
9108335-03	EB5-3.25'	30	du
GSBL090391	METHOD BLANK	30	ND

ND - Not detected at or above the practical quantitation limit for the method.

TOG - Total Oil & Grease is determined by Standard Method 5520E&F.

All testing procedures follow California Department of Health Services (Cal-DHS) approved methods.

#### TOTAL OIL AND GREASE MATRIX SPIKE REPORT STANDARD METHOD 5520EF ANAMETRIX, INC. (408) 432-8192

Anametrix I.D.: 9108335-03

Sample I.D. : 060-180-01 EB5-3.25'
Matrix : SOIL
Date sampled : 08/30/91
Date extracted: 09/03/91
Date analyzed : 09/03/91

Analyst APP Supervisor

Date Released: 09/04/91

Motor Oil 300 267 89% 267 89% 0% 48-114	COMPOUND	SPIKE AMT. (mg/Kg)	MS (mg/Kg)	%REC MS	MSD (mg/Kg)	%REC MSD	%RPD	% REC LIMITS
	Motor Oil	300	267	89%	267	89%	0%	48-114%

<sup>\*</sup> Quality control limits established by Anametrix, Inc.

4444	
<b>FBF</b>	

### **ENVIRONMENTAL BIO-SYSTEMS, INC.**

Innovative Solutions for a Better Environment 30028 Industrial Pkwy., S.W.

Suite C Hayward, CA 94544  PROJECT NUMBER  O 60-180-01  CLIENT  DOROTHY Contes  SITE  33 LaSalle AVE PERMONT, CA			COMPOSITE	Mr as Hearling Oil	06-by 5500 BZF				M ES O C	METHODS AND DETECTION LIMITS ESTABLISHED BY REGION OF THE STATE WATER RESOURCES CONTROL BOARD.  INSTRUCTIONS:  # ASAP A8 hr if necessary		
SAMPLE I.D.	MATRIX	NUMBER OF CONTAINERS	8	1						TURNAROUND	SAMPLE CONDITION	LABSAMPLE#
FB2-8'	S			0	0				5	Ahrt		all samples
E133-2/4	S			0	1				á	460+		are cold
EBS-3'4'	S			0	1				2	9hrx		brace linear
												container
												No head-
												spare in
												intene.
												ð
SAMPLING COMPLETED S 20 19	TIME SAMP	LING ORMED BY Tin	1B	aba	ock	•	* 1	1111				
RELEASED BY	1113L		ATE		TIME 1540		RECEIV	ED BY Fasa	zh Bui	Asi `	0/30/9	15:40
RELEASED BY	$\bigcirc$		ATE		TIME	<del></del>	RECEIV				DATÉ	TIME
RELEASED BY		ļ c	ATE		TIME		RECEIV	ED BY	<del></del>		DATE	TIME
SHIPPED VIA			ATE SE	NT TA	TIME SENT	COOLER	#				······································	

**CHAIN OF CUSTODY** 

ANALYSIS