SOIL/GROUNDWATER MITIGATION AND CLOSURE 5800 CHRISTIE STREET EMERYVILLE, CALIFORNIA

MAY 22, 1989



McLaren Environmental Engineering



McLaren Environmental Engineering

May 22, 1989

Mr. Steve G. Croley Croley & Herring Investment Co. 1311 63rd Street Emeryville, CA 94608 Mr. Gregg Steele The Good Guys, Inc. 1649 Adrian Road Burlingame, California 94010

SUBJECT: SOIL/GROUNDWATER MITIGATION AND CLOSURE, 5800 CHRISTIE STREET, EMERYVILLE, CALIFORNIA

Dear Mr. Croley and Mr. Steele:

This letter presents the following topics in regard to the subject facility:

- · Previous Soil Investigation,
- Foundation Excavation Area Soil Analysis,
- Contaminated Soil Excavation/Treatment,
- · Groundwater Investigation Results,
- · Ambient Air Monitoring, and
- Projected Soil and Groundwater Remediation Cost.

Previous Soil Investigation

A soil investigation of the subject facility was previously performed by Robert Gils & Associates and a site assessment report was prepared on January 20, 1989. A total of 17 soil borings were drilled (Figure 1). A copy of the Gils report was appended in McLaren's April 5, 1989 report entitled "Source Area Soil Remediation Plan". A summary of the soil analysis results were presented as Tables 2-1, 2-2 and 2-3 in the McLaren's report. Significant soil contamination was detected at soil boring locations #1, #2, #3, and #4.

Foundation Excavation Area Soil Analysis

The proposed Good Guys Store construction plan includes demolition of foundation footings on the north side of the existing building and construction of new foundations on the southern half of the existing parking lot (Figure 1). Eleven soil sample locations were proposed within

980 Atlantic Avenue, Suite 100, Alameda, CA 94501 (415) 521-5200 Headquarters: 11101 White Rock Road, Rancho Cordova, CA 95670 (916) 638-3696

the foundation excavation area. A total of 9 soil samples were collected and analyzed for EPA 8240 volatile organic compounds (VOCs). Soils were sampled to a depth of about 3 feet below grade. The detected total VOCs were less than 0.5 parts per million (ppm). Laboratory analysis results are included in Attachment 1.

Contaminated Soil Excavation & Treatment

On April 5, 1989, McLaren submitted a source area soil remediation plan to the Alameda County Health Care Services (lead agency for soil remediation) for review. Approval for the implementation of the on-site soil excavation and remediation was obtained on April 13, 1989 (Attachment 2).

Prior to the source area soil excavation, permission for access was obtained from the adjacent land owner (F.P. Lathrop Co.) and the California Department of Health Services (CDOHS). In addition, full cooperation was obtained from Mr. Ric Notini and Mr. Dave Anderson of CDOHS on site clearance and the health and safety plan for excavation.

During May 1, 1989 through May 4, 1989, the source area soil was excavated and stockpiled at the soil treatment area. A soil sample collected on the north side wall (A-1) of the excavation detected less than 0.5 ppm VOCs. A south side wall soil sample (E-2) did not detect any VOCs. A total of about 80 cubic yards of contaminated soil was excavated and the excavation was backfilled and compacted to specification. The excavated soil was placed on a lined surface and covered with plastic sheets. The soil is presently awaiting treatment.

Prior to the soil excavation, the Bay Area Air Quality Management Board (BAAQMD) was notified in accordance to BAAQMD Regulation 8, Rule 40 as amended February 15, 1989 (Attachment 2). Also prior to initiation of soil treatment, advance notice will be provided to BAAQMD in accordance to BAAQMD Regulation 8, Rule 40.

The anticipated soil treatment will start May 15, 1989 and the projected treatment duration is about 8 weeks. The exact duration of treatment will depend on soil conditions and initial total volatile organic concentrations. The proposed cleanup level of 50 ppm for total VOCs was approved by the Alameda County Health Care Service on April 5, 1989.



Groundwater Investigation Results

Initially, three shallow groundwater monitoring wells were installed and were named as MW-1, MW-2 and MW-3 (Figure 1). The associated well logs and construction details are included in Attachment 3.

Groundwater samples were collected from these wells and analyzed for EPA 8240 VOCs. Results of the laboratory analyses are included in Attachment 4. No VOCs were detected in wells MW-2 and MW-3. Only 2 VOCs were detected at Well MW-1 and they were 1,1-DCA and 1,2-DCE. The detected concentrations for both VOCs were 9 parts per billion (ppb).

A groundwater level survey was performed on April 25, 1989 and the groundwater table elevations at MW-1, MW-2 and MW-3 were 3.31, 3.11 and 2.99 feet above mean sea level, respectively. The groundwater flow direction was estimated as southwest towards the bay with a hydraulic gradient of 0.00145. Well MW-3 is the downgradient well.

Ambient Air Monitoring

Two separate rounds of air monitoring were conducted inside the existing building (formerly occupied by Fisher Berkeley) on 5/5/89 and 5/8/89 with OVM equipment. The organic vapor levels detected were below 2 ppm, which is the background level in open air. Specific OVM readings were also taken at boreholes 16 and 17 drilled during the Gils investigation. These boreholes are close to the source area. The OVM readings were below 2 ppm.

Projected Soil & Groundwater Remediation Cost

There may be residual concentrations of VOCs in soils along the excavation walls. Based on the low concentration of VOCs encountered in samples from boreholes 15, 16 and 17, the anticipated residual VOCs may be limited to below the footing of the building foundation. Vapor which volatilizes can be captured by a vapor extraction well system in the sandy backfill material and filtered through vapor phase carbon prior to emission. The proposed vapor venting system in the sandy backfill material will include about 4 vent wells to a depth of 5 feet with a 10 to 15 foot spacing between wells.



At boreholes 13 and 14, adjacent to the L. P. Lathrop fuel tank, the low level of gasoline detected (3 to 5 ppm TPH) in soil 11 feet deep will most likely not require remediation. Any vapor volatilization at these low concentrations will most likely be non-detectable by the time it reaches the ground surface.

A new groundwater extraction Well EW-1 was constructed on 5/5/89 in the source area after soil excavation and backfill were completed. A groundwater sample collected on 5/8/89 was analyzed for EPA 601 and 602 volatile organic compounds. The following volatile organic compounds were detected:

```
1,1 DCE 78 ppb (action level 6 ppb)
TCE 640 ppb (action level 5 ppb)
Toluene 190 ppb (action level 180 ppb)
Xylenes 170 ppb (action level 680 ppb)
```

McLaren has also taken two groundwater samples in the downgradient direction of extraction Well EW-1. One of the sample locations is located at the center of the former Fisher Berkeley facility, about 80 feet downgradient. No organic chemical compounds were detected. The other groundwater sample was taken at the southeast corner of the former Fisher Berkeley facility. Benzene was detected at 47 ppb. The state action level of benzene is 1 ppb. Because, benzene was not found at the source area, its origin at this location is most likely from an off-site source.

It is apparent from these results that the contaminants on-site have not significantly affected the shallow aquifer. However, the 1,1-DCE, TCE and toluene concentrations are above the state action level for groundwater cleanup. McLaren recommends a groundwater extraction/treatment system be installed to clean up the minor quantity of contaminant which was detected. The treatment system would be comprised of an aqueous phase activated carbon filter.

For estimation of the groundwater remediation cost, McLaren anticipates that the maximum plume has a 60 foot radius, a saturated thickness of 15 feet, and an effective porosity of 0.10. The estimated plume volume is about 127,000 gallons. About 63,500 gallons of the plume volume is estimated to be off-site and underlying the F.P. Lathrop property. Extraction Well EW-1 is capable of recovering the contaminated water off-site. The duration of treatment for one plume volume is estimated at 90 days assuming an extraction rate of 1 gallon per minute (1,440 gallons



per day). Assuming a total maximum VOC concentration in groundwater at 1 ppm, the amount of VOC in the groundwater plume is estimated at a maximum of 1.1 pounds. McLaren estimates that two 55-gallon drums of aqueous phase activated carbon would be needed to remove the VOCs. The regulatory agency will most likely require quarterly groundwater monitoring for 2 years after the cleanup level is achieved.

A summary of the projected soil and groundwater remediation costs for the subject site is presented in Table 1.

The total projected soil remediation cost is \$128,000. The initial groundwater remediation cost is projected to be \$45,000 plus 2 years of groundwater monitoring at \$60,000 if required. Therefore, total remediation costs are projected to be \$233,000 for the subject facility.

To date, all contaminated soil accessible to excavation equipment (about 80 cubic yards) located on the subject property was removed and stockpiled for treatment. A minor amount of contaminated soil located under the footing foundation will be remediated by the proposed vapor venting system. This vapor venting system will also be effective recovering organic vapor as far as 10 feet into the F.P. Lathrop property, and remediating residual contamination on the east wall (property line) of the excavation. In the highly unlikely case that the soil contamination extends 20 feet beyond the property boundary, the additional soil remediation cost for off-site soil vapor venting is estimated to be \$20,000. Based on the current soil and groundwater data and on our experience, the proposed soil remediation and groundwater extraction and treatment system will satisfy the requirements of the regulatory agency of concern (Alameda County Health Care Services and Regional Water Quality Control Board) for site closure.

The total maximum cost for on-site soil and groundwater remediation is \$173,000. The total maximum cost for off-site soil and groundwater remediation is \$80,000. This includes soil remediation 20 feet beyond the east boundary of the site. McLaren believes the above mentioned costs are maximum based on the investigation results to date.

Tables 2 and 3 summarize the soil/groundwater investigation and remediation work performed to date and to be performed in the future.



If you have any question about this letter, please contact us.

Sincerely,

Walter Loo, C.E.G. Principal Geohydrologist

James Vais, P.E. Supervising Engineer

0509adg1








TABLE 1
SUMMARY OF PROJECTED SOIL & GROUNDWATER REMEDIATION COST

Soil Remediation Cost	
Soil Remediation Plan	\$ 10,000
Soil Excavation	15,000
Soil Treatment System	
Piping & Liner	2,800
Air Management Unit (Carbon, blower, meters, etc.)	15,000
Soil Sample Analysis	13,500
Engineering/Operation/Maintenance	22,200
Organic Vapor Venting System	40,000
Health & Safety	5,500
Closure Report	4,000
•	\$128,000
Groundwater Investigation/Remediation Cost	
Investigation (5 wells)	\$ 25,000
Groundwater Extraction/Treatment	12,000
(1 well, carbon, piping, etc.)	
Groundwater Remediation Plan	6,000
Groundwater Sampling (60 samples, EPA 624)	20,000
Quarterly Monitoring Reports (2 years)	33,000
Groundwater Closure Plan	9,000
	\$105,000
PROJECTED TOTAL	\$233,000

0509ADG1

TABLE 2
SITE INVESTIGATION RESULTS

	ON SITE AREAS INSPECTED	VOC IDENTIFIED	ACTION LEVEL	REF. FOR FINDINGS	RECOMMENDED ACTION
SOIL	Area near Lathrop gasoline tank	TPH 3-5 ppm	N/A	RGA Findings In ACDOHS approved plan	None
	Inside building	Trace	N/A	RGA Findings	None
	Exterior of Bldg. Northern 1/2 near foundation	Trace	N/A	McLaren findings Attachment I in 5/19/89 letter	None
	Area Required for for foundation footings	Trace	N/A	McLaren findings Attachment I in 5/19/89 letter	None
	Alley Way	Various		RGA findings in ACDOHS plan	Soil Excavation and vapor venting
GROUNDWATER	N.W. corner of lot (MW-2)	Not detected	N/A	McLaren findings Attachment 3 5/19/89 letter	None
	S.W. corner of lot (MW-3)	Not detected	N/A	tt	None
	Mid lot on East (MW-1)	1,1-DCA 9 ppb 1,1-DCE 9 ppb	20 ppb 16 ppb	11	Extraction
	Middle of Fisher Berkeley (TW-2)	Not detected	N/A	New	None

TABLE 2
SITE INVESTIGATION RESULTS
(continued)

	ON SITE AREAS INSPECTED	VOC IDENTIFIED	ACTION LEVEL	REF. FOR FINDINGS	RECOMMENDED ACTION
GROUNDWATER	S.E. corner of Fisher Berkeley (TW-2)	Benzene 47 ppb	1 ppb	New	None
	Mid lot East (EW-1 source area)	1,1-DCE 78 ppb TCE 640 ppb Toluene 190 ppb Xylene 170 ppb	6 ppb 5 ppb 180 ppb 680 ppb	New	Extraction/ Treatment

0509adg1

TABLE 3

REMEDIATION OBJECTIVES

	PROBLEMS THAT REMAIN	EXTENT OF PROBLEM	REMEDIATION	TIME TO REMEDIATE	ESTIMATED COST
SOIL	Alley excavation and excavated walls ad- jacent Lathrop Property	Peripheral and 10' onto Lathrop Property	Venting Venting	3 - 6 months 3 - 6 months	\$ 128,000
	Worst cast on adja- cent Lathrop property	_	Venting	6 - 36 months	\$ 20,000 (over \$ 128,000)
	Excavated Soil	80 cu. yds. stockpiled on site	Soil Treatment	3 months	Included in \$ 128,000 above
GROUNDWATER	Mid alley on site	15' deep 60' radius	Extraction Well (EW-1)	3 months	\$ 105,000
	Adjacent Lathrop	127,000 gallons 1/2 on site 1/2 on Lathrop	Extraction (Well EW-1)	Same	

0509adg1

ATTACHMENT 1

FOUNDATION EXCAVATION SOIL ANALYSIS RESULTS

McLaren Analytical Laboratory Chain of Custody Record

Nº 211454

L. P. 1668

- HOJEOT L	DESIGNATION	CHI			SAI	MPLE TY			ENBY: Geri		
AREA	SAMPLE LO	CATION	DATE	TIME	WA	TED	6011	SAMPLE NO.	TYPE CONTAINER(S)		LYSIS JIRED
	\$ 10 3	3.5'	4-14-89				~	5228	Brasstube	8240	2 4/33
	114	3.5					V	5229	11	и	2-4139
	HA 9	3.51				1	V	5230	4(IJ	2 4/35
	HA6	3.51					V	5231	11	11	L Y/36
**	HA 5	マンフィ					V	5232	16	11	24/32
	HAT	3.51			: :		V	5233	п	• (24/38
	HA II		1				V	5234	10	11	24139
	HA 4			•	 		V	5235	<i>i</i> (17	24140
	HAF						V	5236	11	11	2414
		<u> </u>			<u> </u>						
IMMEDI STORAC	SHED BY:	ERATOR =				EIVED B			SECURED TYES	4-148	ЕЛІМЕ 7 /702 ЕЛІМЕ
5.	FOR LABORATOR	Fed E	₹				_			4 15 C	7 9 A-N
ABORATO	E ANALYSIS [SAM O kan	PLESOR	ECE	IVED TION	Į		EZER	78 ID <u>4 5</u> 28 □ ID <u>——</u> □ ID ———		SECURED VES NO

* PRINT NAME AFTER SIGNATURE



Project: CHIC 2.0 Lab ID: 24141

Sample Date

Location: HA1 2 1/4' Sampled: 04/14/89

Sample Date

Number: <u>5236</u> Analyzed: 04/24/89

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/kg	ug/kg
	(dqq)	(dqq)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	< 10	10.
Methylene Chloride	67.	25.
Acetone	< 5	25.
Carbon Disulfide	< 5	5.
1,1-Dichloroethene	< 5	5.
1,1-Dichloroethene	< 5	5.
1,2-Dichloroethene(cis/trans)	< 5	5.
Chloroform	< 5	5.
1,2-Dichloroethane	< 5	5.
2-Butanone	< 25	25.
1,1,1,-Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2-Dichloropropane	< 5	5.
Trans-1,3-Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2-Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis-1,3-Dichloropropene	_. < 5	5.
Bromoform	< 5	5.
4-Methyl-2-pentanone	< 25	25.
2-Hexanone	< 25	25.
1,1,2,2-Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	19.	5.
Chlorobenzene	< 5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylene	< 5	5.
Freon 113	< 5 /	5.
11m	7 4 1 2 1/1	

Reviewed By:

Date: 04/27/89

Laboratory Director:

TAMES

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	108	70-121
S2 = D8-Toluene	101	81-117
S3 = 4-Bromofluorobenzene	98	74-121

Comments:



Project: <u>CHIC 2.0</u> Lab ID: 24140

Sample Date

Location: HA4 2' Sampled: 04/14/89

Sample Date

Number: <u>5235</u> Analyzed: <u>04/23/89</u>

COMPOUND	ANALYTE <u>CONCENTRATION</u> ug/kg	REPORTING LIMIT ug/kg
<u>com comp</u>	(ppb)	(ppb)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	10	10.
Methylene Chloride	حر130 /	25.
Acetone	5	25.
Carbon Disulfide	< 5	5.
1,1-Dichloroethene	< 5	5.
1,1-Dichloroethene	< 5	5.
1,2-Dichloroethene(cis/trans)	< 5	5.
Chloroform	< 5	5.
1,2-Dichloroethane	< 5	5.
2-Butanone	< 25	25.
1,1,1,-Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2-Dichloropropane	< 5	5.
Trans-1,3-Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2-Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis-1,3-Dichloropropene	< 5	5.
Bromoform	< 5	5.
4-Methyl-2-pentanone	< 25	25.
2-Hexanone	< 25	25.
1,1,2,2-Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	160	5.
Chlorobenzene	5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylene	< 5	5.
Freon 113	5 2	5.
11211	K 11) clarely	

Reviewed By: Date: 04/27/89

Laboratory Director:

M. Bartell

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	104	70-121
S2 = D8-Toluene	111	81-117
S3 = 4-Bromofluorobenzene	102	74-121

Comments:



HA 5 WHY

Project: CHIC 2.0 Lab ID: 24137

Sample

Date Location: HA4 2.7' Sampled: 04/14/89

Sample

Date Number: Analyzed: <u>04/24/89</u> <u>5232</u>

	ANALYTE CONCENTRATION	REPORTINGLIMIT
COMPOUND	ug/kg	ug/kg
	(ppb)	(dqq)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	< 10	10.
Methylene Chloride	< 25	25.
Acetone	< 5	25.
Carbon Disulfide	< 5	5.
1,1-Dichloroethene	< 5	5.
1,1-Dichloroethene	< 5	5.
1,2-Dichloroethene(cis/trans)	< 5	5.
Chloroform	< 5	5.
1,2-Dichloroethane	< 5	5.
2-Butanone	< 25	25.
1,1,1,-Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2-Dichloropropane	< 5	5.
Trans-1,3-Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2-Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis-1,3-Dichloropropene	< 5	5.
Bromoform	< 5	5.
4-Methyl-2-pentanone	< 25	25.
2-Hexanone	< 25	25.
1,1,2,2-Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	80.	5.
Chlorobenzene	5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylene	< 5	5.
Freon 113	< 5	5.
1 arch (1	V 200	

Reviewed By:

Date: 04/27/89

Laboratory Director:

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	103	70-121
S2 = D8-Toluene	87	81-117
S3 = 4-Bromofluorobenzene	108	74-121

Comments:



Project: CHIC 2.0 Lab ID: 24136

Sample Date

Location: <u>HA6 3.5'</u> Sampled: <u>04/14/89</u>

Sample Date

Number: <u>5231</u> Analyzed: <u>04/24/89</u>

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/kg	ug/kg
	(dqq)	(ppb)
Chloromethane	< 50	50.
Bromomethane	< 50	50.
Vinyl Chloride	< 50	50.
Chloroethane	< <u>50</u>	50.
Methylene Chloride	(130)	125.
Acetone	< 125	125.
Carbon Disulfide	< 25	25.
1,1-Dichloroethene	< 25	25.
1,1-Dichloroethene	< 25	25.
1,2-Dichloroethene(cis/trans)	< 25	25.
Chloroform	< 25	25.
1,2-Dichloroethane	< 25	25.
2-Butanone	< 125	125.
1,1,1,-Trichloroethane	< 25	25.
Carbon Tetrachloride	< 25	25.
Bromodichloromethane	< 25	25.
1,2-Dichloropropane	< 25	25.
Trans-1,3-Dichloropropene	< 2 5	25.
Trichloroethene	< 25	25.
Benzene	< 25	25.
1,1,2-Trichloroethane	< 25	25.
Dibromochloromethane	< 25	25.
Cis-1,3-Dichloropropene	< 25	25.
Bromoform	< 25	25.
4-Methyl-2-pentanone	< 125	125.
2-Hexanone	< 125	125.
1,1,2,2-Tetrachloroethane	< 25	25.
Tetrachloroethylene	< 50	50.
Toluene	(120.	25.
Chlorobenzene	< 25	25.
Ethyl Benzene	< 25	25.
Styrene	< 25	25.
Total Xylene	< 25	25.
Freon 113	< 25	25.
110.	The contract of the contract o	

Analyst:

Mony by Reviewed By:

 $\overline{}$

Date: 04/27/89

Laboratory Director:

<u>McLaren</u>

J. M. Bartel

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	104	70-121
S2 = D8-Toluene	92	81-117
S3 = 4-Bromofluorobenzene	96	74-121

Comments: 1:5 dilution used in analysis.



Project: CHIC 2.0 Lab ID: 24138

Sample Date

Location: <u>HA7 3.5'</u> Sampled: <u>04/14/89</u>

Sample

Number: <u>5233</u> Analyzed: <u>04/24/89</u>

	ANALYTE	REPORTING
	CONCENTRATION	LIMIT
<u>COMPOUND</u>	ug/kg	ug/kg
	(ppb)	(ppb)
Chloromethane	< 50	50.
Bromomethane	< 50	50
Vinyl Chloride	< 50	50.
Chloroethane	< 50	50.
Methylene Chloride	< 125 * [°]	125.
Acetone	< 125	125.
Carbon Disulfide	< 25	25.
1,1-Dichloroethene	< 25	25.
1,1-Dichloroethene	< 25	25.
1,2-Dichloroethene(cis/trans)		25.
Chloroform	< 25	25.
1,2-Dichloroethane	< 25	25.
2-Butanone	< 125	125.
1,1,1,-Trichloroethane	< 25	25.
Carbon Tetrachloride	< 25	25.
Bromodichloromethane	< 25	25.
1,2-Dichloropropane	· < 25	25.
Trans-1,3-Dichloropropene	< 25	25.
Trichloroethene	< 25	25.
Benzene	< 25	25.
1,1,2-Trichloroethane	< 25	25.
Dibromochloromethane	< 25	25.
Cis-1,3-Dichloropropene	< 25	25.
Bromoform	< 25	25.
4-Methyl-2-pentanone	< 125	125.
2-Hexanone	< 125	125.
1,1,2,2-Tetrachloroethane	< 25	25.
Tetrachloroethylene	< 50	50.
Toluene	72.	25.
Chlorobenzene	< 25	25.
Ethyl Benzene	< 25	25.
Styrene	< 25	25.
Total Xylene	< 25	25.
Freon 113	< 25 *	25.
$A \cap M$	SK of man	

Analyst: Howard By: Date: 04/27/89

Laboratory Director:

McLaren

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	108	70-121
S2 = D8-Toluene	97.	81-117
S3 = 4-Bromofluorobenzene	103	74-121

Comments: * Methylene chloride and freon were detected at 110 ppb and 14 ppb respectively which were less than the raised reporting limit.
1:5 dilution used in analysis.



Project: CHIC 2.0 Lab ID: 24134

Sample Date

Location: <u>HA8 3.5'</u> Sampled: <u>04/14/89</u>

Sample Date

Number: <u>5229</u> Analyzed: <u>04/24/89</u>

	ANALYTE CONCENTRATION	REPORTING
COMPOUND	ug/kg	ug/kg
<u> </u>	(ppb)	(ppb)
	(PPE)	(PPD)
Chloromethane	< 50	50.
Bromomethane	< 50	50.
Vinyl Chloride	< 50	50.
Chloroethane	< 50	50.
Methylene Chloride	< 125 *	125.
Acetone	< 125	125.
Carbon Disulfide	< 25	25.
1,1-Dichloroethene	< 25	25.
1,1-Dichloroethene	< 25	25.
1,2-Dichloroethene(cis/trans)	< 25	25.
Chloroform	< 25	25.
1,2-Dichloroethane	< 25	25.
2-Butanone	< 125	125.
1,1,1,-Trichloroethane	< 25	25.
Carbon Tetrachloride	< 25	25.
Bromodichloromethane	< 25	25.
1,2-Dichloropropane	< 25	25.
Trans-1,3-Dichloropropene	< 25	25.
Trichloroethene	< 25	25.
Benzene	< 25	25.
1,1,2-Trichloroethane	< 25	25.
Dibromochloromethane	< 25	25.
Cis-1,3-Dichloropropene	< 25	25.
Bromoform	< 25	25.
4-Methyl-2-pentanone	< 125	125.
2-Hexanone	< 125	125.
1,1,2,2-Tetrachloroethane	< 25	25.
Tetrachloroethylene	< 50	50.
Toluene	48.	25.
Chlorobenzene	< 25	25.
Ethyl Benzene	< 25	25.
Styrene	< 25	25.
Total Xylene	< 25	25.
Freon 113	< 25	25.
10-211		

Analyst:

Mowy Mr Reviewed By:

Date: 04/27/89

Laboratory Director:

McLaren

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	111	70-121
S2 = D8-Toluene	102	81-117
S3 = 4-Bromofluorobenzene	109	74-121

Comments: * Methylene chloride was detected at 73 ppb which was less than the raised reporting limit.
1:5 dilution used in analysis.



Project: <u>CHIC 2.0</u> Lab ID: <u>24135</u>

Sample

Location: <u>HA9 3.5'</u> Sampled: <u>04/14/89</u>

Sample

Number: <u>5230</u> Analyzed: <u>04/24/89</u>

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/kg	ug/kg
	(ppb)	(ppb)
Oh 1		
Chloromethane	< 50	50.
Bromomethane	< 50	50.
Vinyl Chloride	< 50	50.
Chloroethane	< 50	50.
Methylene Chloride	< 125 *	125.
Acetone	< 125	125.
Carbon Disulfide	< 25	25.
1,1-Dichloroethene	< 25	25.
1,1-Dichloroethene	< 25	25.
1,2-Dichloroethene(cis/trans)	< 25	25.
Chloroform	< 25	25.
1,2-Dichloroethane	< 25	25.
2-Butanone	< 125	125.
1,1,1,-Trichloroethane	< 25	25.
Carbon Tetrachloride	< 25	25.
Bromodichloromethane	< 25	25.
1,2-Dichloropropane	< 25	25.
Trans-1,3-Dichloropropene	< 25	25.
Trichloroethene	< 25	25.
Benzene	< 25	25.
1,1,2-Trichloroethane	< 25	25.
Dibromochloromethane	< 25	25.
Cis-1,3-Dichloropropene	< 25	25.
Bromoform	< 25	25.
4-Methyl-2-pentanone	< 125	125.
2-Hexanone	< 125	125.
1,1,2,2-Tetrachloroethane	< 25	25.
Tetrachloroethylene	< 50	50.
Toluene	< 25 *	25.
Chlorobenzene	< 25	25.
Ethyl Benzene	< 25	25.
Styrene	< 25	25.
Total Xylene	< 25	25.
Freon 113	<u></u> 5—25	25.
1120	50 000	 -

Analyst:

_Reviewed By:

Date: <u>04/27/89</u>

L. A. Mooney

Laboratory Director:

McLaren

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	100	70-121
S2 = D8-Toluene	95	81-117
S3 = 4-Bromofluorobenzene	107	74-121

Comments: * Methylene chloride and toluene were present at 63 ppb and 7 ppb respectively which were less than the raised reporting limit.

1:5 dilution used in analysis.



Project: <u>CHIC 2.0</u> Lab ID: 24133

Sample

Date Location: HA10 3.5' Sampled: 04/14/89

Sample

Date Number: Analyzed: <u>04/24/89</u> <u>5228</u>

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/kg	ug/kg
	(ppb)	(ppb)
Chloromethane	< 50	50.
Bromomethane	< 50	50.
Vinyl Chloride	< 50	50.
Chloroethane	< 50	50.
Methylene Chloride	< 125 *	125.
Acetone	< 125	125.
Carbon Disulfide	< 25	25.
1,1-Dichloroethene	< 25	25.
1,1-Dichloroethene	< 25	25.
1,2-Dichloroethene(cis/trans)	< 25	25.
Chloroform	< 25	25.
1,2-Dichloroethane	< 25	25.
2-Butanone	< 125	125.
1,1,1,-Trichloroethane	< 25	25.
Carbon Tetrachloride	< 25	25.
Bromodichloromethane	< 25	25.
1,2-Dichloropropane	< 25	25.
Trans-1,3-Dichloropropene	< 25	25.
Trichloroethene	< 25	25.
Benzene	< 25	25.
1,1,2-Trichloroethane	< 25	25.
Dibromochloromethane	< 25	25.
Cis-1,3-Dichloropropene	< 25	25.
Bromoform	< 25	25.
4-Methyl-2-pentanone	< 125	125.
2-Hexanone	< 125	125.
1,1,2,2-Tetrachloroethane	< 25	25.
Tetrachloroethylene	< 50	50.
Toluene	49.	25.
Chlorobenzene	< 25	25.
Ethyl Benzene	< 25	25.
Styrene	< 25	25.
Total Xylene	< 25	25.
Freon 113	< 25	25.
10.14	23	20.

_Reviewed By:

Date: <u>04/27/89</u>

Laboratory Director:

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	112	70-121
S2 = D8-Toluene	99	81-117
S3 = 4-Bromofluorobenzene	98	74-121

Comments: * Methylene chloride was present at 71 ppb which was less than the raised reporting limit.
1:5 dilution used in analysis.



Project: CHIC 2.0 Lab ID: 24139

Sample Date

Location: <u>HA11 2.5'</u> Sampled: <u>04/14/89</u>

Sample Date

Number: <u>5234</u> Analyzed: <u>04/24/89</u>

COMPOUND	ANALYTE CONCENTRATION ug/kg (ppb)	REPORTING LIMIT ug/kg (ppb)
Chloromethane	< 50	50.
Bromomethane	< 50	50
Vinyl Chloride	< 50	50.
Chloroethane	< 50	50.
Methylene Chloride	< 125 *	125.
Acetone	< 125	125.
Carbon Disulfide	< 25	25.
1,1-Dichloroethene	< 25	25.
1,1-Dichloroethene	< 25	25.
1,2-Dichloroethene(cis/trans)	< 25	25.
Chloroform	< 25	25.
1,2-Dichloroethane	< 25	25.
2-Butanone	< 125	125.
1,1,1,-Trichloroethane	< 25	25.
Carbon Tetrachloride	< 25	25.
Bromodichloromethane	< 25	25.
1,2-Dichloropropane	< 25	25.
Trans-1,3-Dichloropropene	< 25	25.
Trichloroethene	< 25	25.
Benzene	< 25	25.
1,1,2-Trichloroethane	< 25	25.
Dibromochloromethane	< 25	25.
Cis-1,3-Dichloropropene	< 25	25.
Bromoform	< 25	25.
4-Methyl-2-pentanone	< 125	125.
2-Hexanone	< 125	125.
1,1,2,2-Tetrachloroethane	< 25	25.
Tetrachloroethylene	< 50	50.
Toluene	30.	25.
Chlorobenzene	< 25	25.
Ethyl Benzene	< 25	25.
Styrene	< 25	25.
Total Xylene	< 25	25.
Freon 113	< 25	25.
In m		

Analyst:

__Reviewed By:

Date: 04/27/89

Laboratory Director:

McLaren

GCMS 8240 SURROGATE % RECOVERY

Compounds	% Recovery	Soil Matrix
S1 = D4-1,2-Dichloroethane	107	70-121
S2 = D8-Toluene	96	81-117
S3 = 4-Bromofluorobenzene	106	74-121

Comments: * Methylene chloride was detected at 43 ppb which was less than the raised reporting limit.
1:5 dilution used in analysis.



ATTACHMENT 2

ALAMEDA COUNTY HEALTH CARE SERVICES AUTHORIZATION LETTER 4/13/89

NOTIFICATION OF INTENTION TO EXCAVATE 4/20/89

ALAMEDA COUNTY

HEALTH CARE SERVICES

AGENCY

DAVID J. KEARS, Agency Director

13 April, 1989

DEPARTMENT OF ENVIRONMENTAL HEALTH Hazardous Materiais Program 80 Swan Way, Rm. 200 Oakland, CA 94621 (415)

RECEIVED

APR 18 1989

McLAREN

Mr. S.G. Crowley 1311 63rd Street Emeryville, Ca. 94608

Subject: Soil Remediation at 5800 Christie Ave. Emeryville.

Dear Mr. Crowley:

Thank you for the fee deposit check, remediation action and site safety plans submitted to our office concerning the facility listed above. The plans have been reviewed by our staff and approval is granted for their implementation.

If you have any questions concerning this matter, please contact, Dennis Byrne, Hazardous Materials Specialist, at (415) 271-4320.

Sincerely,

Rafat A. Shahid, Chief,

Edgar B Howellist

Hazardous Materials Division

RAS: DB

cc: Walter Loo, Principal Geohydrologist
McLaren Environmental Engineering
980 Atlantic Avenue
Suite 100
Alameda, Ca. 94501



McLaren Environmental Engineering

April 20, 1989

Mr. Milton Feldstein Air Pollution Control Officer Bay Area Air Quality Management District 939 Ellis Street San Francisco, CA 94109

Dear Mr. Feldstein:

NOTIFICATION OF INTENTION TO EXCAVATE

This letter presents Croley and Herring Investment Company's (CHIC) intention to excavate soil located on site at 5800 Christie Street, Emeryville, California. McLaren is the remediation consultant to CHIC. The scheduled starting date of this excavation is on or during the week of April 24, 1989.

The proposed total excavation will be less than 100 cubic yards of soil. Concentrations of organic compounds detected in the soil average less than 500 ppm. Organic compounds which have been detected include; Carbon Tetrachloride, Ethyl Benzene, Toluene, 1,1,1-Trichloroethane, Trichloroethene, Xylenes, and Gasoline.

Remediation action and site safety plans were submitted to and reviewed by the Alameda County Department of Environmental Health and approval was granted for their implementation (see attached letter). If you have any questions please call me at (415) 521-5200.

Sincerely,

Amy Brownell

Assistant Engineer

any Brownell

Attachment

0420LCD1

980 Atlantic Avenue, Suite 100, Alameda, CA 94501 (415) 521-5200 Headquarters: 11101 White Rock Road, Rancho Cordova, CA 95670 (916) 638-3696

ATTACHMENT 3

SOIL DRILLING LOGS WELLS MW-1, MW-2, & MW-3

ÀÀ

SOIL DRILLING LOG

McLaren Environmental Engineering

SB/MW	#_	: MW	<i>[</i> -1
# D			
Page	1	of _	1
Sample	r.	B. WRIG	GHT

PROJECT	5800 CH	RISTIE	LOCATION 88'SW OF SHELLMOUND, 4'NW OF BACK FENCE								
ELEVATION	9.23' MSL	MONITO	RING DEVIC	E LEL	., 580 A OVM; DR	AEGER					
SAMPLING DAT	ſE(S)	4/21/89	START	0930	FINISH	1140					
SAMPLING MET		RNIA SPLIT SPO	ON SUBCON	TRACTOR 6	& EQUIPMENT	AQUA SCIENC	E ENGINEERS,				
мемо	HAND AUG	ER TO 4.5 FEET			·	MOBILE DRILL	. B-61				

:	elbw (ft.)	Penetration Results		Depth I (ft.)	al (ft.)		Soil Description Color, Texture, Moisture,Etc.	ation	gon	Sampled Depth		Well Construction Details
	Depth Below Surface(ft.)	Blows 6"-6"-6"	叝	Sampler Depth Interval (ft.)	Sample ID#	OVM reading (ppm)		Unified Classification	Graphic Log	Sample	Vault B	
	-						Grayish brown (2.5Y 5/2) gravelly sand, unconsolidated, well graded slightly moist.	sw	3+3+3 3+3+3 3+3+3 3+3+3			2" Sch. 40 PVC Flush Joint Blank Casing
Ā	- - - 5'	3-2 2-1-1	5 2	4.5- 5.5 6.0-	29105		Very dark gray (2.5Y 3/0) to greenish gray (5GY 6/1) at 3.0'; silty clay, high plasticity, medium stiff, slightly moist common gravel and debris.	CL			3' 4' 5.5'	Sanitary Seal, Portland cement with 5% Bentonite
	- - -			7.5								Bentonite Pellets —— 11" Borehole
	10' 	1-1-1	2	10.0- 11.5			Black (2.5Y 2/0) silty clay, soft, sticky, satruated, organic odor.	OL				0.020" slot 4" CWW 304 Stainless Steel Well Screen
	15' - -	4 -6- 14	20	15.0- 16.5			Light yellowish brown (2.5Y 6/4) gravelly sand, unconsolidated, well graded, clay to medium pebble gravel, saturated, 21' sample same	sw				8/20 Mesh Sand
	- 20' - -	6-8-13	21	21.0- 22.5			as above with 20% clay matrix, moist.			2).5	TID. End Cap
	- 25' -				:							-
	30, -											

SIGNATURE OF FIELD SUPERVISOR

SIGNATURE OF REVIEWER

TILE

TILE

M

SOIL DRILLING LOG

SB/MW # : MW-2 # D-Page 1 of 1 _Sampler: B. WRIGHT

McLaren Environmental Engineering

PROJECT580	O CHRISTIE	LOCATION_	8' SW OF 5	SHELLMOUND, 15' E C	OF CHRISTIE EME	RYVILLE
ELEVATION 7.42'	MSL MONITO	RING DEVIC	E [.EL, 580 A OVM; DRAI	EGER	
SAMPLING DATE(S)	4/20/89	START	0800	FINISH	1115	
SAMPLING METHODO	LIFORNIA SPLIT SPO	ON SUBCON	TRACTO	R & EQUIPMENTAG	QUA SCIENCE ENC	INEERS,
• —	AUGER TO THREE FI				OBILE DRILL B-61	*

	WC (;	Penetration Results		epth (.)		ing (ppm)	Soil Description Color Taxtura Maistura Etc.			8,	₽ Ded Ded	Well Construction	
	Depth Below Surface(ft.)	Blows 6"-6"-6"	#	Sampler Depth Interval (ft.)	Sample D#	OVM reading (ppm)	Color, Texture, Moisture,Etc.	Unified		Graphic Log	Well Construction Details Vault Box Locking C		
	- -					1.0	Light olive brown (2.5Y 5/4) clayey sand, poorly graded, unconsolidated, moist.	sc				2" Sch. 40 PVC Flush Joint Blank Casing	
∇	-	2-3-5	8	3.0- 4.5	29103	0.0	Very dark gray (10YR 3/1) sandy clay, medium plasticity, soft, common coarse gravels, and construction	CL				3' Sanitary Seal, Portland	
	- 5' - -	2-1-1	2	6.0-		0.0	debris, moist. Dark greenish gray (5GY 4/1) silty sand, poorly graded silt to fine	SM				5% Bentonite Bentonite	
	- - — 10'						sand, dense saturated Very dark gray (2.5Y 3/0) sity clay, low plasticity, very soft, sticky, common fine sand, saturated,	οι				Pellets	
	-	1-1-3	4	10.0- 11.5		0.0 8.0	organic odor. Very dark gray (2.5Y 5/4) silty sand, soft, dense, very moist, mild organic odor.	SN				0.020" slot 2" Sch. 40 PVC Flush Joint Well Screen	
	- 15'	8 -9- 13	22	15.0- 16.5		0.0	Light olive brown (2.5Y 5/4) silty sand, dense, poorly graded fine sand, very moist.	SP	1 1 1			8/20 Mesh Sand	
	- - - 20'				:		Ofive brown (2.5Y 4/4) gravelly sand, unconsolidated, well graded fine sand to fine subrounded pebble gravels, saturated.	sv				7.D.	
	20 - - -	8-12-14	26	20.0- 21.5		0.0	Light olive brown (2.5Y 5/4) silty clay, common embedded pebble gravels, high plasticity, very stiff, slightly moist.	CL				End Cap	
	- 25' -											-	
	— 30' - -												

SIGNATURE OF FIELD SUPERVISOR

SIGNATURE OF REVIEWER

TITLE

TITLE

M

SOIL DRILLING LOG

McLaren Environmental Engineering

SB/MW # D-	#_	:	MW-	3	
Page	1		of_	1	
Sample	r	В	WRIG	HT	

PROJECT_	5800 CH	RISTIE	LOCATION		WELL ST., 13' E OF		VILLE
ELEVATION	8.51' MSL	MONIT	ORING DEVI	E L	EL, 580 A OVM; DRAI	EGER	
SAMPLING	DATE(S)	4/20/89	START	1340	FINISH	1435	
SAMPLING	METHODCALIFO	RNIA SPLIT S	POON SUBCON	NTRACTOR	& EQUIPMENTAG	QUA SCIENCE ENG	INEERS,
МЕМО		ER TO THREE			M	OBILE DRILL B-61	

	elow (ft.)	Penetration Results		Depth (ft.)		OVM reading (ppm)	Soil Description Color, Texture, Moisture, Etc.	d ation	<u>6</u>	Sampled Depth	Well Construction Details
	Depth Below Surface(ft.)	Blows 6"-6"-6"	扭	Sampler Depth Interval (ft.)	Sample ID#	OVMrea	COIDI, Texture, Moisture, Etc.	Unitied Classification	Classification Graphic Log		Vault Box Locking Cap
	-						Grayish brown (2.5Y 5/2) gravelly sand, well graded construction fill, slightly moist.	sw			2" Sch. 40 PVC Flush Joint Blank Casing
모	- 5'	5-8-14 2-2-2 1-1-1	4 2	3.0- 4.5- 4.5- 6.0- 6.5-	29104	0.0	Dark greenish gray (5GY 4/1) silty clay, medium plasticity, stiff common construction debris, slightly moist. Dark gray (5Y 4/1) silty clay, trace	CL			Sanitary Seal, Portland cernent with 5% Bentonite
	- - -	2-2-2	4	8.0 8.0 9.5	29104	0.0	fine sand, medium plasticity, soft, very moist. Olive brown (2.5Y 4/4) clayey sand, poorly graded fine sand, soft,	SP CL SW			Bentonite Pellets
	— 10' - - -			11.0			sticky, saturated. Grayish brown (2.5Y 5/2) sitty clay, soft, sticky, very moist to saturated, gravelly sand at 9.0'-9.5'. Very dark gray (2.5Y 3/0) sitty	OL			0.020" slot 2" Sch. 40 PVC Flush Joint Well Screen
	- 15' - -	4- 9- 11	20	15.0- 16.5		0.0	clay, soft, sticky, saturated, organic odor. Mottled greenish gray (5GY 5/1) and olive yellow (2.5Y 6/6) sandy clay, low plasticity, stiff, slightly	CL			8/20 Mesh Sand
	- 20' -	5-7-11	18	20.0- 21.5		0.0	moist.				тр.
•	- 25' -										-
	- 30										

SIGNATURE OF FIELD SUPERVISOR

SIGNATUREOFREVIEWER

TILE

TILE

ATTACHMENT 4

GROUNDWATER ANALYSIS RESULTS

L.P. 1699 Nº 209517

McLaren Analytical Laboratory Chain of Custody Record

McLaren Environmental Engineering

11101 White Rock Road, Rancho Cordova, CA 95670 (916) 638-3696

24 hr. rush

							2	1/1	$\mathcal{L}I$	
PROJECT D	ESIGNATION Chic-	ے، 2، 3-			S	AMPLES TAKE	EN BY: Dec	Deserte	Brow Win	
				SAMPLE						
AREA	SAMPLE LOCATION	DATE	TIME	COMP GRAI	SOIL	SAMPLE NO.	TYPE CONTAINER(S)	REO	ALYSIS LURED	
	mw-1	4/25/89	1200	X		028577	VOA	681	624	
	1	1		λ		०२७५१८	VOA	(20)	spare	
				χ		028519	UOA	6001	()	
				X		028530	Vo.A	601	<u> </u>	
				- 7		०३४५३।	VoA	600	*	
				χ		628522	JOA	680	Spare +	
				Х		028523	Uo4	602	1 *	
	V	1	1	γ		028524	VOA	692	<u> </u>	
								~ 1		
-										
FIELD DISP	OSITION: Fec)Ex#	2030	476726	>		* : Pres	erved u	U. 7h HCL	
STORAG	TE DELIVERY ().) ID	-				SECURED TYES	S		
		1 ID	-				□ NO			
RELINGUIS	HED BY:			RECEIVED	BY:*			14/25/87 140C		
RELINQUIS	HED BY	1		RECEIVED	TE/TIME					
RECEIVED	PICHAEL N. NEUENBURG 1/24/9 10=									
METHOD O	F SHIPMENT:	7 1200	<u> </u>	7			·		y	
LABORATO	RY DISPOSITION:	· · · · · · · · · · · · · · · · · · ·								
IMMEDIATE	ANALYSIS 🗆	STOF	RAGE 🗆	□ REFRIGERATOR Ø ID SECU						
					FRI	EEZER	□ ID		Ø □	
PRINT NAME AFTER SIGNATURE IN GOOD CO			RECEIVE)N	BINET	□ ID		YES NO		
_=			•							

L.P. 1699 N° 209519

McLaren Analytical Laboratory Chain of Custody Record

24 hr moh

		Chic-				SAI	MPLE TY	YPE		EN BY: Broc		
AREA	SAMPLE LO	CATION	DATE	E	TIME		TER	SOIL	SAMPLE NO.	TYPE CONTAINER(S)		ALYSIS DUIRED
	MW-2		4/25	187	1040		X		028561	U04	TOPE (624 Gy
							X		078207	Uo.4	9XI	spure
·		-			\perp		ア	-	०७८७३	VOA	6001	11_
							7		028504	UOA	661	V-
							を		028505	VOA	662	622fa.
•							×		028504	UOA	(38)	spare
							X		028507	UOA	6X	
				/		,	Y		02850	VOA	(ex21	11
					·							
<u>-</u>												
HELD DISPO IMMEDIA STORAG	TE DELIVERY 🥦	ERATOR [•		°976	726			· ·	SECURED □YES		HCL
ELINGUISI		4				REC	EIVED (BY:*			t t	ATE/TIME
2100) (N. log		<u> </u>			DEC	EIVED I	PV-*				188 1400 ATE/TIME
RĒLINQUISI	HED BY:						EIVED		·			,,,,
RECEIVED	FOR LABORATOR	RY BY:		Ale	me	nhu	MICHA	AEL N	. NEUEN	BURG	· 4/26	ATE/TIME
NETHOD O	F SHIPMENT:	- / /					/ -				7	_
	RY DISPOSITION		S/s	NV.	I.E.	S RE	CEIV	ED _{REI}	RIGERATOR	m 10 3		SECURE
			11A	uu	UD	CON	וווטו			□ ID		Σξ (YES N
								UAI	BINET			, ,,
PRINT NAI	ME AFTER SIGN	ATURE										

McLaren Environmental Engineering

McLaren Analytical Laboratory Chain of Custody Record

L.P. 1699 Nº 209516

24 hr wish

							.)	\	//_ \	l
PROJECT D	ESIGNATION Chic.	- 2. ८)			s	AMPLES TAKI	EN BY: 640	(1) wal	Brow	12/1
				SAMPLE			Ditt			
AREA	SAMPLE LOCATION	DATE	TIME	WATER COMP GRA	SOIL	SAMPLE NO.	TYPE CONTAINER(S)		NALYSIS EQUIBED	
	12.3 Blank	4125/89	1000	X		018525	VO4	6001	624	(4)
				λ		028526	UOA	600	Stave	
				X		028527	404	6001	h	
				<u>}</u>		<i>038</i> 538	UOA	6002		*
				x		028527	UDA_	600	5व्यार	*
		<i> </i>	1	\ <u>\</u>		038230	VO.A	602	L.	}
									·····	
						1	:			
FIELD DISP	OSITION: FC)Ex#	२०३	057672	4		* : §) Lesses c	F, W 64	ラオ
STORAG	REFRIGERATOR		_				SECURED YES			
RELINQUIS		□ ID	-	RECEIVED	BY:*				DATE/TIME	
Buc	West							4/29	189 140	2 <u>d</u>
RELINQUIS	HED BY:			RECEIVED	BY:*			1	DATE/TIME	
RECEIVED	FOR LABORATORY BY:	M	A) a			 		4/2/	DATE/TIME	
METHOD O	F SHIPMENT:		Nei	<u>envu</u>	MIC	HAEL N.	NEUENBURG	1///	784] 10	- 20
				·.						
	RY DISPOSITION: E ANALYSIS □	ST <u>O</u> F	RAGE □		RE	FRIGERATOR	Ø 10 <u>3</u>		SEC	URED
		SAMPLE				EEZER	□ ID		Æ I	
	ı	N GOOD	CON	MOITION	CA	BINET	□ ID		YES	NO
	ME AFTER SIGNATURE									

McLaren Environmental Engineering

Project: CHIC-3.0 Lab ID: 24512

Sample Date

Location: MW-1 Sampled: 04/25/89

Sample Date

Number: 028517 Analyzed: 04/27/89

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/L	ug/L
	(ppb)	(ppb)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	< 10	10.
Methylene Chloride	< 25	25.
Acetone	< 25	25.
Carbon Disulfide	< 5	5.
1,1 Dichloroethene	< 5	5.
1,1 Dichloroethane	/9.)	5.
1,2 Dichloroethene(cis/trans)	(9. <i>/</i>	5.
Chloroform	< 5	5.
1,2 Dichloroethane	< 5	5.
2 Butanone	< 25	25.
1,1,1 Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2 Dichloropropane	< 5	5.
Trans 1,3 Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2 Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis 1,3 Dichloropropene	< 5	5.
Bromoform	< 5	5.
4 Methyl 2 Pentanone	< 25	25.
2 Hexanone	< 25	25.
1,1,2,2 Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	< 5	5.
Chlorobenzene	< 5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylenes	< 5	5.

Analyst: Mony for Reviewed By:

Rt Lames

Date: 04/27/89

Laboratory Director:

McLaren

Lab ID: 24512

GCMS 624 SURROGATE % RECOVERY

COMPOUND NAME	% RECOVERY	RANGE	
S1 = 1,2-Dichloroethane-D4	108	76-114	-
S2 = Toluene-D8	94	88-110	
S3 = 4-Bromofluorobenzene	96	86-115	



Project: <u>CHIC-3.0</u> Lab ID: <u>24509</u>

Sample Date

Location: MW-2 Sampled: 04/25/89

Sample Date

Number: <u>028501</u> Analyzed: <u>04/26/89</u>

	ANALYTE CONCENTRATION	REPORTING LIMIT
<u>COMPOUND</u>	ug/L	${ m ug/L}$
	(ppb)	(dqq)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	< 10	10.
Methylene Chloride	< 25	25.
Acetone	< 25	25.
Carbon Disulfide	< 5	5.
1,1 Dichloroethene	< 5	5.
1,1 Dichloroethane	< 5	5.
1,2 Dichloroethene(cis/trans)	< 5	5.
Chloroform	< 5	5.
1,2 Dichloroethane	< 5	5.
2 Butanone	< 25	25.
1,1,1 Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2 Dichloropropane	< 5	5.
Trans 1,3 Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2 Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis 1,3 Dichloropropene	< 5	5.
Bromoform	< 5	5.
4 Methyl 2 Pentanone	< 25	25.
2 Hexanone	< 25	25.
1,1,2,2 Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	< 5	5.
Chlorobenzene	< 5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylenes	< 5	5.

Analyst: Morry for Reviewed By:

R. L. James

Date: 04/27/89

Laboratory Director:

<u>McLaren</u>

Lab ID: 24509

GCMS 624 SURROGATE % RECOVERY

COMPOUND NAME	% RECOVERY	RANGE	
S1 = 1,2-Dichloroethane-D4	106	76-114	-
S2 = Toluene-D8	98	88-110	
S3 = 4-Bromofluorobenzene	102	86-115	



Project: <u>CHIC-3.0</u> Lab ID: <u>24510</u>

Sample Date

Location: MW-3 Sampled: 04/25/89

Sample Date

Number: Analyzed: <u>04/27/89</u> 028509

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/L	ug/L
	(ppb)	(ppb)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	< 10	10.
Methylene Chloride	< 25	25.
Acetone	< 25	25.
Carbon Disulfide	< 5	5.
1,1 Dichloroethene	< 5	5.
1,1 Dichloroethane	< 5	5.
1,2 Dichloroethene(cis/trans)		5.
Chloroform	< 5	5.
1,2 Dichloroethane	< 5	5.
2 Butanone	< 25	25.
1,1,1 Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2 Dichloropropane	< 5	5.
Trans 1,3 Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2 Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis 1,3 Dichloropropene	< 5	5.
Bromoform	< 5	5.
4 Methyl 2 Pentanone	< 25	25.
2 Hexanone	< 25	25.
1,1,2,2 Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	< 5	5.
Chlorobenzene	< 5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylenes	< 5	5.

Reviewed By:

Laboratory Director:

Date: 04/27/89

Lab ID: <u>24510</u>

GCMS 624 SURROGATE % RECOVERY

COMPOUND NAME	% RECOVERY	RANGE	
S1 = 1,2-Dichloroethane-D4	93	76-114	-
S2 = Toluene-D8	101	88-110	
S3 = 4-Bromofluorobenzene	103	86-115	



Project: <u>CHIC-3.0</u> Lab ID: <u>24511</u>

Sample Date

Location: Trip Blank Sampled: 04/25/89

Sample

Number: 028525 Analyzed: 04/26/89

	ANALYTE CONCENTRATION	REPORTING LIMIT
COMPOUND	ug/L	ug/L
	(ppb)	(ppb)
Chloromethane	< 10	10.
Bromomethane	< 10	10.
Vinyl Chloride	< 10	10.
Chloroethane	< 10	10.
Methylene Chloride	< 25	25.
Acetone	< 25	25.
Carbon Disulfide	< 5	5.
1,1 Dichloroethene	< 5	5.
1,1 Dichloroethane	< 5	5.
<pre>1,2 Dichloroethene(cis/trans)</pre>	< 5	5.
Chloroform	< 5	5.
1,2 Dichloroethane	< 5	5.
2 Butanone	< 25	25.
1,1,1 Trichloroethane	< 5	5.
Carbon Tetrachloride	< 5	5.
Bromodichloromethane	< 5	5.
1,2 Dichloropropane	< 5	5.
Trans 1,3 Dichloropropene	< 5	5.
Trichloroethene	< 5	5.
Benzene	< 5	5.
1,1,2 Trichloroethane	< 5	5.
Dibromochloromethane	< 5	5.
Cis 1,3 Dichloropropene	< 5	5.
Bromoform	< 5	5.
4 Methyl 2 Pentanone	< 25	25.
2 Hexanone	< 25	25.
1,1,2,2 Tetrachloroethane	< 5	5.
Tetrachloroethylene	< 10	10.
Toluene	< 5	5.
Chlorobenzene	< 5	5.
Ethyl Benzene	< 5	5.
Styrene	< 5	5.
Total Xylenes	< 5	, 5 .
	4	

Analyst: Reviewed By: Date: 04/27/89

R. L. Zames

Laboratory Director:

J. M. Ba

McLaren

Lab ID: 24511

GCMS 624 SURROGATE % RECOVERY

COMPOUND NAME	% RECOVERY	RANGE	
S1 = 1,2-Dichloroethane-D4	96	76-114	-
S2 = Toluene-D8	98	88-110	
S3 = 4-Bromofluorobenzene	105	86-115	



L. P. / 699 Nº 209518

McLaren Analytical Laboratory Chain of Custody Record

24 hr rish

	ESIGNATION CARE	۵.۶				•		EN BY: Buch	12 H	R. Kara
PROJECT D	ESIGNATION CATE	\(\begin{array}{c} \cdot	<u> </u>	SAI	MPLE T	OF OF	MPLES TAKE	NBY: //CE/U	LIGHT D	<u>vociery</u> r
AREA	SAMPLE LOCATION	DATE	TIME		TER	SOIL	SAMPLE NO.	TYPE CONTAINER(S)	ANAL REQU	YSIS JIRED _
	MW-3	4125189	1125		γ		<i>ට</i> 28%9	U04	001	450 624 GA
	1				X		038510	UOA	60	spare
					Х		028511	J0A	6001	
					þ		028512	UOA	601	<u></u>
					X		028513	UdA	(%)	*
					γ		028514	UOA_	6 62	spare *
					X		038515	V0.4	662	1 +
			1		Х		028516	U 0.4	662	L *
									/ \	V
FIELD DISPO IMMEDIA STORAG	ATE DELIVERY (X) SE	=x # 20 1001	53697 -	ne 72	(¢			Presection of the secured of the sec		HCL
RELITIQUIS			-	REC	EIVED E	BY:*	······································		DAT	E/TIME
Dloc)	alegh			RECEIVED BY: DATE/T						
RELINQUIS	HED BY?			HEC	EIVEDE	3Y:* 			DAI	E/TIME
99	FOR LABORATORY BY: What F SHIPMENT:	Nen	ent	Mil	CHAE	L N.	NEUENB	URĜ	DAT 1/26/8	E/TIME
METHODO	F SHIFMENT.			<i>/</i> .					·	
LABORATO	RY DISPOSITION:									
IMMEDIATE	ANALYSIS 🗆	STOR © A Bat	AGE []	DEC		REF	RIGERATOR	DX10 <u>3</u>		SECURED
		SAM IN GO)OD	CON	DITIO	LUFRE DN:AR	EZER INFT	□ ID		YES NO
* PRINT NAI	ME AFTER SIGNATURE		· • •	· · ·						120 110

McLaren Environmental Engineering