

# NOVEMBER 2003 GROUNDWATER MONITORING REPORT

January 8, 2004

1220 West Tennyson Road Hayward, California

> Prepared For: Mr. Kelly Engineer All Star Inc. 1791 Pine Street Concord, CA 94520



# NOVEMBER 2003 GROUNDWATER MONITORING REPORT

# 1220 West Tennyson Road Hayward, California

ACC Project Number 6651-004.00

Prepared for:

Mr. Kelly Engineer All Star Inc. 1791 Pine Street Concord, CA 94520

January 8, 2004

Prepared by:

Edward Giacometti Staff Geologist

Reviewed by:

David R. DeMent, RG, REA II
Environmental Division Manager

DAVID R. DEMENT NO. 5874

Alomeda County

Environmental Health

# TABLE OF CONTENTS

		Page
1.0	INTRODUCTION	
2.0	BACKGROUND	1
3.0	GROUNDWATER SAMPLING AND MONITORING  3.1 Groundwater Monitoring  3.2 Groundwater Gradient  3.3 Groundwater Sampling	2
4.0	RESULTS OF GROUNDWATER SAMPLING	3
5.0	DISCUSSION	4
6.0	CONCLUSIONS	5
7.0	RECOMMENDATIONS	5
8.0	LIMITATIONS	6
TAI	BLES	
2 - 0	Groundwater Depth Information Groundwater Gradient and Flow Direction Groundwater Sample Analytical Results	3
FIG	GURES	
2 - 5	Location Map Site Plan Groundwater Gradient Map	
API	PENDICES	
	Well Monitoring Worksheet  Analytical Results and Chain of Custody Record	

# NOVEMBER 2003 GROUNDWATER MONITORING REPORT 1220 West Tennyson Road Hayward, California

#### 1.0 INTRODUCTION

This November 2003 Groundwater Sampling and Monitoring Report was prepared by ACC Environmental Consultants, Inc., (ACC) at the request of Kelly Engineer and All Star Inc., to describe work performed at 1220 West Tennyson Road, Hayward, California (Site). The project objectives were to purge and sample three groundwater monitoring wells and one observation well, calculate groundwater gradient and flow direction, and characterize concentrations of petroleum hydrocarbons in groundwater in the vicinity of four former underground storage tanks (USTs). No significant water was measured in the observation well and it was not purged and sampled.

# 2.0 BACKGROUND

The subject site is located on the southwest corner of West Tennyson Road and Pompano Street, Hayward, California (Figure 1). An operating gasoline and automobile repair facility currently occupy the Site. The following information was obtained during file review at the City of Hayward Fire Department.

Environmental Geotechnical Consultants, Inc. removed one 6,000-gallon and three 4,000-gallon USTs from the site in October 1990. Four new USTs were subsequently installed at the site. One groundwater and eight soil samples were collected from the tank pit during removal of the USTs. Analysis of the soil samples revealed the presence of total petroleum hydrocarbons as gasoline (TPHg) at 4,300 parts per million (ppm), benzene at 29,000 parts per billion (ppb), toluene at 160,000 ppb, ethylbenzene at 68,000 ppb and total xylenes at 280,000 ppb. Analysis of the groundwater sample revealed the presence of TPHg at 26 ppm, benzene at 2,400 ppb, toluene at 1,800 ppb and total xylenes at 5,200 ppb.

Artesian Environmental Consultants (Artesian) performed a subsurface investigation at the Site in March 1992. Three soil borings were drilled at the Site and converted into groundwater monitoring wells (MW-1, MW-2 and MW-3). Analysis of seven soil samples collected from the borings revealed the presence of TPHg at 680 ppm, benzene at 8,100 ppb, toluene at 15,000 ppb, ethylbenzene at 11,000 ppm and total xylenes at 73,000 ppb. Analyses of soil samples collected from the tank pit revealed the presence of TPHg at 2,900 ppm, benzene at 12,000 ppm, toluene at 160,000 ppm, ethylbenzene at 35,000 ppb and total xylenes at 420,000 ppb. Analyses of groundwater samples collected from the groundwater monitoring wells revealed the presence of TPHg at 59,000 ppb, benzene at 13,000 ppb, toluene at 12,000 ppb, ethylbenzene at 1,600 ppb and total xylenes at 13,000 ppb.

The City of Hayward has requested additional site investigation and remediation at the Site.

## 3.0 GROUNDWATER SAMPLING AND MONITORING

ACC conducted groundwater sampling and monitoring on November 21, 2003. Work at the site included measuring depth to water, subjectively evaluating groundwater in the wells, purging and sampling the wells, and submitting the samples to a laboratory for analysis.

# 3.1 Groundwater Monitoring

Before groundwater sampling, the depth to the surface of the water table was measured from the top of the well casing using a Solinst water level meter. The water level measurements were recorded to the nearest 0.01 foot with respect to mean sea level (MSL). Worksheets of recorded groundwater monitoring data are included as Appendix 1. Information regarding well elevations and groundwater depths is summarized in Table 1.

TABLE 1 - GROUNDWATER DEPTH INFORMATION

Welling.	Well Elevation (above MSE)	-Date Measured	- Deilino - Giologwater	Groundwater Elevation
MW-1	21.86	04/07/92	10.08	11.78
		04/11/01	10.54	11.32
		07/16/01	11.18	10.68
		11/25/02	11.62	10.24
		2/24/03	11.29	10.57
		05/27/03	11.49	10.37
		08/27/03	11.85	10.01
		11/21/03	11.73	10.13
MW-2	21.56	04/07/92	9.49	12.07
		04/11/01	9.67	11.89
		07/16/01	10.36	11.20
		11/25/02	11.13	10.43
		2/24/03**	10.51	11.05
		05/27/03	10.99	10.57
		08/27/03	11.35	10.21
		11/21/03	11.23	10.33
MW-3	20.54	04/07/92	10.64	9.90
		04/11/01	11.40	9.14
,		07/16/01	11.67	8.87
		11/25/02	10.22	9.68
		2/24/03	9.88	10.66
		05/27/03	10.09	10.45
		08/27/03	10.47	10.07
		11/21/03	10.31	10.23

Notes: All measurements in feet

<sup>\*</sup>Well elevation measured to top of casing

#### 3.2 Groundwater Gradient

The groundwater flow direction, as determined from monitoring well data that was obtained on November 21, 2003, is illustrated on Figure 3. ACC utilized the well elevations relative to mean sea level reported by Artesian in its *Subsurface Investigation Report* dated April 1992. Based on groundwater elevation calculations, groundwater flow direction is toward the west-southwest at an average gradient of 0.005 foot per foot. These values are inconsistent with previous trends. Table 2 summarizes previous gradients and calculated groundwater flow directions.

<b>Date Monitored</b>	Gradient (foot/foet):	Direction
04/07/92	0.025	south-southeast
04/11/01	0.031	south
07/16/01	0.026	south
11/25/02	0.008	south
02/24/03	0.002	south
05/27/03	0.005	west-southwest
08/27/03	0.004	west-southwest
11/21/03	0.005	west-southwest

TABLE 2 - GROUNDWATER GRADIENT AND FLOW DIRECTION

# 3.3 Groundwater Sampling

Before groundwater sampling, each well was purged using a disposable polyethylene bailer. Groundwater samples were collected when a minimum of four well casing volumes of water had been removed. Following purging, each well was allowed to recharge before sampling. When recovery to 80 percent of the static water level was observed, a sample was collected for analysis.

Wells were sampled using disposable polyethylene bailers attached to new rope for each well. From each monitoring well, approved, laboratory-supplied sample vials were filled to overflowing and sealed to eliminate trapped air in the vial. Once filled, sample vials were inverted and tapped to test for air bubbles. Sample containers were labeled with self adhesive, preprinted tags. The samples were stored in a prechilled, insulated container pending delivery to STL San Francisco, a state-certified laboratory for analysis.

Water purged prior to sampling the monitoring wells was temporarily stored on site in Department of Transportation-approved 55-gallon drums pending laboratory analysis and proper disposal.

#### 4.0 RESULTS OF GROUNDWATER SAMPLING

Groundwater samples from monitoring wells MW-1, MW-2, MW-3 were collected and submitted to STL-San Francisco (STL-SF) for analysis of TPHg, BTEX, and MTBE by EPA Method 8260B. MTBE was reported in the samples at concentrations ranging from 22 to 3,100 ppb. Analytical

results from the groundwater samples are summarized in Table 3. A copy of the analytical results and chain of custody record for groundwater samples is included as Appendix 2.

TABLE 3 - GROUNDWATER SAMPLE ANALYTICAL RESULTS

Walt	Date: #	TPHe	Bénzene	Aoine ie	ERVI-	i i i i i i i i i i i i i i i i i i i	Marker	
No.	- (Sampled )	(1g/b)	(政権)	- (he/L)	benzene	<b>X</b> vieries	100/09/16	radole)
					(µg/L)	(1826)		1.5
MW-1	04/07/92	< 50	2.1	0.56	< 0.5	1.4	NA	. NA
	04/11/01	< 50	< 0.5	< 0.5	< 0.5	< 0.5	< 5.0	NA
	07/16/01	< 50	< 0.5	< 0.5	< 0.5	< 0.5	< 5.0	NA
	11/25/02	16,000*	< 100	< 100	< 100	< 100	20,000	NA
	02/24/03	<25,000	< 250	<250	< 250	< 500	59,000	NA NA
	05/27/03	38,000*	< 250	< 250	< 250	< 500	53,000	NA
	08/27/03	< 13,000	< 130	<130	< 130	<250	36,000	NA
	11/21/03	< 20,000	< 200	< 200	< 200	<400	<b>₩</b> 19,000	NA
MW-2	04/07/92	2,100	450	200	45	360	NA	NA .
	04/11/01	< 5,000	< 50	< 50	< 50	150	5,200	NA NA
	07/16/01	6,300	< 50	< 50	< 50	< 50	6,500	NA
	11/25/02	13,000*	< 50	< 50	< 50	< 50	20,000	NA
	02/24/03**	< 5,000	< 50	< 50	< 50	< 100	17,000	NA
	05/27/03	130*	< 0.50	< 0.50	< 0.50	< 1.0	190	NA
	08/27/03	< 50	< 0.50	< 0.50	< 0.50	< 1.0	60	NA
	11/21/03	< 50	< 0.50	< 0.50	< 0.50	< 1.0	22	NA
MW-3	04/07/92	59,000	13,000	12,000	1,600	13,000	NA	NA
	04/11/01	4,800	< 5.0	5.1	320	<5	760	1,500
	07/16/01	4,300	< 10	< 10	100	60	2,400	NA
	11/25/02	2,900*	< 10	< 10	< 10	< 10	4,000	NA
	02/24/03	< 5,000	< 50	< 50	< 50	< 100	4,900	NA
	05/27/03	<10,000	< 100	< 100	< 100	< 200	7,400	NA
	08/27/03	< 2,500	<25	< 25	< 25	< 50	4,500	NA
	11/21/03	< 5,000	< 50	< 50	< 50	< 100	3,100	NA

Notes:  $\mu g/L = micrograms per liter (approximately equivalent to ppb)$ 

<= concentrations were below reporting limits

 $NA = Not \ analyzed$ 

## 5.0 DISCUSSION

The November 2003 sampling event represents the eight ACC groundwater monitoring event. The calculated groundwater flow direction and gradient were west-southwest at 0.005 foot per foot. These values have remained relatively consistent during the last 12 months.

<sup>\* =</sup> Hydrocarbon reported in the gasoline range does not match the gasoline standard

<sup>\*\* =</sup> ACC inadvertently sampled a 4-inch observation well located on the site instead of monitoring well MW-2

Water sample analytical results are fairly consistent with previous analytical results. MTBE only was reported in the three water samples at concentrations ranging from 22 to less than 19,000 ppb. MTBE concentrations decreased in well MW-1 from 36,000 to less than 19,000 ppb, decreased in well MW-2 from 60 to 22 ppb, and decreased in well MW-3 from 4,500 to 3,100 ppb.

Since groundwater monitoring resumed in November 2002, reported TPHg values are likely comprised entirely of MTBE since they do not match the laboratory gasoline standard and no significant BTEX concentrations were reported. While reporting limits were raised due to interference effects of MTBE, TPHg and BTEX concentrations are significantly less than those reported by Artesian Environmental in 1992, especially in downgradient well MW-3.

#### 6.0 CONCLUSIONS

Based on the results of groundwater sampling and monitoring performed at 1220 West Tennyson Road in November 2003, ACC concludes the following:

- Groundwater gradient and flow direction were calculated at 0.005 foot/foot to the west-southwest,
   which are consistent with historical trends;
- Groundwater sample analytical results indicate that previous TPHg, BTEX, and/or MTBE
  impacts in groundwater across the majority of the site appear to have decreased or are below
  laboratory reporting limits;
- Natural attenuation processes appear to be actively decreasing MTBE concentrations in groundwater; and
- MTBE, the primary constituent of concern, decreased in all three groundwater monitoring wells.

## 7.0 RECOMMENDATIONS

Based on the conclusions of previous investigation and recent groundwater monitoring performed, ACC recommends:

- Continuing quarterly groundwater monitoring in wells MW-1, MW-2, and MW-3;
- Analyzing all future water samples for TPHg, BTEX, and MTBE and all fuel oxygenates by EPA Method 8260B; and
- Discuss with STL San Francisco the methods available to achieve the lowest possible reporting limits for TPHg, BTEX, and MTBE for water samples collected during future sampling events.


The next monitoring event is tentatively scheduled for February 2003.

#### 8.0 LIMITATIONS

The service performed by ACC has been conducted in a manner consistent with the levels of care and skill ordinarily exercised by members of our profession currently practicing under similar conditions in the area. No other warranty, expressed or implied, is made.

The conclusions presented in this report are professional opinions based on the indicated data described in this report and applicable regulations and guidelines currently in place. They are intended only for the purpose, site, and project indicated. Opinions and recommendations presented herein apply to site conditions existing at the time of our study.

ACC has included analytical results from a state-certified laboratory, which performs analyses according to procedures suggested by the U.S. Environmental Protection Agency and the State of California. ACC is not responsible for laboratory errors in procedure or result reporting.





Source: The Thomas Guide, Bay Area 2002

# Title:Location Map 1220 West Tennyson Road Hayward, California

Figure Number: 1 Scale: None

Project No: 6551-004.00 Drawn By: EJG


A • C • C

ENVIRONMENTAL
CONSULTANTS

7977 Capwell Drive, Suite 100
Oakland, California 94621
(510) 638-8400 Fax: (510) 638-8404

S

# West Tennyson Road



# Mantilla Avenue

# Legend

Groundwater Monitoring
MW-3 Well Location

Area of Excavation

Approximate Former Tank Location


Title: Site Map 1220 W. Tennyson Ave. Hayward, California

Figure Number: 2 Scale: 1" = 20'
Project Number: 6551-004.00 Drawn By: EJG


 $A \cdot C \cdot C$ 

ENVIRONMENTAL CONSULTANTS


7977 Capwell Drive, Suite 100 Oakland, California 94621 (510) 638-8400 Fax (510) 638-8404




# West Tennyson Road



Mantilla Avenue








# ACC MONITORING WELL WORKSHEET

JOB NAME:				PURGE METHOD: Mamual Rail					
SITE ADDRESS: 1220 W.	emmus	son f	₹.	SAMPLED BY: Ed Gigcometti					
JOB#: 6651 -004. 00	J			LABORATORY: STZ-SF					
DATE: 11/21/03				ANALYSIS: TPHG/BTEX MTBE					
Onsite Drum Inventory SOIL:				MONITO		C)	,	1520	VELOPING []
EMPTY: WATER: 1@ 8	35%		-	SAMPLI	NG EQ	50		5	AD TO BEING TO STATE OF THE STA
	PURGE VOL		PURG	E WATE	R REAL	DINGS			OBSERVATIONS
WELL: MW-1	(Gal)	рΗ	Temp.(C)	Cond.	Sal.	Turb.	D.O.		Froth
DEPTH OF BORING: 18.81	1.1		215				2.17	X	Sheen
DEPTH TO WATER: (1-73	0.2		21.4				2.07	λ	Odor Type <u>908</u>
WATER COLUMN: 7.08	3.3		21.3				1.84		Free Product
WELL DIAMETER: 2) 17	4.4		21.2				2.00	Amo	ountType
WELL VOLUME: 1.1									Other
COMMENTS: Purge: 13:00									
Sample: 14:00									17
WELL: MW-2	(Gal)	рН	Temp.(C)	Cond.	Sal,	Turb.	D.O.		Froth
DEPTH OF BORING: 17.14	1.0		22.5				2.12		Sheen
DEPTH TO WATER: 11.23	2.0		22.5				0.25		Odor Type
WATER COLUMN: 5.91	3.0		22,5		- 8		2.42		Free Product
WELL DIAMETER: 211	4.0		22.4				2.85	Amo	ountType
WELL VOLUME: 1.0									Other
COMMENTS: Purge: 13:20									sity
Sample: 14:10									
WELL: MW-3	(Gal)	рΗ	Temp.(C)	Cond.	Sal.	Turb.	D.O.		Froth
DEPTH OF BORING: 18,24	1.3		21.6				1.48		Sheen
DEPTH TO WATER: 10.81	2.6		21.9			B	1.56	Ī	Odor Type
WATER COLUMN: 7.93	3.9		22.0				1.46	Ħ	Free Product
WELL DIAMETER: ऄ <sup>14</sup>	5.2		21.9				1.74	Amo	ountType
WELL VOLUME: 1.3							N.		Other
COMMENTS: Purge: 13:40 Sample: 14:15									





## **ACC Environmental Consultants**

December 04, 2003

7977 Capwell Drive, Suite 100 Oakland, CA 94621

Attn.:

Ed Giacometti

Project#:

6651-004.00

Project:

1220 W. Tennyson

Dear Mr. Giacometti,

Attached is our report for your samples received on 11/24/2003 14:00

This report has been reviewed and approved for release. Reproduction of this report is permitted only in its entirety.

Please note that any unused portion of the samples will be discarded after 01/08/2004 unless you have requested otherwise.

We appreciate the opportunity to be of service to you. If you have any questions, please call me at (925) 484-1919.

You can also contact me via email. My email address is: vvancil@stl-inc.com

Sincerely,

Vincent Vancil

Project Manager





ACC Environmental Consultants

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004.00

1220 W. Tennyson

Received: 11/24/2003 14:00

#### Samples Reported

Sample Name	Date Sampled	Matrix	Lab#
MW-1	11/21/2003 14:00	Water	1
MW-2	11/21/2003 14:10	Water	2
MW-3	11/21/2003 14:15	Water	3



ACC Environmental Consultants

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004.00

1220 W. Tennyson

Received: 11/24/2003 14:00

Prep(s):

5030B **MW-1** 

Test(s):

8260B

Lab ID:

2003-11-0824 - 1

Sample ID: Sampled:

11/21/2003 14:00

Extracted:

12/1/2003 16:55

Matrix:


Water

QC Batch#:

2003/12/01-01.62

Analysis Flag: o (See Legend and Note Section)

Compound	Conc.	RL	Unit	Dilution	A = 1,1	
Gasoline	ND		<del></del>		Analyzed	Flag
Methyl tert-butyl ether (MTBE)	i	20000	ug/L	400.00	12/01/2003 16:55	i
· · · · · · · · · · · · · · · · · · ·	19000	200	ug/L	400.00	12/01/2003 16:55	
Benzene	ND	200	ug/L	400.00	12/01/2003 16:55	
Toluene	ND	200	ug/L	400.00	12/01/2003 16:55	ĺ
Ethylbenzene	ND	200	ug/L	400.00	12/01/2003 16:55	
Total xylenes	ND	400	ug/L	400.00	12/01/2003 16:55	
Surrogate(s)			-3	12,00	12/01/2003 10:55	
1,2-Dichloroethane-d4	93.2	76	%	400.00	10/04/0000 10 55	}
Toluene-d8	95.7	I	1		12/01/2003 16:55	
		88	<u>%</u>	400.00	12/01/2003 16:55	





ACC Environmental Consultants

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004.00

1220 W. Tennyson

Received: 11/24/2003 14:00

Prep(s):

5030B

Test(s):

8260B

Sample ID:

MW-2

Lab ID:

2003-11-0824 - 2

Sampled:

11/21/2003 14:10

Extracted:

12/1/2003 17:17

Matrix:

Water

QC Batch#:

2003/12/01-01.62

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	ND	50	ug/L	1.00	12/01/2003 17:17	
Methyl tert-butyl ether (MTBE)	22	0.50	ug/L	1.00	12/01/2003 17:17	
Benzene	ND	0.50	ug/L	1.00	12/01/2003 17:17	
Toluene	ND	0.50	ug/L	1.00	12/01/2003 17:17	
Ethylbenzene	ND	0.50	ug/L	1.00	12/01/2003 17:17	
Total xylenes	ND	1.0	ug/L	1.00	12/01/2003 17:17	1
Surrogate(s)						
1,2-Dichloroethane-d4	91.5	76	%	1.00	12/01/2003 17:17	
Toluene-d8	101.3	88	%	1.00	12/01/2003 17:17	





**ACC Environmental Consultants** 

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004.00

1220 W. Tennyson

Received: 11/24/2003 14:00

Prep(s):

5030B

Test(s)

8260B

Sample ID: MW-3

Lab ID:

2003-11-0824 - 3

Sampled:

11/21/2003 14:15

Extracted:

12/1/2003 17:39

Matrix:


Water

QC Batch#:

2003/12/01-01.62

Analysis Flag: o (See Legend and Note Section)

Compound	Conc.	RL	Unit	Dilution	Analyzed	Flag
Gasoline	ND	5000	ug/L	100.00	12/01/2003 17:39	
Methyl tert-butyl ether (MTBE)	3100	50	ug/L	100.00	12/01/2003 17:39	
Benzene	ND	50	ug/L	100.00	12/01/2003 17:39	
Toluene	ND	50	ug/L	100.00	12/01/2003 17:39	
Ethylbenzene	ND	50	ug/L	100.00	12/01/2003 17:39	
Total xylenes	ND	100	ug/L	100.00	12/01/2003 17:39	
Surrogate(s)	ŀ					
1,2-Dichloroethane-d4	90.8	76	%	100.00	12/01/2003 17:39	
Toluene-d8	99.2	88	%	100.00	12/01/2003 17:39	





ACC Environmental Consultants

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004.00

1220 W. Tennyson

Received: 11/24/2003 14:00

		Bal	ch QC Report	
Prep(s): 5030B				Test(s): 8260B
Method Blank			Water	QC Batch # 2003/12/01-01.62
MB: 2003/12/01-01.	62-003			Date Extracted: 12/01/2003 16:03

	2.5.5.5.5.5.5.			Lifetime dellifi
Conc.	RL	Unit	Analyzed	Flag
ND	50	ug/L	12/01/2003 16:03	
ND	0.5	ug/L	12/01/2003 16:03	
ND	0.5	ug/L	12/01/2003 16:03	
ND	0.5	ug/L	12/01/2003 16:03	
ND	0.5	ug/L	12/01/2003 16:03	
ND	1.0	ug/L	12/01/2003 16:03	
	-			
88.4	76-114	%	12/01/2003 16:03	
97.8	88-110	%	12/01/2003 16:03	
	ND ND ND ND ND ND	Conc. RL  ND 50  ND 0.5  ND 0.5  ND 0.5  ND 0.5  ND 1.0  88.4 76-114	Conc.         RL         Unit           ND         50         ug/L           ND         0.5         ug/L           ND         0.5         ug/L           ND         0.5         ug/L           ND         0.5         ug/L           ND         1.0         ug/L           88.4         76-114         %	Conc.         RL         Unit         Analyzed           ND         50         ug/L         12/01/2003 16:03           ND         0.5         ug/L         12/01/2003 16:03           ND         1.0         ug/L         12/01/2003 16:03           88.4         76-114         %         12/01/2003 16:03





**ACC Environmental Consultants** 

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004.00

1220 W. Tennyson

Received: 11/24/2003 14:00

			Batch QC Re	port					3.2.1	
Prep(s): 5030B									Test(s)	: 82608
Laboratory Control Spike			Water				QC Ba	tch # 2	003/12/0	1-01.62
LCSD 2003/12/01-01.6			Extracted: 1 Extracted: 1	그 열린 글로 달				arta kartin	2/01/200 2/01/200	354 - NAPE 1
Compound	Conc.	ug/L	Exp.Conc.	Reco	very %	RPD	Ctrl.Lim	its %	Fla	ags
	LCS	LCSD		LCS	LCSD	%	Rec.	RPD	LCS	LCSD
Methyl tert-butyl ether (MTBE) Benzene	17.7 23.1	17.7 22.1	25.0 25.0	70.8 92.4	70.8 88.4	0.0 4.4	65-165 69-129	20 <b>2</b> 0		
Toluene	24.3	22.4	25.0	97.2	89.6	8.1	70-130	20		Ī
Surrogates(s)		ŀ								
1,2-Dichloroethane-d4	452	426	500	90.4	85.2		76-114			
Toluene-d8	524	484	500	104.8	96.8		88-110			





**ACC Environmental Consultants** 

Attn.: Ed Giacometti

7977 Capwell Drive, Suite 100

Oakland, CA 94621

Phone: (510) 638-8400 Fax: (510) 638-8404

Project: 6651-004,00

1220 W. Tennyson

Received: 11/24/2003 14:00

#### Legend and Notes

#### **Analysis Flag**

o

Reporting limits were raised due to high level of analyte present in the sample.



# **STL San Francisco**

Chain of Custody

1220 Quarry Lane ● Pleasanton CA 94566-4756 Phone: (925) 484-1919 ● Fax: (925) 484-1096 Email: info@chromat () con

Rete	erei	nce	#:	

Report To													Ana	alysis	Requ	est									
Attn: ED GIACOMETTI							,	not												ш					
Company: ACC ENVIRONMENTAL CONSULTANTS					260B	<b>~</b>	a Gel	1 BTEX Cl Etha		(OCs)		E	□ 608 □ 608	110		RCRA		л Н <sub>2</sub> О)	Alkalinity TDS						
Address: 7977 CAPWELL DRIVE, OAKLAND, CA						82605	Silic	Gas C EDB	S	AS (V		☐ Petroleum ☐ Total		83				miur e for	Alka	NO.					
P: (510) 638-8400 x 114					5/8021 EX	tics 21 🗆	≥		urbon 21	GC/A	/MS 625		EPA 8081 EPA 8082	70 1	7471]	3	Q	Chro d tim		SO SO					iners
Bill To: ACC Sampled By:				1- [1 8015/8021] [1 8260B	Purgeable Aromatics BTEX EPA - ☐ 8021 ☐ 82608	TEPH EPA 8015M ☐ Silica Gel	Fuel Tests EPA 8260B: □ Gas □ BTEX □ Five Oxyenates □ DCA, EDB □ Ethanol	Purgeable Halocarbons (HVOCs) EPA 8021	Volatile Organics GC/MS (VOCs)	Semivolatiles GC/MS □ EPA 8270 □ 625	ase	Pesticides   El	□ 8270 □ 8310	CAM17 Metals (EPA 6010/7470/7471)	Metals: © Lead © LUFT © RCRA	W.E.T (STLC) TCLP	Hexavalent Chromium pH (24h hold time for H <sub>2</sub> O)	Spec Cond. TSS	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0					Number of Containers	
Attn: ED Phone ext: 114					TPH EPA								geabl X EF	M17 N A 601	als: C	Z.⊆	훈됩	Sp	.: SIC				ا يُورِ	nber	
Sample ID	Date Time Mat Pres rix erv.			erv.	± <b>53.</b>	Pur BTB	声片	18 C	至到	\$0	Sen	G Si	Pes PC	P <sub>N</sub>	CAN CE	M C	00	00	00	Anions					
Mw-I	1/21/03	14:00	H <sub>2</sub> O	HEYLOG	X																				3
MW-2	1/21/03		#20	No.	×		-																		3
Mw-3	1/21/03		H2D	HOUSE	X																				3
				,																					
				,	i																				
								·																	
	-																								
				·													-				· ·				
																<u> </u>									
			<del></del>						-											<u> </u>					
Project Info. Sample Receipt						1) Relinquished by:					,2) F	2) Relinguished by:						3) Relinquished by:							
Project Name: # of Containers:						Edward Suconett					7	The Aller											_ }		
Project#: Head Space:					Signature Time						\$/9	Signature Time						Signature Time							
6681-004.00					Printed Name Date					<i>I/o</i> 3 ⊪te	<u>K</u> Prin	Printed Name Date					ء الخ	Printed Name Date				-			
PO#: Temp:				,	ACC ENVIRONMENTAL CONSULTANTS						3	122: H8													
Credit Card#: Conforms to record:						Company					Cor	Company					<sup>-</sup>   c̄	Company							
T Sub Other:					1) Received by:					2) 6	2) Received by:						3) Received by:								
Std 5 Day 72h 48h 24h Other:					Joan Ah 13:10						2) Notelyed by.						Signature Time								
Report: Secutine Level 3 Level 4 DEDD State Tank Fund EDF						Signature Time					/ Sigi	Signature Time						Signature Time							
Special Instructions / Comments:						PANON HOURS												\\UU\\U\\\\\\\\\\\\\\\\\\\\\\\\\\\\							
						Printed Name Date					Prin	Printed Name Date						Printed Name Date							
							COL01						Campani						\$7L-x						
,							Company							Company						Company					