



AUG EAS

**Workplan for Site Investigation  
at  
Young's Cleaners**

**Foothill Shopping Center  
10700 MacArthur Boulevard  
Oakland, California**

August, 1994

*NEW THARES  
DRAKE BOURNERS  
910 JAY THARES (CORPORATE)  
10700 MACARTHUR # 200  
OAKLAND - CA*

**Augeas Corporation  
780 Purissima Street  
P.O.Box 940  
Half Moon Bay, CA 94019  
Telephone: (415) 726-7700  
Facsimile (415) 726-1217**



AUG E A S

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 Introduction	2
2.0 Background	2
2.1 Operation as a Dry Cleaners	2
2.2 Request by County for Site Investigation	2
3.0 Purpose and Scope Of Work	3
4.0 Technical Approach	5
4.1 Phase I- Field Testing	5
4.2 Phase II- Laboratory Analysis	6
4.3 Phase III- Report of Findings	6
5.0 Methodology	8
5.1 Drilling and Soil Sampling	8
5.2 Monitoring Well Installation	8
5.3 Well Development and Sampling	9
5.4 Laboratory Analyses	10
5.5 Decontamination	10
5.6 Drilling Spoils	10
6.0 Project Schedule	11

Figure 1- Site Location Map

Figure 2- Monitoring Well/Soil Boring Location Map

Foothill Square, 10700 MacArthur Blvd., Oakland, California

---



This workplan was prepared under the supervision of a registered geologist. All statements, conclusions and recommendations are based solely upon field observations and analytical test results related to the work performed by Augeas Corporation.


Site conditions are subject to change with time; therefore, our conclusions result only from the interpretation of present conditions and available site information. This report was prepared in accordance with accepted professional standards and technical procedures as certified below.

Reviewed by:

Charles D. Conway  
Charles D. Conway, Registration No. 4530  
Project Geologist

August 19, 1999

Date



---

Project Number: DRA0894



## 1.0 INTRODUCTION

Augeas Corporation has prepared this Workplan for site investigation of the subject site located at 10700 MacArthur Boulevard, Oakland, California. The site is located in the Foothill Square Shopping Center at the intersection of Foothill Boulevard and MacArthur Boulevard. The site location is shown in Figure 1, "Site Location Map".

## 2.0 BACKGROUND

### 2.1 Operation as a Dry Cleaners

The site has been operated as Young's Cleaners since 1984. A coin operated dry cleaner, Norge Cleaners, operated at the location between 1962 and 1980. In July, 1980 the current owners took over management of the property.

*What is the area of the site.*

In December, 1980 the cleaners was placed on the CALSITES list for further evaluation. On October 1, 1993, Augeas Corporation contacted Mr. Don Cox, Unit Chief, Site Mitigation Branch, Site Evaluation Unit, Department of Toxic Substances Control, Berkeley, California concerning the status of the investigation. Mr. Cox indicated that the original site inspection "checklist" that had been filed showed that the site had been placed on the CALSITES list because of its SIC classification and not because of any identified contamination problems.

### 2.2 Request by County for Site Investigation

On March 23, 1993 Alameda County Health Care Services Agency requested that the vertical and lateral extent of perchloroethylene contamination, discovered on the shopping center site by ARCO while investigating its release from adjacent underground tanks, be investigated by the shopping center owners.

According to the correspondence from the Alameda County Health Care Services Agency, "data generated by ARCO's investigation suggests



AUG E A S

that perchloroethylene detected in ground water samples from their monitoring wells came from [the shopping center] site."

### 3.0 PURPOSE AND SCOPE OF WORK

The purpose of the proposed investigation will be to evaluate the extent of dissolved fuel hydrocarbons and perchloroethylene present in groundwater at the subject property in accordance with the criteria specified in the Regional Board Staff Recommendations for Initial Evaluation and Investigation of Underground Tanks, Appendix A, Tri-Regional Recommendations.

The scope of the proposed investigation will be accomplished by and limited to: exploratory boring and soil sampling, installation of two groundwater monitoring wells, development and sampling of the groundwater wells, and chemical analysis of soil and groundwater samples. The completed Site Investigation Report will provide a summary of existing groundwater conditions. The proposed scope of services will include the following tasks:

- Preparation and submittal of a Technical Work Plan acceptable to the Alameda County Health Care Services Agency and in accordance with Alameda County guidelines.
- Obtaining necessary permits prior to the commencement of the field portion of the investigation;
- Drilling and sampling of soils for lithologic evaluation and laboratory analysis;
- Installation of one 2-inch diameter groundwater monitoring well near the rear of the store, and one 2-inch diameter monitoring well near the front of the store, if access conditions permit;



- Well development and sampling of the wells installed by Augeas Corporation and sampling of well WGR MW-2 installed by Western Geologic Resources (Figure 2);
- Chemical analysis of soil and groundwater samples to assess the presence and concentrations of fuel hydrocarbons and solvents;
- Preparation of a written report to present our findings, conclusions and recommendations.
- Arrange for a survey of the horizontal locations of all the nearby existing monitoring wells and the mean sea level elevations of their wellheads. We will measure the water level in each well, and prepare a local ground water gradient map showing ground water elevation contours.



#### 4.0 TECHNICAL APPROACH

Based upon review of previous investigations conducted at the subject property and published data regarding local geographic and hydrologic conditions, Augeas Corporation developed the following technical approach for the proposed investigation.

In order to accomplish the goals established for the proposed investigation, the project would be separated into three distinct work items as follows:

**Field Investigation** to advance three exploratory soil borings for the purpose of logging subsurface conditions and obtaining soil samples for chemical analysis. Two of the soil borings will be completed to a depth of about 30 feet, and will be completed as monitoring wells. Since the depth to ground water ranges from 24 to 27 feet below grade, the screened interval will extend from approximately 20 feet to 30 feet below grade.

**Laboratory Analysis** of soil and ground water samples obtained from the field investigation to evaluate the presence and concentration of chlorinated solvents, and petroleum constituents.

**Report Preparation** summarizing the results of the chemical analysis and the evaluation of applicable mitigating and/or remedial technologies appropriate for the site based upon data obtained from current and previous investigations.

Further description of these work phases is presented in the following discussion.

##### 4.1 Phase I - Field Testing

Augeas Corporation will install three exploratory soil borings on the subject property at the locations shown in Figure 2. These soil borings

*What EPA method 8010-1 soil? 8/20*



will provide additional data regarding the presence of chlorinated solvents and fuel hydrocarbons present in the soil and groundwater. Field screening of the soil samples will be used to detect variations of contaminant concentrations with depth.

Augeas Corporation will arrange for a survey of the horizontal locations of all the existing monitoring wells with respect to streets and property lines, as well as the mean sea level elevations of their wellheads. The water level in each well will be measured, and a local ground water gradient map will be completed showing ground water elevation contours.

The groundwater monitoring wells nearby will be utilized to evaluate lateral migration of hydrocarbons in groundwater, and their surveyed locations and elevations will provide data for assessing the groundwater quality and gradient. ~~No characterization of site-specific hydrogeologic parameters, such as a pumping test, will be performed during this investigation.~~

*So we dont know that the flow is  
or w flow is*

#### 4.2 Phase II- Laboratory Analysis

Soil and ground water samples will be maintained and transported under proper chain-of custody protocol to a State-approved laboratory for chemical analysis. Soil and ground water samples will be analyzed to detect the presence and concentration of benzene, toluene, xylenes, ethylbenzene (EPA Method 8020) and total petroleum hydrocarbons as referenced to gasoline (EPA Method 8015 [modified]) and EPA Method 8240/624 for chlorinated solvents.

#### 4.3 Phase III - Report of Findings

Augeas Corporation will prepare an investigation report at the completion of the field, laboratory, and office analysis portions of the investigation. The report will detail the findings of the investigation, and include provisions for control of contaminated groundwater, if analytical data indicate a need for such control.



**Foothill Square, 10700 MacArthur Blvd., Oakland, California**

---



Augeas Corporation will then prepare a remedial action plan to evaluate remedial and mitigating alternatives based upon data obtained. All reports will be prepared under the supervision of and signed by a State of California Registered Civil Engineer or Geologist.



## 5.0 METHODOLOGY

### 5.1 Drilling and Soil Sampling

Drilling will be performed utilizing a truck mounted drill rig equipped with 8-inch continuous flight hollow-stem augers. Augeas Corporation's geologist or engineer will be present during drilling to assist in obtaining relatively undisturbed samples of the subsurface materials, to maintain a log of borings, to field screen samples with a device capable of detecting volatile organic hydrocarbons as a trace gas, and to make observations of the site conditions.

Soils will be sampled at approximately 5-foot vertical intervals (or more frequently as deemed appropriate by the field geologist or engineer), commencing at an approximate depth of five feet below the existing grade. Samples will be obtained by means of a California Modified sampler lined with stainless steel sleeves or rings. The samples will be advanced by blows from a 140 pound hammer falling 30 inches. Soil will be classified according to the Unified Soil Classification System.

Upon retrieval, samples retained for chemical analysis will be contained with a plastic caps over Teflon™ seals, and taped at each end. The samples will be stored in a chilled container and shipped under proper chain-of-custody protocol to a certified analytical laboratory. A minimum of two samples will be analyzed from each boring. Field screening results will be utilized to assist in the selection of soil samples for analysis.

### 5.2 Monitoring Well Installation

The boreholes will be advanced to about 30 feet below ground surface. The design of the groundwater monitoring wells is in general compliance with the State of California Department of Water Resources Bulletin 74-90 Monitoring Well Standards (DWR 163907).

*Screening  
20 to 30 feet  
GW depth  
15 to 27 feet*



The monitoring wells will be constructed through hollow stem augers using 2-inch flush threaded PVC Schedule 40 casing, since the static groundwater level is approximately 24 to 27 feet below ground surface. The screened intervals will allow an approximately five-foot interval above and below the stabilized groundwater level. A No. 2/12 medium graded sand will be used as a filter medium around the screened interval and completed to a depth of 10 feet above the well screen. A seal composed of bentonite pellets will be placed to an approximate thickness of one foot above the sand. The pellets will be hydrated to prevent the entry of portland cement grout into the screened interval.

From the bentonite seal to the surface vault, the remaining annulus will be back-filled with a sand/cement slurry with approximately 3 per cent bentonite added.

Expansion locking caps will be installed on the wellheads, and a water-tight, traffic-rated surface vault will be placed at grade for well security.

### **5.3 Well Development and Sampling**

The wells will be developed by hand bailing and surging and/or by using a positive displacement pump. Well development methods which employ air-lift or the introduction of air into the well will not be used. The wells will be developed until they are relatively free of sediment and turbidity.

The wells will be sampled with a disposable PVC bailer. The depth to ground water will be initially measured with a well sounder. Each well will then be purged of a minimum of four well casing volumes, and it will be sampled following stabilization of pH, temperature and specific conductivity. If the wells are slow to recover while they are being purged, they will be sampled following recovery to 80 percent of their original stabilized level.



#### **5.4 Laboratory Analysis**

The laboratory analyses will be focused on the detection of chlorinated solvents and fuel hydrocarbon compounds. The following methodologies will be specified for the chemical analyses of soil and ground water samples:

EPA Method 602/8020 for BTEX

EPA Method 8015 (modified) for Total Petroleum Hydrocarbons (TPH) as gasoline

EPA Method 8015 (modified) for Total Petroleum Hydrocarbons (TPH) as stoddard solvent

EPA Method 8240/624 for chlorinated solvents

#### **5.5 Decontamination**

Between soil sampling attempts, the sampler will be disassembled and washed in a trisodium phosphate (TSP) solution, rinsed twice with clean tap water, and re-assembled with to minimize the potential of spreading any contaminants among samples.

#### **5.6 Drilling Spoils**


Auger cuttings from the drilling operation will be placed in drums and retained on-site. The results of chemical analysis will be used to evaluate the appropriate disposal of any contaminated auger cuttings.





## 6.0 PROJECT SCHEDULE

Consultant should be prepared to begin this study upon receipt of approval for the work from Drake Builders. The Alameda County Health Care Services Agency will request notification before starting any work at the site. It is estimated that the proposed scope of services will require about six to eight weeks to complete. This schedule is partially dependent on the scheduling of drilling equipment, local weather restrictions, access to the site, permitting requirements, and time required for specific chemical analysis. A visit to the site for the field portion of the investigation is to be arranged through the subject property owners.

Figure 1  
Site Location Map



SCALE 1:24 000



SAN LEANDRO, CALIF.

NW 4 HAYWARD 15' QUADRANGLE  
N3737.5—W12207 5/7 5

1959  
PHOTOREVISED 1980  
DMA 1559 II NW · SERIES V895




QUADRANGLE LOCATION

<p><b>AUGEAS CORPORATION</b></p>	<p><b>Figure 1- Site Location Map</b> 10700 MacArthur Boulevard, Oakland, CA</p>	<p>jf 09/16/93</p>
----------------------------------	--	------------------------

Figure 2  
Monitoring Well/ Soil Boring Location Map





**Augeas Corporation  
Half Moon Bay, CA**

**Fig. 2 -- Site Location Map**

10700 MacArthur Blvd Oakland, CA

Drawn by  
Carol Lapinski

8-18-94  
DYS/HD

Scale  
1" = 100'