Golder Associates Inc.

180 Grand Avenue, Suite 250 Oakland, CA USA 94612 Telephone (510) 239-9000 Fax (510) 239-9010

June 19, 1998

Ms. Susan Hugo Alameda County Health Care Services Agency Department of Environmental Health 1131 Harbor Bay Parkway, Room 250

Alameda, California 94502

Subject: Work Plan for Removal, Onsite Transfer and Offsite Disposal of Asbestos-containing Soils, 2200 Powell Street, Emeryville, California

Dear Ms. Hugo:

Golder Associates Inc., (Golder) has prepared this Work Plan on behalf of Spieker Properties for the subject site. In this Work Plan we have presented the scope of work, health and safety plan and waste management plan for the removal, onsite transfer and offsite disposal of recently discovered asbestoscontaining soils at the site. A Site Location Map is shown in Figure 1 and a Site Plan is shown in Figure 2.

During April 1998, while excavating for placement of irrigation water pipelines in existing landscaped islands at the site, contractors retained by Spieker Properties encountered soils containing gray fibrous material. Approximately 150 cubic yards of soils were excavated from the landscaped islands and stockpiled at the site. At the request of Spieker Properties, Golder collected soil samples from the excavated soil stockpiles and analyzed for asbestos. Asbestos was suspected to be present as soils encountered in exploratory boreholes drilled by others previously in the random fill materials at the site, contained asbestos at various locations. Results of analyses indicated that asbestos was present in soil samples. Currently these soils are stockpiled at the site and are covered with plastic liners.

Spieker Properties is also planning to remove two 10,000 gallon underground storage tanks (UST) at the site. A Closure plan for the removal of these USTs was approved by the Alameda County Health Care Services Agency (ACHCSA) in March 1998. Spieker Properties requested that Golder pursue the option of backfilling the recently encountered asbestos-containing soils into the UST excavation once they have been removed. On May 27, 1998, Golder submitted a letter to Regional Water Quality Control Board (RWQCB) requesting their approval to translocate the asbestos-containing soils to the UST location (a copy of this letter is included as Attachment A). Also included with this letter is a letter from RWQCB which has indicated that they are the appropriate agency for handling regulatory activities at the site. On June 4, 1998 Golder submitted a letter to RWQCB documenting their approval to translocate asbestos-containing soils to the UST location (a copy of this letter is included as Attachment B).

At this time we are submitting a copy of this work plan to ACHCSA and Bay Area Air Quality Management District (BAAQMD) for review and approval of the field work. Permission to translocate asbestos-containing soils has already been granted by the designated lead agency RWQCB.

pg 2 - additional recuration

pg 3 = office disposed blands

add relification to

ACDEH prior to any

deglas I trenching

Dapper a - Housedaras

Disposed facility 
valuable and facility 
any automic sail containing

any automic sail containing

#### SCOPE OF FIELD WORK

The scope of field work will be performed by an asbestos abatement contractor retained by Spieker Properties that is licensed to work with asbestos-containing materials. The contractor will obtain appropriate permits and provide agency notifications prior to performing the field work. Golder will document the field activities and provide sampling and monitoring during the field work. Following the removal of the USTs, the scope of work will be as follows:

- 1. Translocating soils from landscaped islands and backfill in former UST location
- 2. Additional excavation of soils in landscaped islands and offsite disposal  $-\nabla$ ?

### Health and Safety Measures During the Field Work

The scope of work listed above will be performed according to appropriate regulations governing asbestos abatement, worker and public health and safety and engineering controls. These health and safety and engineering controls include but may not be limited to the following:

- Public egress and ingress will be controlled through the use of barriers and mandated signs,
- Work will be scheduled during non-working hours to limit disturbance to surrounding businesses and public,
- Security officers will be appointed to limit disruption to project activities,
- Documentation will be obtained to verify that asbestos abatement-trained workers as defined in 40 CFR Part 763 perform work on this project,
- Asbestos workers will be fitted in Tyvek suits and HEPA respirators during the project,
- All workers will be documented as having completed appropriate Asbestos Hazard Emergency Response Act (AHERA) training as well as passing the respirator fit test,
- Workers will wear appropriate health and safety gear.
- Decontamination facilities will be set up for workers, equipment and work areas,
- Air monitoring will be performed inside and outside the work area, and
- Soils and plastic barriers will be wetted to prevent asbestos fibers from becoming airborne.

### Translocating Soils from Landscaped Islands and Backfill in Former UST Location

Currently approximately 150 cubic yards of soils are stockpiled and covered with plastic liners at the landscaped islands at the site. These soils will be translocated to the former location of USTs and backfilled appropriately. During the field work, a Golder asbestos certified consultant will document the field activities and perform air monitoring in the area of the work.

Prior to moving the soils in the landscaped islands plastic liners will be removed and soils will be wetted down. Once the soils have been wetted down sufficiently, soils will be moved to the UST area using a front end loader to limit soils disturbance and potential asbestos fiber release.

During the placement of soils in the UST excavation, soils will be wetted continuously as they are being placed in the excavation. Soils will be placed in approximately one-foot lifts, and will be compacted to preset specifications using a backhoe equipped with a compactor. Soil wetting will be performed during soil compaction procedure. Approximately two-foot thick cap of clean soils will be placed over the asbestos-containing soils in the UST area.

As discussed in this report earlier, permits to remove USTs at the site are already in place. Prior to removing the USTs, soils from the top of the USTs will be analyzed for asbestos. In the event soils above the USTs are found to be impacted with asbestos, the soils will be wetted down sufficiently to limit exposure of asbestos fibers into the air. Excavated soils will be placed in stockpiles and covered with plastic liners; these soils may be replaced in UST excavation or disposed at off-site location – appropriately.

### Additional Excavation of soils in Landscaped Islands and Offsite Disposal

Spieker Properties is proposing to remove approximately top one-foot of soils from all landscaped islands shown in Figure 2 and replaced with clean cap of soils imported from offsite. This is being performed to facilitate growth of landscape plants and to limit possible future worker and public exposure to the residual asbestos-containing soils that may be present in the landscaped islands. Additionally, excavation will be performed at various locations in the landscaped islands for planting palm trees. During the field work a Golder certified asbestos consultant will document the field activities and perform air monitoring in the area of the work. Additionally Golder will document the offsite disposal of soils using the appropriate hazardous waste manifest.

We estimate a total of approximately 200 cubic yards of soils will be excavated for the removal of top one foot of soils and for the placement of palm trees in the landscaped islands. Soils generated will be manifested and disposed at a landfill permitted to accept asbestos-containing waste. Excavation will be performed using a backhoe, and prior to performing excavation soils will be sufficiently wetted. Excavated soils will be placed in appropriately lined dump trucks. During the process of excavating the soils and placing in dump trucks, water will be sprayed as appropriate to limit the exposure of possible asbestos fibers into the air. Once a dump truck has reached its loading capacity, soils in the dump truck will be appropriately covered and secured and hauled to licensed offsite facility. Upon completion of proposed excavation in the landscaped islands, clean soils brought from offsite will be placed and compacted appropriately in the landscaped islands.

#### EXCAVATION MANAGEMENT PLAN

For future use and worker notification, Spieker Properties will develop an Excavation Management Plan. This plan will include, at a minimum, measures for:

- Preparation of site specific health and safety plans
- Capping exposed areas with buildings, asphalt concrete and clean fill in landscaped areas
- Procedures for handling potentially hazardous materials
- Procedures for notification to workers.

In summary, Spieker Properties is planning to transport and use stockpiled soils from the landscaped islands to backfill the UST pit. This plan was approved by the RWQCB who has indicated that they are the appropriate agency for handling regulatory activities at the site.

At this time we are requesting ACHCSA and the AQMD to provide an expedient review and approval of this work plan in order to allow Spieker Properties to perform work in timely manner and meet their schedule for completing the project. In case you have questions regarding this letter, please call us at (510) 239 9000.

Sincerely,

GOLDER ASSOCIATES INC.

Kevin A. Roberts, C.A.C., R.E.A.

. Cherm for

Project Environmental Scientist

Charles Almestad, R.G, C.Hg.

Associate

KAR/CA/mcs


Attachments:

Figure 1 – Site Location Map

Figure 2 – Site Plan


Attachment A – Golder Report to RWQCB dated May 27, 1998 Attachment B – Golder Letter to RWQCB dated June 4, 1998

cc: Jeff White, Spieker Properties, Emeryville, California Ravi Arulanantham, RWQCB, Oakland, California Dennis Baker, BAAQMD, San Francisco, California



PROJECT NO. 973-7187 DRAWING NO. 5256 DATE 11/6/97 DRAWIN BY DVR

**Golder Associates** 



## ATTACHMENT A

Golder Report to RWQCB dated May 27, 1998

#### Golder Associates Inc.

180 Grand Avenue, Suite 250 Oakland, CA USA 94612 Telephone (510) 239-9000 Fax (510) 239-9010



Our Ref.: 973-7187

May 27, 1998

Mr. Curtis Scott
Regional Water Quality Control Board (RWQCB)

San Francisco Bay Region 2101 Webster Street, #500 Oakland, California 94612

RE: ASBESTOS CONTAINING SOILS
WATERGATE OFFICE COMPLEX
2200 POWELL STREET, EMERYVILLE, CALIFORNIA

Dear Mr. Scott

Following our telephone conversation with Mr. Alan Friedman on May 14, 1998, we have prepared this letter on behalf of Spieker Properties, the owners of the Watergate Office Complex in Emeryville, California. The Watergate Office Complex consists of three multi-story commercial office buildings (Towers I, II and III) on the north side of Powell Street. The site location is shown in Figure 1, and the site plan is shown in Figure 2.

This letter was prepared to seek approval for the placement of asbestos containing soil into an underground storage tank (UST) excavation (which will be capped) on-site as opposed to off-site disposal. These asbestos containing soils were encountered at the site during trenching for placement of irrigation conduit.

#### SITE BACKGROUND

Historically the site was a part of San Francisco Bay. Beginning in the 1940s, and until the mid 1960s the site and the surrounding area was filled. Impoundment dikes of soil, rocks and debris were constructed on bay tidelands, and then the area within the dikes was filled with materials including construction debris, foundry casing sands and slag, soil and industrial wastes. In approximately 1968, the property was purchased by F. P. Lathrop and the entire site and the surroundings were capped with engineered fill, pavement and structural foundation slabs. The existing buildings constitute the first development of the site.

In 1989, Woodward-Clyde Corporation (WCC) performed Phase I, II and III environmental assessments at the site. Five ground water monitoring wells were installed around the property. A range of chemical constituents were detected in soil and ground water samples collected from the site. Available WCC boring logs illustrating the types of construction related materials which were encountered during drilling are included as Appendix A. Among other chemical constituents, petroleum hydrocarbons were detected in water samples collected from all ground water monitoring wells, and their presence was attributed to the fill material placed in the diked areas. WCC concluded that there is no significant threat to human health and the environment because the site is capped with engineered fill, and the concentrations are not of sufficient magnitude.

During late 1996 and early 1997, Golder performed a Phase I environmental assessment at the site on behalf of Spieker Properties who was planning to purchase the property. Golder consulted with the Regional Water Quality Control Board (RWQCB) San Francisco Bay Region regarding the need for further action at the Watergate Office Complex. RWQCB staff reviewed the WCC reports and aerial photographs and concluded that based on the information they reviewed, the site was not a significant concern to them. The RWQCB staff considered the site to be an area of "random fill" and therefore not subject to reporting requirements under the California Code of Regulations, Title 23, Chapter 15. Further, the RWQCB indicated that since the site is located adjacent to the San Francisco Bay, their agency is the appropriate agency for handling regulatory activities associated with the site. A letter dated December 30, 1996 from RWQCB summarizing their opinions is included as Appendix B.

#### RECENT SITE ACTIVITIES

Since acquiring the site in early 1997, Spieker Properties has been performing construction work at the site including remodeling building interiors, trenching for irrigation conduit and re-landscaping. As a part of these upgrades, Spieker Properties will also be removing two existing USTs from the site. Reportedly, these double-walled USTs were installed at the site in 1984-1985 and have been passing tightness tests.

### **Underground Storage Tanks Removal**

During January 1998, a contractor retained by Spieker Properties submitted a Closure Plan to Alameda County Health Care Services Agency (ACHCSA) for the removal of two 10,000 gallon capacity double walled USTs from the site. Along with this Closure Plan Golder submitted a letter to ACHCSA presenting the site background information. In this letter Golder pointed out that soils and ground water beneath the site and in the surrounding area are known to contain petroleum hydrocarbon as a result of the random fill materials. Therefore, Golder proposed no over excavation to be performed after the removal of USTs to assess or remove potentially affected fill material at the site. Golder also proposed to backfill the excavation immediately after the removal of USTs, which will avoid collection of ground water in the excavation and thus save significant costs associated with dewatering and disposal. This closure plan was approved by the ACHCSA in March 1998. Spieker Properties is planning to remove these USTs in the near future.

### **Trenching for Irrigation Conduits**

During April 1998, Spieker Properties requested that Golder inspect soil stockpiles that their contractors had excavated during trenching operations for the installation of irrigation conduits. Approximate location of irrigation trenches is shown in Figure 2.

Golder staff observed that approximately 100 cubic yards of soils were excavated during the irrigation trenching operation and stockpiled at the site. Golder staff observed gray fibrous material present in the stockpiled soils at the site. Golder recommended that these soil stockpiles be wetted down and covered with plastic liners. On April 2, 1998 one composite soil sample was collected from these stockpiled soils and on April 16, 1998, 20 additional soil samples were collected from these stockpiled soils for asbestos analysis. Samples were transported to R. J. Lee Group, Inc. in San Leandro, California for the analysis of asbestos by polarized light microscopy (PLM). Analytical results indicated that asbestos was present in 13 out of 21 soil samples at or above 1 percent. The analytical results are enclosed as Appendix C.

On April 16, 1998, one additional soil sample was collected from the southern-most landscaped island for landfill acceptance determination (profiling). This soil sample was transported to Curtis & Tompkins, Ltd., in Berkeley, California for analyses of toxicity characteristics leaching potential (TCLP) for semi volatile organic compounds (SVOC) by EPA Method 8270, TCLP volatile organic compounds (VOC) by EPA Method 8260, California Assessment Manual (CAM) 17 Metals by EPA Method 7000 series, total petroleum hydrocarbons (TPH) quantified as gasoline, TPH quantified as diesel, and Total recoverable petroleum hydrocarbons quantified as oil and grease. Results of sampling performed for landfill acceptance indicate that TPH quantified as gasoline, semi-volatile organic compounds and volatile organic compounds were not reported above laboratory detection limits. TPH quantified as diesel was reported at 66 milligrams per kilogram (mg/kg) and total oil and grease was reported at 650 mg/kg. Metals were reported at concentrations well below total threshold limit concentrations (TTLC). The laboratory report for landfill acceptance analysis is enclosed in Appendix C.

#### RECOMMENDATIONS

We have obtained preliminary cost estimates to dispose of 100 cubic yards of asbestos affected soil at a landfill. Estimated costs for disposing soils off-site are very high (up to approximately \$200,000). Given that the soils surrounding the UST excavation contain similar asbestos containing construction fill materials, we propose that Spieker properties be granted permission to place stockpiled soils at the bottom of the UST cavity following UST removal. The asbestos containing soils would be covered by an approximately two foot cap of clean imported soil to reduce future exposure to these soils.

The soils will be moved on site under controlled conditions and in accordance with appropriate regulations including OSHA and BAAQMD. We understand that these soils should be removed from their current location as soon as possible, therefore, your expedient response and approval in this matter will be appreciated.

May 27, 1998 973-7187

If you have any questions, comments, or require additional information regarding this proposal, please call the undersigned at (510) 239-9000.

Sincerely,

GOLDER ASSOCIATES INC.

Rajeev Cherwoo Project Engineer

Charles H. Almestad, R.G, C.Hg.

Associate

RC/CA/mcp

Attachments:

Figure 1 Site Location

Figure 2 Site Plan

Figure 3 Approximate Location of Stockpiled Soil Samples Collected for Asbestos

Analysis


Appendix A WCC Boring Logs

Appendix B Letter from RWQCB dated December 30, 1996

Appendix C Laboratory Reports of Asbestos Analysis of Soil Samples and Landfill Profiling


Soil Samples Collected in April 1998

cc: Jeff White, Spieker Properties (w/attachments)




REFERENCE: USGS MAP, OAKLAND WEST QUADRANGLE 1959, PHOTOREVISED 1980.

SITE LOCATION MAP 2200 POWELL STREET, EMERYVILLE, CA



16

4000



APPENDIX A
WCC Boring Logs

NG LOCA	190021.08	DRILLER	120000	1-00 T	DA	TE ST	ART	ED	lon	uary	13 1	989
LING AGE	NOOS COMMINGEN (CONTRACTOR CONTRACTOR CONTRA	DRULLER	Jim /	Gary	CO	TE FR		_	_	oary		MPLER 2'California
TIMG EOU	OINE 10	11.			DE	PTH		DIST.	26.5	_	1	Modified Type
LLING MET	o rionottatoni riogoto	DRILL BIT	CME Ca	rbide		OF MPLE	S		_	/A		DMPL 24 HRS.
E AND TYP	E OF CASING 2" PVC					VEL		FIRST		1/2	_	N/A N/A
E OF PER	FORATION 0.010" Slotted	FROM	5 10	25 PL	u	OGGE	D B	Y:			°	HECKED BY:
E AND TYP	PE OF PACK Lonestar #2/12 Monterey Sand	FROM	4 to 2.5 to	25 A.	1	Chu	uck	Rami	bo			Alan Lattanner
YPE OF	NO. 1 Bentonite Pellets	FROM	0 το	2.5 R.	1						1	
	No. 2 Neat Cement	FROM		HICLOG	4	-	_		AMPL	ES	+	REMARKS
(Jeal)	DESCRIPTION		Lithology	Piezomet	or .	Water	rzometer ta	Drive	_	_	ounts	(Drill Rate, Fluid Loss, Odor, etc.)
ě	FILL : CLAYEY SAND (SC)			Wistandia	12	\$8	ĒÖ	충	SE	EE	8	
	-brown -very moistefth fine point, FILL - SR.TY CLAY (CL) -dark gray -moist -with concrete rubble		-		***		5 -	1	1		9 50	
10-	FILL - TAR PAPER -dark reddish brown -very hard  FILL - SILTY CLAY (CL) -gray -with concrete and wood rubble						10	- 2	1 1 1		1 1 2	
15	-pink -with asbestos -very soft					E 1	15	1 2 2	1		1	OVA = 2 ppm
20-	SILTY CLAY (CL) -dark gray -with shell fragments						20		4		1111	
25-	-with gravel -light gray -moist -stiff						2	5	5	;		5. A. 10
30-	Bottom of boring at 26 1/2' Augered to 25'							30 -				
35								35_				SHEET 1 OF 1

ORING LOC	MITTE:				ELEV	ATIO	N A	ND DA	TUM				
RELLING AC	Datoni Exporatori	DRILLER	Jim/G	ary	DATE	E STA	RTI	D	Jan	wary	12,1	989	
RILLING EC	CME - 75				DEP	PLETI	юн	2	5'		SA	MPLER 2°C	alfomia
RILLING M	ETHOD 8" Hollowstern Augers	DRILL BIT	CME Ca	utbide	NO.	OF PLES	10	NST.	N	/A	UN	IDIST. N/A	
IZE AND TY	PE OF CASING 2" PVC		21		WAT	ER		IRST		0.5	α	N/A 24 H	RS. N/A
	REFORATION 0.010" Slotted	FROM	5 10	25 R.	-	GGED	BY	:		W.W	C	HECKED BY:	IVA
IZE AND T	PPE OF PACK Lonestar #2/12 Monterey Sand	FROM	4 TO	25 p.									
TYPE OF	NO.1 Bentonite Pellets	FROM .	2.5 TO	4 PL		Chuc	K I	Ramb	0			Alan Lattani	ner
SEAL	No. 2 Neat Cement	FROM	0 10	2.5 R.	1								
			GRAP	HC LOG		ě	T	8/	MPL	ES	1	REMARKS	
	DESCRIPTION		Lithology	Piezomet		Jerome	=	Number	admin ampar	Feet.	onut	(Drill Rate, Fluid Lo ric.)	ms, Odor,
	FILL - SILTY SAND (SM)			:4T-	E.	1	٦	PZ	0.2		4	OVA = 0 ppm	
-	-with gray gravel -brown				3		4	4	-				
1	-moist					1	+	1	:			12220000	Mark Common
5	FILL - SILTY CLAY (CL) -with sand lenses -black						+					OVA = 8 ppm t drum of cut Petroleum Odd	from the lings
-	: Torrison		1			5		2	1	3333E	12 16	from the de	
-							_		-		4		
] -{	-with concrete and wood debris				in.	aes	-				1		
10			1		Ŧ	<b>#</b>	-						
1,07			1			10	)-	3			Ŧ		
1	a		1				Ī		1		7		
1 -			1					l			- 1		
	20		1					1		Н	-1	1	
15-						h	5-	1	1		14	OVA = 50 pp	- Mana
	-with rooting paper, asphalt shingles, ar	d wood debris	1			- 1	Ī	1	1		10	Gundic	oun gra
		175				- 1				П			
. +-	SILTY CLAY ICHO					- 1		1		П			
20	SILTY CLAY (CH) -dark gray -moist		1			2	0-	-	1		ᠴ	OVA = 0 ppm	1
	-very soft					- 1		5	1		츳	2000 CONTRACTOR (10)	
1 1							- 1	]					
1 -							1	4					
25-	Rottom of horizon at OCI		_	993	4	<u>-</u>  2	25-	+	$\vdash$	$\vdash$			
1 1	Bottom of boring at 25'							1					
				1 2									
-								]					
30 —						1	30 -	-					
								+					
] ]					- 1			1					
1								]					
35_				1			35						

ORING LO	CATION MW-3				ELEVAT	пон	AND D	ATUM		
RILLING A	Datoill Exploration	DRILLER	Jim	Gary	DATE S			Jan	uary 1	13,1989
HILLING E	QUIPMENT CME - 75				COMPL	ETIO	N :	21 1/2		SAMPLER 2'California Modified Typ
RILLING N	ETHOD 8" Hollowstern Augers	DRILL BIT	CME Ca	ırbide	NO. OF		DIST.	N	Ά	UNDIST. N/A
ZE AND T	YPE OF CASING 2" PVC				WATER	-	FIRST	12	,	COMPL. 24 HRS.
PE OF PE	RFORATION 0.010" Slotted	FROM	5 то	21.5 PL	LOGG	ED 8	Y;			CHECKED BY:
ZE AND T	YPE OF PACK Lonestar #2/12 Monterey Sand	FROM	4 TO	21.5 R.	] _		_			
TYPE OF	NO. 1 Bentonite Pellets	FROM	2.5 TO	4 Ps	Ch	NUCK	Ram	bo		Alan Lattanner
BEAL	No. 2 Neat Cement	FROM	0 то	2.5 PL	1					
			GRAP	HIC LOG		ter	-	AMPLE	s	REMARKS
9	DESCRIPTION		Lithology	Piezomete Installation	Water	Plezorne Deta	Amper	Sample Number	(Feet.)	(Oriti Rate, Fluid Loss, Odo etc.)
	FILL - SILTY CLAY (CL)			تابات	7	-	DZ.	0,2		1
4	-moist									
4	-with sand -dark gray			1	2	١.	-			V *
					7		4			
5-			1			5 -		1		
1			4		naves	1	1	-		L.
]					¥	1	7	$  \  $		1
4							]		-	
10-	FILL - ASBESTOS (FIBERGLASS?)		4			10-	1	-		2 OVA = 9 pom
+	-pink and white libers -very soft						- 2			No Odor
-	ACIA STIF		1			1	┨			
1			1				1	Ш		
15-			1			L	1			
·	SILTY CLAY (CL)		$\dashv$			15	_ 3	:		OVA≈2ppm
4	-dark gray -moist		1			1	+	1		1
+	-very soft -with shells -"Bay Mud"		1				4			
20_	- cony many						-			
"]			1			20	4	;		OVA = 0 ppm
-1-			_			+	1	+;-		<del>-</del>
4	Bottom of boring at 21 1/2'			1			1			1
-							-		П	
25-				4		25	$\dashv$			
]				8			7			
1							]			
4							_			
30 —						30	4			
+							-			
]							-			
]							1			
35_				1	- 1	h.		1		

NG LOC	munity.				-	ELEVA'	1120-000	DOM: NO. NO.	ATUI	4		
LLING AG	Catorii Exploration	DRILLER	Jim/C	Bary		DATE S			Ja	nuan	/ 13	,1989
	CME - 75					COMPL DEPTH	ETIO	١ :	26.6	11	1	SAMPLER 2 California Modified Type
TING ME	6° Hollowstern Augers	DRILL BIT	CME Ca	ırbide		NO. OF	ES	DIST.	١	₩A.	٦	UNDIST. N/A
E AND TY	PE OF CASING 2" PVC					WATER	3	FIRST		3 1/2		COMPL. N/A 24 HRS. N/A
OF PER	REPORTATION 0.010" Slotted	FROM 1	0 10.	25	PŁ.	LOGG	ED 8	Y:			П	CHECKED BY:
E AND TY	PE OF PACK Lonestar #2/12 Monterey Sand		8 10	25	PL.	_	hi wik	Ram	ha			Alan Lattanner
PE OF SEAL	NO.1 Bentonite Pellets		6 TO	8	PL.	١ ٣	IUCK	папі	00			Man Laugnner
21/20/20	No. 2 Neat Cement	FROM	0 то	6	PL.							
			GRAP	HICLO	1	٠.	reter	-	AMP	ES	_	REMARKS (Orli flate, Fluid Loss, Odor
	DESCRIPTION		Lithology	Piez	omete aliation	Water	Piezome	Orfre	Sample	Recov.	Sounts	A Section of the sect
14	FILL - SANDY CLAY (CL)			1	K	-	7.					24
+	-moist FILL - SILTY CLAY (CL)		1			3		-	:		,	}
j	-with sand -light gray -with debris					3	١.	1	1		1	
4	-with Geons						5 -	1_				
-							١,	2	,		‡	4
-							١.	1	1		۲	1
. 1	-with roofing shingles						1	1	1	1		
IJ						ABO	P7	1				
7			1			É	10:	3	1		2	
14			1					_	+	1		-
-								4	1	1		İ
. †	FILL-LINOLEUM & TAR PAPER		+				1	4	1	1		V
5-	-with esphalt						15	-	1			
]							1	4	1	=	50	<u>=</u>
1								]	1	1	1	
-								4	1		1	
20 -	-with wood and liberglass shingles						20	- 5	1.	-		10
			1				1:	+	+	┦	-	10
	SILTY CLAY (CL)		-		目		1	1	ľ	1	1	1
	-dark gray -moist -very soft		1		目		1	1	1	1	ı	
25-	-with shells -"Bay Mud"		1				25	1		_		
-	Surferior.							- 6				Ħ
-	Pottom of bodgs of 271		-	- 20			$\dashv$	+	Ŧ	+	7	
1	Bottom of boring at 27'							+				*
BO -						1	30	J				
-							٢					
-								4				
1								-				
35				1			3	-				

ING LOC	EATION MW-5				E	LEVAT	NOI	UND D	ATUL	4			
LLING AG	BENCY Datum Exploration	DRILLER	Jim /	Gary	000	ATE S	TART	ED ED	Jan	nuar	y 16,	1989	
TIMG EC	CME - 75					OMPL EPTH	ETIO	4	25"		s	AMPLER N	2'California fodified Type
LLING M	ETHOD 8" Hollowstern Augers	DRILL BIT	CME Ca	rbide	N	O. OF	ES	DIST.	- 1	VA	-	INDIST.	N/A
E AND TY	PE OF CASING 2" PVC				T	VATER		FIRST		r to		XOMPL. N//	24 HRS. N/A
E OF PE	REFORATION 0.010" Slotted	FROM	<b>5</b> то	25 R.	-+-	LOGG	ED B	Y:				CHECKED 1	
EANDT	YPE OF PACK Lonestar #2/12 Monterey Sand	FROM	4 TO	25 m.	٦						- 1		
PE OF	No. 1 Bentonite Pellets	FROM	1 TO	4 R	٦	Ça	ırl Pa	ırten			- 1	Alan I.	attanner
SEAL	No. 2 Neat Cement	FROM	0 то	1 R.									
T			GRAPI	ec Log	_		ji i		LAMP		二		IARKS Field Lose, Oder,
Page 1	DESCRIPTION		Lithology	Piezome Installat	iter ion	Water	Plezome	Orfve	Sample	Recov.	Blow	e(c)	rion coss, ouor,
]	FILL-SILTY CLAY (CH)		2	4	E.						П		
4	-gray -damp -medium stiff					3		1			П		
4						3		1			П		
+-	FILL - CLAYEY SAND (SC)		1	777				1				1	
J	-gray -well sorted						5 -	1	:		+	OVA - Stight:	: 1000+ ppm Saur Odor
7	-demo -medium dense						8	$\vdash$	1-		7	OVA	Readings while
4	-moist		100			AMO		+	1			drilling	500 - 900 ppm
+						¥	1	1	1				
,–	FLL - CLAYEY SAND (SC)						10.	2	$\top$	T	5		covery eve with Standard
]	-gray -wet -loose						1	]-	+	-	-	P	en, Sampler
4	-with sandstone fragments to 1*		1		\$ 0		1	-	1		1		
4								+					
5-	FILL-CLAYEY SAND (SC) & SANDY CLAY	Y (CL)					15	3	1		4	OVA	= 20 to 30 ppm coarbon Odor
]	<ul> <li>the majority of the sample consists of tar paper and rooting scraps</li> </ul>						1	1	+:	+	A	٩ '''	<b>J</b>
-							1	4	1	1		1	
4								+				1	
20-							20	+			1	al ove	= 50 to 100 ppm recerbon Odor
1	SILTY CLAY (CH)		7		<b>3</b>			1	4	+	4	7 7	IDOREDOLI COLO
4	-gray to black -wet -soft						1	1		1			
4	-"Bay Mud"				■*			4					
25-	Dana - dhada - a Ari				1	W	-25	-	+	+	+	1	
]	Bottom of boring at 25'							]					
4	*							-					
								4					
30 -							34	9					
]				1				]					
								-					
								+		1			
35							3	5_					

PROJECT HAME: Lathrop Property

NO. 8810235A

Hodward-Ciyde Consultants 💳

## APPENDIX B

Letter from RWQCB dated December 30, 1996



n Francisco Bay gional Water Quality Control **Poard** 

701 Webster Street Suite 500 kland, CA 94612 0) 286-1255 X (510) 286-1380 December 30, 1996 File No.: 2223.09 (SA) SMS Case File

Spieker Properties 4900 Hopyard Road, Suite 120 Pleasanton, California 94588

Attention: Mr. John Winther

Properties at 5801, 5855-5895 Christie Avenue, 5813-5815 Shellmound Street, RE: and the Watergate Towers Complex property, Emeryville, Alameda County.

Dear Mr. Winther:

This letter contains San Francisco Bay Regional Water Quality Control Board (RWQCB) Staff's views on the environmental conditions at the above subject properties. We understand Spieker properties is considering acquisition of the properties. RWQCB Staff discussed the properties with representatives of Speiker Properties and Lathrop Properties at two meetings held on November 6, 1996, and December 3, 1996. Based on the meetings and review of information presented to us, we have the following views regarding the environmental conditions at the properties.

### Properties at 5801, 5855-5895 Christie Avenue (Christie Avenue properties) and 5813-5815 Shellmound Street

- 1. The properties, located east of Interstate I-80, are within the area of the Emeryville Brownfield's Initiative. Historically the properties were owned by Fiberboard Corporation and it's predecessors. Environmental conditions beneath the Christie Avenue properties have not been documented. Based on historical information, it appears that the Christie Avenue properties were filled with industrial debris and soil similar to that placed west of Interstate I-80.
- 2. The Christie Avenue properties have not been under the RWQCB's regulatory oversight and are not listed in the RWQCB's site management system database. However, based on the RWQCB Staff's experiences with other sites in this area, we believe that the risk to human health and the environment is most likely acceptable because the sites are paved and any subsurface hazardous constituents that may be present are essentially in deep soil layers. If subsurface work (e.g.



Our mission is to preserve and enhance the quality of California's water resources, and ensure their proper allocation and efficient use for the benefit of present and future generations. foundations, utilities etc.) is necessary, a risk management plan that includes plans for the possibility of handling potential hazardous materials is advisable.

- 3. With regard to groundwater beneath the properties, we do not consider the uppermost groundwater zone a suitable drinking water source. The Brownfield Initiative is a mechanism for the City of Emeryville (COE) and regulatory agencies to acknowledge the regional nature of hazardous constituents in soil and groundwater and deal with them on a regional basis which may include containment, selected risk-based cleanup, and monitoring. The COE plans to enter into a memorandum of understanding with the RWQCB, Department of Toxic Substances Control (DTSC), Environmental Protection Agency (EPA), and potentially other regulatory agencies using a regional monitoring program and risk management practices. Soil issues would remain the responsibility of the property owner or responsible party and groundwater issues would be handled by the city. In the absence of specific pollution sources, the RWQCB would not view groundwater remediation on a site by site basis, as reasonable, except where significant individual pollution sources are present.
- 4. The 5813-15 Shellmound Street Property is listed as a petroleum release site under the jurisdiction of the Alameda County Department of Environmental Health (ACDEH). Both the RWQCB and the ACDEH are using risk-based approaches to assess the need for remediation at the property.

### The Watergate Towers Complex property (located on the west side of Interstate I-80)

- 1. There are three potential issues with respect to the historical industrial landfilling at the property. These issues include: (a) Health and Safety (b) Use of groundwater for drinking and (c) effects of the landfill materials on the San Francisco Bay.
  - a. Health and Safety. Health and safety was addressed in previous reports prepared by Woodward Clyde Consultants and future potential concerns can be adequately addressed with an operations and maintenance plan that includes requirements for subsurface excavation work that might uncover potentially hazardous materials. We believe that there is no unacceptable threat to human health, for the current office/commercial use of the property, as the site is covered with pavement, building floors and asphalt parking lots.
    - b. Beneficial Uses of Groundwater. The shallow groundwater at the site is not a current source of drinking water and the probability of its use for domestic purposes is extremely low. In addition, deeper water-bearing zones are not likely to be impacted by vertical migration of hazardous constituents because of the presence of low permeability bay mud underlying the fill materials.
    - c. Impacts of Historic Fill Areas on the Bay. The issue of impacts of the fill areas on the San Francisco Bay is uncertain as the RWQCB has not developed or implemented guidelines to measure and assess the potential impacts of historic fill areas to San Francisco Bay. However, given the

current state of knowledge, it is unlikely that the site will come under the oversight of the RWQCB in the future. If and when the RWQCB develops a method to assess potential impacts of historical fill to San Francisco Bay, some additional assessment of potential releases of hazardous constituents from the site to the Bay may be required. It is unlikely that containment systems would be required.

- 2. The RWQCB staff consider the site to be an area of "random fill" and therefore not subject to reporting requirements under the California Code of Regulations, Title 23, Chapter 15. The site is currently not subject to RWQCB environmental regulatory oversight and that status is not likely to change in the future. The concern with the hazardous constituents in the fill relates primarily to metals contained in the fill and their potential mobility into the Bay. Further assessment of soluble constituents and the potential for their migration from the site to the Bay may be required if and/or when the RWQCB develops methods to assess similar sites around the Bay. The RWQCB recognizes the difficulty in differentiating between the potential contributions of hazardous constituents to the Bay from historical and current sources.
- 3. Since the site is located adjacent to the San Francisco Bay, any regulatory actions at the site should be based on protection of water quality, environment, and human health. Thus, the RWQCB is the appropriate agency for handling regulatory activities associated with the site.

We hope that this letter clarifies the RWQCB Staff's views on the properties. If you have any questions, please call Sumadhu Arigala at (510)-286-0434.

Sincerely, Loretta K Barsamian, Executive Officer

Stephen L. Moese Stephen I. Morse, Ly Dam Chief, Toxics Division.

cc: Curtis Scott, Landfills Section, RWQCB

Barbara Cook, DTSC 700 Heinz Avenue, Suite 200 Berkeley, CA 94710-2737

Charles Almestad, Golder Associates 1451 Harbor Bay Parkway, Suite 1000 Alameda, CA 94502

Bruce Klafter, Orrick Herrington & Sutcliffe Old Federal Reserve Bank Building 400 Sansome Street, San Francisco, CA 94111-3143

## **APPENDIX C**

Laboratory Reports of Asbestos Analysis of Soil Samples and Landfill Profiling Soil Samples Collected in April 1998

# RJ Lee Group, Inc.

530 McConmick Street San Leandro, CA 94577 (510) 567-0480 • FAX (510) 567-0488

April 7, 1998

Mr. Rajesv Cherwoo Golder Associates Inc. 1RO Grand Ave., Ste. 250 Oakland, CA 94612

RE:

PLM Standard Asbestos Analysis Respits for Samples as Shown on Test Report

RJLeeGroup, Inc. Joh No.: AOC804041 Client P.O. Job Number: P98-7034

Client Job Name/Location: Spieker Emeryville

Dear Mr. Cherwoo:

Enclosed are the results from the polarized light microscopy (PLM) asbestos analysis of the above referenced sample(s). Sample(s) were analyzed in accordance with guidelines set forth in the EPA Method for the Determination of Asbestos in Bulk Building Materials. U.S. EPA/600/R-93/116 (7/93 Edition).

Test Report lists each sample identification number, gross sample description, sample location, type(s) and concentration of nonaspestos fibers, major exumponents and concentration and a layer breakdown if applicable. All concentrations are given in area percents (visual estimation).

RI Lee Group, Inc., is accredited by the National Voluntary Laboratory Accreditation Program (NVLAP) (NVLAP Participant Number 1208-2) for bulk asbestos fiber analysis (PLM), and by the California Department of Health Services, Environmental Laboratory Accreditation Program (CALELAP) for bulk asbestos analysis. Neither the NVLAP Accreditation of this laboratory nor this report may be used to claim product endorsement by NVLAP or any agency of the United States government.

These results are submitted pursuant to RI Lee Group's current terms and conditions of sale, including the company's standard warranty and limitation of liability provisions and no responsibility or liability is assumed for the manner in which the results are used or interpreted. Unless notified in writing to return the sample(s) covered by this report, in which the results are used or interpreted. Unless notified in writing to return the sample(s) covered by this report, RI Lee Group will store the sample(s) for a period of ninety (90) days before discarding. A shipping and handling fee will be assessed for the return of any sample(s).

If you have any questions on this report or if RJ Lee Group, Inc. can be of further assistance, please do not hesitate to call.

Sincocel

Stephon's. Yuu (

Goologist

SSY/sb Enclosure

Monroeville, PA • San Leandro, CA • Washington, D.C. • Houston, TX Chopta-Lee, Inc., Grand Island, NY

WITE 1200 PAR THE WE PER ARRATE SHAFE

APR- 7-98 TUE 3:40

LEE GROUP,

## Test Report - Golder Associates, Inc.

Potarized Light Analysis Results Project AOC804041

	a		^	sbesto	S		q#	Mineral	Nonast Fibrous	Synthetic	: Callet :	ACITAL LINES	al/All Date
npie Number / opie Appearance Client Sample Number 66471 CPI. SP-1 av soil	Chrystalle A	Amosite C 17 %	meidolite Ar	nthophyl	ike Tremolike NFM: Qiz,	Actinolite C	Cettulose 1 % , Clay,	Wool	Glass -	Fibers	Fibers	Material 82 % Homogen	4/6/98 PTM

Samples received our Thursday, April 2, 1998

RJ Lee Group, Inc. Bay Area Lab

530 McCormick Street San Leandro, CA 94577 Page: 1 of 1

Authorized Signature

Peter McIntyre, Goologist Monday, April 6, 1998

Phone Fax

(510) 567-0480 (510) 567-0488

5105670488

## RI Lee Group, Inc.

530 McCormick Street San Leandro, CA 94577 (510) 567-0480 • FAX (510) 567-0488

April 20, 1998

Mr. Rajeev Cherwoo Golder Associates Inc. 180 Grand Ave., Ste. 250 Oakland, CA 94612



RE:

PLM Standard Asbestos Analysis Results for Samples as Shown on Test Report

RJLeeGroup, Inc. Job No.: AOC804186 Client P.O./Job Number: Spieker Emeryville Client Job Name/Location: Spieker Emeryville

Dear Mr Cherwoo:

, . . . . . . .

Enclosed are the results from the polarized light microscopy (PLM) asbestos analysis of the above referenced sample(s). Sample(s) were analyzed in accordance with guidelines set forth in the EPA Method for the Determination of Asbestos in Bulk Building Materials, U.S. EPA/600/R-93/116 (7/93 Edition).

Test Report lists each sample identification number, gross sample description, sample location, type(s) and concentration of nonasbestos fibers, major components and concentration of nonfibrous material (NFM), sample run date, analyst, sample homogeneity, and a layer breakdown if applicable. All concentrations are given in area percents (visual estimation).

RJ Lee Group, Inc. is accredited by the National Voluntary Laboratory Accreditation Program (NVLAP) (NVLAP Participant Number 1208-2) for bulk asbestos fiber analysis (PLM), and by the California Department of Health Services, Environmental Laboratory Accreditation Program (CALELAP) for bulk asbestos analysis. Neither the NVLAP Accreditation of this laboratory nor this report may be used to claim product endorsement by NVLAP or any agency of the United States government.

These results are submitted pursuant to RJ Lee Group's current terms and conditions of sale, including the company's standard warranty and limitation of liability provisions and no responsibility or liability is assumed for the manner in which the results are used or interpreted. Unless notified in writing to the sample of the sample of the sample of the sample of ninety (90) days before discarding. A shipping and handling fee will be assessed for the return of any sample (s).

If you have any questions on this report or if RJ Lee Group, Inc. can be of further assistance, please do not hesitate to call.

Sincerely

Stephen S. Yata

SSY/sb Enclosure

Monroeville, PA • San Leandro, CA • Washington, D.C. • Houston, TX
Chopra-Lee, Inc., Grand Island, NY

CONTRACTOR OF THE PROPERTY OF THE PROPERTY WITH

n de transportant de la companya de la co La companya de  companya del companya de la companya del la companya de la companya

## Test Report - Golder Associates, inc.

## Polarized Light Analysis Results Project AOC804186

					1103000		_				Managh	anton.			_
					Asbest	tos			3.61		-INOMASI Fibrana	Comthetic	Other	NonFibrou	s Run Date
0 1. 35 ton /									Min			Synthetic	Cibere	Material	Analyst
Sample Number /	Client Sample Number	Chrysotile	Amosi	te Croci	dolite Anthoph	yllite Tremolite	Actino	olite Cellulose	W	001	Glass	Fideis	Fiocis		4/17/98
	CHERT Sample Frances		<1 9	<u> </u>			-	<1 %	<1	%	-	-	-	<del>99+</del> %	\$\$Y
1667721CPL	SP-3-1	_	, ,			NFM: Qtz,	Carb,	Opaq, Misc. I	Part.					TT	
Brown soil														Homogen	eous
				_		_	_	<b %	<1	%	-	-	_	99+ %	4/17/98
1667722CPL	SP-3-2	-	<1 9	6 -	-	NEM: Or	Carb	Opaq, Misc. I							SSY
Brown soil						MIMI Que,		OP-1,						Homogen	eous
			,					<\ %	<b>~</b> 1	<b>%</b>	_	_	-	99+ %	4/17/98
1667723CPL	SP-3-3	-	<1 9	6 -	-		сh			70					SSY
Brown soil						NFM: Qtz.	Caro,	Opaq, Misc. I						Homogen	eous
			•							<b></b>				00± %	4/17/98
1667724CPL	SP-3-4	•	<1 9	<b>%</b> -	_	-	-	<1 %		%	-	-	-	<i>))</i> 1 <i>1</i> 0	SSY
Brown soil	01 - J					NFM: Qtz,	, Carb,	Opaq, Misc. I	ert.					Homogen	
			- 4 -			_	_	<1 %	<1	%	-	•	-	90 %	4/17/98
1667725CPL	SP-3-5	-	10 9	b -	-	NEM: Ota	Carb	Opaq, Misc. l							SSY
Brown soil						Mann de	, 0110,	-F-P						Homogen	eous
					•					or.			_	92 %	4/17 <i>1</i> 98
1667726CPL	SP-3-6	-	8 %	, -	. <del>-</del>	-	_ •	<1 %		<b>%</b> 0	•	-	-	, <u>, , , , , , , , , , , , , , , , , , </u>	SSY
Brown soil						NFM: Qtz,	, Carb,	Opaq, Misc. 1	Tart.					Homogen	
TINHH DOW															

Samples received on: Friday, April 17, 1998

RJ Lee Group, Inc. Bay Area Lab

530 McCormick Street San Leandro, CA 94577 Page: 1 of 4

Authorized Signature

Date

Stephen S. Yata Scologist Monday April 20, 1998

Phone

(510) 567-0480 (510) 567-0488 Fax

## Test Report - Golder Associates, Inc.

## Polarized Light Analysis Results Project AOC804186

				A.	haata	}					-Nonasb	estos			-
Sample Number /			4 540		-			•		neral 'ool	Fibrous Glass	Synthetic	Other 1	NonFibrou Material	is Run Date Analyst
Sample Appearance 1667727CPL Brown soil	Client Sample Number SP-3-7	Chrysotile 2	5 %	Crocidonie And	-	NFM: Qtz,	-	SI A	, ,,	<del>%</del>	-	-	•	95 % Homogen	4/17/98 SSY eous
1667728CPL Brown soil	SP-3-8		4%	-	-	NFM: Qtz,	- Carb,	<1 % Opaq, Miss		-	<1 %	-	-	96 % Homogen	4/17/98 SSY eous
1667729CPL Brown soil	SP-4-1	-	1%	-	-	NFM: Qtz,	- Carb,	<1 % Opaq, Misc		l <b>%</b>	-	<b>-</b>	-	99 % Homogen	4/17/98 SSY eous
1667730CPL Brown soil	SP-4-2	•	2%	•	-	NFM: Qtz,	- Carb,		6 <1 :. Part.	<b>%</b>	-	-	-	98 % Homogen	4/17/98 SSY eous
1667731CPL Brown soil	SP-4-3	-	<1 %	-	-	NFM: Qtz,	- , Carb,	<1 % Opaq, Gyp			-	-	-	99+ % Homogen	4/17/98 SSY leous
1667732CPL Brown soil	SP-4-4	-	2 %	-	-	NFM: Qtz,	- , Carb	<1 %, Opaq, Mise		l %		-	-	98 % Homogen	4/17/98 SSY neous

Samples received on: Friday, April 17, 1998

RJ Lee Group, Inc. Bay Area Lab

530 McCormick Street San Leandro, CA 94577 Page: 2 of 4

**Authorized Signature** Monday, April 20, 1998 Date

(510) 567-0480 (510) 567-0488 Phone Fax

## Test Report - Golder Associates, Inc.

# Polarized Light Analysis Results Project AOC804186

					A about	00				-Nonast	estos			-
Sample Number /	Client Sample Number	Chanatila		 ta Concidalit					Mineral	Fibrous	Symmetre	Cuici .	Material	Analyst
Sample Appearance 1667733CPL Brown soil	SP-5-1	-	<1 9	<u>ге стостолг</u>	<u>.</u>	_		<1 % Opaq, Mica,		. <u>-</u>	-	-	99+ % Homogen	4/17/98 PJM eous
1667734CPL Brown soil	SP-5-2	<1 %	-	-	•	- NFM: Qt	z, Carb,	<1 % Opaq, Naica,	- Misc. Part	<b>-</b>		-	99+ % Homogen	4/17/98 PJM eous
1667735CPL Brown soil	SP-5-3	<1 %	1 %	-	-	NFM: Qt	- z, Carb,	< % , Opaq, Mica,	_ Misc. Part	-	-	-	99 % Homogen	4/17/98 PJM eous
1667736CPL Brown soil	SP-5-4	-	-	<u>.</u>	-	NFM: Qt	z, Opaq	5 % . <sub>l</sub> , Mica, Fine G	raiņs, Mis	c. Part.	•	-	95 % Homogen	4/17/98 РЈМ eous
1667737CPL Brown soil	SP-5-5	-	4 %	· •	-	NFM: Q	- z, Opac	1 % <sub>I</sub> , Mica, Fine G	- Frains, Mis	sc. Part.	-	-	95 % Homogen	4/17/98 PJM eous
1667738CPL Brown soil	SP-5-6	-	2 %	, -	-	NFM: Q	z, Opac	<1 % <sub>1</sub> , Mica, Fine G	- Irains, Mi	- sc. Part	-	-	98 % Homogen	4/17/98 PJM eous

Samples received on: Friday, April 17, 1998

RJ Lee Group, Inc. Bay Area Lab 530 McCormick Street San Leandro, CA 94577 Page: 3 of 4 Authorized Signature Stephen S. Yata, Geologist

Date Monday, April 20, 1998

Phone (510) 567-0480 Fax (510) 567-0488

## Test Report - Golder Associates, Inc.

## Polarized Light Analysis Results Project AOC804186

										-Nonasi	oestos			-
					-Asbestos				Mineral	Fibrous	Synthetic	c Other 1	NonFibrou	s Run Date
Sample Number /				A 15.55-	A mah ambarili	ita Tremolite	Actino	lite Cellulose		Glass	Fibers	Fibers	Material	Analyst
Sample Appearance	Client Sample Number	Chrysotile.	Amurit	e Crocidolite	Апшорцуп	ile l'iemonie	<u> </u>	<1 %		_		-	96 %	4/17/98
1667739CPL	SP-5-7	-	4 %	-										РЈМ
Brown soil	<b>2</b> ·	•				NFM: Qtz,	Carb,	Opaq, Mica,	[4][5C. I M.				Homogen	eous
1667740CPL Brown soil	SP-5-8	<1 %	1%	-	-	NFM: Qtz,	- Carb,	< % Opaq, ica,	- Misc. Part.	-	-	•	99 % Homogen	4/17/98 PJM eous

Samples received on: Friday, April 17, 1998

RJ Lee Group, Inc. Bay Area Lab

530 McCormick Street San Leandro, CA 94577 Page: 4 of 4

Authorized Signature

Stephen S. Yata, Geologist Monday, April 20, 1998

Date

(510) 567-0480 (510) 567-0488

Phone Fax

				_	-1) // 0/	TOO CHAIR		<del></del>		7	7	: /	7/	/		/_ /	1
PRŌJ. I			OCATION KER E		YNLL &		NO.	PRESERVAT	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			//	//		/	/ <del>ફ</del> }/	
AMPLER							OF	S. K.	[]	/ /			/./	<b>\$</b> 0'	\\cdot\{\cdot\}	REMARKS	(with initials)
	Ta	1-ew	(hen		•	•	CON-	8	7			//		SEAL MO	N. S.		
TA. NO.		TIME	שב	MEDIA		IDENTIFICATION	TAINERS	(V)						. /	3/		11 1 1
	01/16	PM	Grab		5P-3.	- 1	1 bug	X						_	Re	rults by	04/24/98
	1	1	1		59-3-		10	*		<u> </u>							<del></del>
					5P-3-			工			<u>L</u>		-	_ -	-		
··					59-3-	4		X		—	-		<u> </u>				,
	$\sqcap$				sp-3-		1	X		+			<del></del>			<u> </u>	<del></del>
					59-3-		!	시		╂	<b> </b> -	-			+-	. <u></u>	<u></u> _
•					58-3-		11	사	_		-						
						-8		싀		+	-		*		<del>                                     </del>		
			<u> </u>		GP-4-		<del>                                     </del>	X		-	<del> </del>				+		
		<del>                                     </del>	-		59-4-		1.	X		-	╫	$\vdash$				Λ.	
		<del>                                     </del>	<del>                                     </del>		5P-4.		<del>-                                    </del>	X		+-	╁─	$\vdash$	·	-	1 .		
					58-4-		<del>                                     </del>	文		┤─	┼─				1		
. 198	-	<del></del>			59-5-			V		-	1-						
	<del>                                     </del>	╀┼	<del>                                     </del>	<del>} -}-</del>	5P-5		+;	人		1	┼						
eta audal	V	Signature	<u>  Y</u>	<u>  W</u>	ate / Time	Received by (Signalu	re/Firm)	Relin	guished	by: (5	gnatu	ro/Fica	1	Date /	Time	Received by:	(Signature/Firm)
) Inders	ileu Dy-	•	/1	04/1	198 4 4 PM	Received by Signalu	RSLEE							ĵ.			<u> </u>
ھلـ	Jun				ote/Time	Received by: (Signatu			quished	by : (5)	gnolu	re/Firm	,	Date	/ Time	Received by	(Signature/Firm)
elinquis	Helt DA;	Signatur	e/rirm/								•						
elinquis	hed by:	(Signatur	o/Firm)	(	Date/Time	Received by: (Signote	uro/Firm)		Dale/	Time		Remar	<u></u>	hment	if nece	ssary)	

						CHAIR	OF CUS	DY	NEC	ORD		44	Y 66	14/	#0	
PROJ.I	١٥.		OCATIO						M.L. M. 4. 5		7/	7	77			
	20.401				4416		NO.	40,	ž./			[ ]	/ /. ,	/ ,	s /;	\$/
AMPLER	(S t <i>(3)g</i> n	\	يديو	بل ي	· · · ·		OF CON-	PAFS	\ <del>5</del> -/	//	//			SEAL M	SEAL INTACT.	REMARKS (with initials)
TA. NO.	DATE	TIME	SAMPLE	MEDIA	SAMPLE	IDE STIFICATION	TAINERS	10	<u>}/</u>	//				• /		
	04/16	PM		Sil	58-5-	Ч	Ibagy	+				<u> </u>			Ri	mlb by 04/20/98
.,	1	1			58-5-			1		_ _			\$			<u> </u>
·					58-5-			1		_	丄					
					51-5-	7		*						-	<del></del>	
		1		V	50-5-	~ <i>&amp;</i>		1		<u> </u>			<u> </u>			<u>. ,</u>
	<del>y</del>								_		-   -	<u> </u>	3			
										+	- -}	-				· · · · · · · · · · · · · · · · · · ·
							<u> </u>		_		No.	<del> </del>	*			
		<u> </u>			<u> </u>		<u> </u>				-   -   -   -   -   -   -   -   -   -	╬			+	
				ļ	ļ	., ., ., ., ., ., ., ., ., ., ., ., ., .					- \$	-				
	<u>'</u>			<u> </u>							1					
		<u> </u>	<del> </del>	<b> </b>	<u> </u>	•	<del></del>					+				
<del></del> _		ļ	<del> </del>	<b> </b>	<u> </u>		<del> </del>		$\dashv$	_		+-	<u> </u>			· · · · · · · · · · · · · · · · · · ·
		<del>- </del> -	<u> </u>	<del> </del>	- 		<del> </del>			_						
Relipquist	hed by:	Signoture	/Firm)	04/66	ate/Time	Received by (Signatur	18/100)	Reli	nguish	ed by:	(Signa)	ture/fir	m)	Date	/Time	Received by: (Signature / Firm
Retinquisi				D	ate/Time	Received by: (Signatur		Reli	nquish	ed by:	(Signol	ura/Fic	7	Date	/ Time	Received by (Signature/Firm
Relinquis	hed by:	(Signatur	/Ficm)	C	Date/Time	Recaived by: (Signalu	ra/Ficm)		Date	/ Time		Remo	rks (alta	chment	s if nece	ssary)



# Curtis & Tompkins, Ltd., Analytical Laboratories, Since 1878

2323 Fifth Street, Berkeley, CA 94710, Phone (510) 486-0900

## ANALYTICAL REPORT

Prepared for:

Golder Associates 180 Grand Ave Suite 250 Oakland, CA 94612

Date: 04-MAY-98

Lab Job Number: 133232 Project ID: N/A

Location: Spieker Emeryville

Reviewed by: Damara Moore

Reviewed by:

This package may be reproduced only in its entirety.



#### Volatile Organics by GC/MS

Client: Golder Associates Analysis Method: EPA 8260 Location: Spieker Emeryville Prep Method: EPA 5030

 Field ID:
 SP-1-5
 Sampled:
 04/16/98

 Lab ID:
 133232-001
 Received:
 04/17/98

 Matrix:
 TCLP Leachate
 Extracted:
 04/21/98

 Batch#:
 40392
 Analyzed:
 04/21/98

Units: ug/L Diln Fac: 0.97

Analyte	Result	Reporting Limit
Vinyl Chloride	ND	9.7
1,1-Dichloroethene	ND	4.9
2-Butanone	ND	9.7
Chloroform	ND	4.9
Carbon Tetrachloride	ND	4.9
1,2-Dichloroethane	ND	4.9
Benzene	ND	4.9
Trichloroethene	ND	4.9
Tetrachloroethene	ND	4.9
Chlorobenzene	ND	4.9
1,4-Dichlorobenzene	ND	4.9
Surrogate	*Recovery	Recovery Limits
1,2-Dichloroethane-d4	103	85-121
Toluene-d8	101	92-110
Bromofluorobenzene	102	84-115

#### BATCH QC REPORT



EPA 8260 Volatile Organics

Client: Golder Associates Analysis Method: EPA 8260 Location: Spieker Emeryville Prep Method: EPA 5030

METHOD BLANK

 Matrix:
 Water
 Prep Date:
 04/21/98

 Batch#:
 40392
 Analysis Date:
 04/21/98

Units: ug/L Diln Fac: 1

MB Lab ID: QC68923

Analyte	Result	Reporting Limit
Vinyl Chloride	ND	10
1,1-Dichloroethene	ND	5.0
2-Butanone	ND	10
Chloroform	ND	5.0
Carbon Tetrachloride	ND	5.0
1,2-Dichloroethane	ND	5.0
Benzene	ND	5.0
Trichloroethene	ND	5.0
<b>Te</b> trachloroethene	ND	5.0
Chlorobenzene	ND	5.0
1,4-Dichlorobenzene	ND	5.0
Surrogate	%Rec	Recovery Limits
1,2-Dichloroethane-d4	100	85-121
Toluene-d8	100	92~110
Bromofluorobenzene	105	84-115

#### BATCH QC REPORT



EPA 8260 Volatile Organics

Client: Golder Associates Analysis Method: EPA 8260 Location: Spieker Emeryville Prep Method: EPA 5030

BLANK SPIKE/BLANK SPIKE DUPLICATE

 Matrix:
 Water
 Prep Date:
 04/21/98

 Batch#:
 40392
 Analysis Date:
 04/21/98

Units: ug/L Diln Fac: 1

BS Lab ID: QC68921

Analyte	Spike Added	BS	%Rec #	Limits
1,1-Dichloroethene	50	47.09	94	69-137
Benzene	50	49.17	98	87-117
Trichloroethene	50	49.31	99	83-116
Chlorobenzene	50	50.48	101	87-117
Surrogate	%Rec	Limits		
1,2-Dichloroethane-d4	98	85-121		-
Toluene-d8	100	92-110		
Bromofluorobenzene	100	84-115		

#### BSD Lab ID: QC68922


Analyte	Spike Added	BSD	%Rec #	Limits	RPD #	Limit
1,1-Dichloroethene	. 50	45.9	92	69-137	3	14
Benzene	50	47.84	96	87-117	3	10
Trichloroethene	50	47.83	96	83-116	3	10
Chlorobenzene	50	48.72	97	87-117	4	10
Surrogate	%Rec	Limit	s		_	
1,2-Dichloroethane-d4	99	85-12	1			
Toluene-d8	101	92-11	.0			
Bromofluorobenzene	101	84-11	.5			

<sup>#</sup> Column to be used to flag recovery and RPD values with an asterisk

RPD: 0 out of 4 outside limits

Spike Recovery: 0 out of 8 outside limits

<sup>\*</sup> Values outside of QC limits



## TVH-Total Volatile Hydrocarbons

Client: Golder Associates Location: Spieker Emeryville Analysis Method: EPA 8015M Prep Method: EPA 5030

Sample # Client ID	Batch #	Sampled	Extracted	Analyzed	Moisture
133232-001 SP-1-5	40410	04/16/98	04/23/98	04/23/98	

Matrix: Soil

Analyte Diln Fac:	Units	133232-001 1	
Gasoline C7-C12	mg/Kg	<1	
Surrogate			
Trifluorotoluene	₹REC	104	
Bromofluorobenzene	%REC	114	

#### BATCH QC REPORT



TVH-Total Volatile Hydrocarbons

Golder Associates Client: Location: Spieker Emeryville Analysis Method: EPA 8015M EPA 5030

Prep Method:

METHOD BLANK

Soil Matrix:

Prep Date: 04/22/98

40410 Batch#: **Units:** mg/Kg

04/22/98 Analysis Date:

Diln Fac: 1

MB Lab ID: QC68982

Analyte	Result	· · · · · · · · · · · · · · · · · · ·
Gasoline C7-C12	<1.0	
Surrogate	%Rec	Recovery Limits
Trifluorotoluene	100	53-157
Bromofluorobenzene	109	53-157

#### BATCH QC REPORT



TVH-Total Volatile Hydrocarbons

Client: Golder Associates Analysis Method: EPA 8015M Location: Spieker Emeryville Prep Method: EPA 5030

LABORATORY CONTROL SAMPLE

Matrix: Soil Prep Date: 04/22/98 Batch#: 40410 Analysis Date: 04/22/98

Units: mg/Kg Diln Fac: 1

LCS Lab ID: QC68981

Analyte	Result	Spike Added	%Rec #	Limits
Gasoline C7-C12	10.59	10	106	78-120
Surrogate	%Rec	Limits		
Trifluorotoluene Bromofluorobenzene	115 138	53-157 53-157		

<sup>#</sup> Column to be used to flag recovery and RPD values with an asterisk

<sup>\*</sup> Values outside of QC limits

Spike Recovery: 0 out of 1 outside limits

#### BATCH QC REPORT



TVH-Total Volatile Hydrocarbons

Client: Golder Associates Analysis Method: EPA 8015M Location: Spieker Emeryville Prep Method: EPA 5030

MATRIX SPIKE/MATRIX SPIKE DUPLICATE

 Field ID:
 ZZZZZZ
 Sample Date:
 04/09/98

 Lab ID:
 133124-005
 Received Date:
 04/09/98

 Matrix:
 Soil
 Prep Date:
 04/23/98

Batch#: 40410 Analysis Date: 04/23/98 Units: mg/Kg dry weight Moisture: 12%

Diln Fac: 1

MS Lab ID: QC68983

Analyte	Spike Added	Sample	MS	%Rec #	Limits
Gasoline C7-C12	11.36	<1.136	11.42	101	38-132
Surrogate	%Rec	Limits			-
Trifluorotoluene	118	53-157			
Bromofluorobenzene	142	53-157			

#### MSD Lab ID: QC68984

Analyte	Spike Added	MSD	*Rec #	Limits	RPD #	Limit
Gasoline C7-C12	11.36	11.33	100	38-132	1	26
Surrogate	%Rec	Limit	s		<u>-</u>	
Trifluorotoluene	120	53-15	57			
Bromofluorobenzene	143	53-19	57			

# Column to be used to flag recovery and RPD values with an asterisk

\* Values outside of QC limits

RPD: 0 out of 1 outside limits

Spike Recovery: 0 out of 2 outside limits



04/23/98

#### Semivolatile Organics by GC/MS

Analyzed:

Client: Golder Associates Analysis Method: EPA 8270B Location: Spieker Emeryville Prep Method: EPA 3520

 Field ID:
 SP-1-5
 Sampled:
 04/16/98

 Lab ID:
 133232-001
 Received:
 04/17/98

 Matrix:
 TCLP Leachate
 Extracted:
 04/20/98

Batch#: 40389 Units: ug/L Diln Fac: 1

Analyte	Result	Reporting Limit
Pyridine	ND	100
2-Methylphenol	ND	100
3,4-Methylphenol	<b>N</b> D	100
2,4,6-Trichlorophenol	ND	100
2,4,5-Trichlorophenol	ND	100
Pentachlorophenol	ИD	100
1,4-Dichlorobenzene	<b>N</b> D	100
Hexachloroethane	ND	100
Nitrobenzene	ND	100
Hexachlorobutadiene	ND	100
2,4-Dinitrotoluene	ND	100
Hexachlorobenzene	ND	100

Surrogate	*Recovery	Recovery Limits
2-Fluorophenol	20	17-107
Phenol-d5	28	18-115
2,4,6-Tribromophenol	40	14-121
Nitrobenzene-d5	80	36-115
2-Fluorobiphenyl	80	36-113
Terphenyl-d14	79	17-115
i		

#### BATCH QC REPORT



EPA 8270 Semi-Volatile Organics

Client: Golder Associates Analysis Method: EPA 8270B Location: Spieker Emeryville Prep Method: EPA 3520

METHOD BLANK

 Matrix:
 Water
 Prep Date:
 04/20/98

 Batch#:
 40389
 Analysis Date:
 04/22/98

Units: ug/L Diln Fac: 1

MB Lab ID: QC68910

Analyte	Result	Reporting Limit
Pyridine	ND	100
2-Methylphenol	ND	100
3,4-Methylphenol	ND	100
2,4,6-Trichlorophenol	. ND	100
2,4,5-Trichlorophenol	ND	100
Pentachlorophenol	ND	100
1,4-Dichlorobenzene	ND	100
Hexachloroethane	ND	100
Nitrobenzene	ND	100
Hexachlorobutadiene	ND	100
2,4-Dinitrotoluene	ND	100
Hexachlorobenzene	ND	100
Surrogate	%Rec	Recovery Limits
2-Fluorophenol	76	17-107
Phenol-d5	76	18-115
2,4,6-Tribromophenol	70	14-121
Nitrobenzene-d5	85	36-115
2-Fluorobiphenyl	75	36-113
Terphenyl-d14	84	17-115

LR: Over linear range

GC/MS BS/BSD Spike Recovery Report for QC6 9 1 Debris 12 mpkins, Ltd.

spiked Compound	BS	*Rec	BSD	*Rec	תפש	im Doe D	DD3
Pyridine -Methylphenol	. 269	67		68	2	Lm Rec R 10-110	50 Flags
4-Methylphenol	282	71	289	72	2		50
2,4,6-Trichlorophenol	581 304	73 76	586	ν <b>73</b>	1		50
,4,5-Trichlorophenol	285	71	309 284	77 71	2	· -	50
entachlorophenol 1,4-Dichlorobenzene	225	56	230	58	2		50 44
Hexachloroethane	254	63	261	65	3		21
itrobenzene	150 355	37	153	38	2		50 .
nexachlorobutadiene	144	89 36	356 142	89 <b>3</b> 5	0		50
2,4-Dinitrotoluene  exachlorobenzene	313	78	323	35 81	2 3		50 19
exaciiorobenzene	379	95	387	97	2	_	50
2-Fluorophenol	751	75					
henol-d5	752	75 75	766 747	77 75		17-107	
,4,6-Tribromophenol Nitrobenzene-d5	725	72	736	74		18-115 14-121	
2-Fluorobiphenyl	421	84	421	84		36-115	
erphenyl-d14	386 406	77	388	78		36-113	
	400	81	409	82		17-115	



#### TEH-Tot Ext Hydrocarbons

Client: Golder Associates Location: Spieker Emeryville Analysis Method: EPA 8015M Prep Method: CA LUFT Cleanup Method: 3630-some

Sample # Client ID	Batch #	Sampled	Extracted	Analyzed Moisture
133232-001 SP-1-5	40390	04/16/98	04/20/98	04/22/98

Matrix: Soil

Analyte Diln Fac:	Units	133232-001	
Diesel C12-C22	mg/Kg	66 YH	
Surrogate			
Hexacosane	*REC	87	

Y: Sample exhibits fuel pattern which does not resemble standard

H: Heavier hydrocarbons than indicated standard

#### BATCH QC REPORT



TEH-Tot Ext Hydrocarbons

Client: Golder Associates

Location: Spieker Emeryville

Analysis Method: EPA 8015M CA LUFT Prep Method:

Cleanup Method: EPA 3630-some

METHOD BLANK

Matrix: Soil Batch#: 40390

04/20/98 Prep Date: Analysis Date: 04/23/98

Units: mg/Kg Diln Fac: 1

MB Lab ID: QC68914

Analyte	Result	-
Diesel C12-C22	<1.0	
Surrogate	%Rec	Recovery Limits
Hexacosane	101	48-142

#### BATCH QC REPORT



TEH-Tot Ext Hydrocarbons

Client: Golder Associates Location: Spieker Emeryville Analysis Method: EPA 8015M Prep Method: CA LUFT

Cleanup Method: EPA 3630-some

LABORATORY CONTROL SAMPLE

Matrix: Soil Batch#: 40390 Units: mg/Kg Prep Date: 04/20/98
Analysis Date: 04/22/98

Diln Fac: 1

LCS Lab ID: QC68915

Analyte	Result	Spike Added	%Rec #	Limits
Diesel C12-C22	41.8	49.5	84	49-108
Surrogate	%Rec	Limits		
Hexacosane	91	48-142		

# Column to be used to flag recovery and RPD values with an asterisk

\* Values outside of QC limits

Spike Recovery: 0 out of 1 outside limits

#### BATCH QC REPORT



#### TEH-Tot Ext Hydrocarbons

Client: Golder Associates Location: Spieker Emeryville Analysis Method: EPA 8015M Prep Method: CA LUFT

Cleanup Method: EPA 3630-some

#### MATRIX SPIKE/MATRIX SPIKE DUPLICATE

Field ID: SP-1-5 Lab ID: 133232-001

Matrix: Soil
Batch#: 40390
Units: mg/Kg
Diln Fac: 2

Sample Date: 04/16/98
Received Date: 04/17/98
Prep Date: 04/20/98

Analysis Date: 04/22/98

MS Lab ID: QC68916

Analyte	Spike Added	Sample	MS	%Rec #	Limits
Diesel C12-C22	49.5	65.86	97.36	64	34-121
Surrogate	*Rec	Limits			
Hexacosane	84	48-142			

MSD Lab ID: QC68917

Analyte	Spike Added	MSD	%Rec #	Limits	RPD #	Limit
Diesel C12-C22	49.5	100.6	70	34-121	3 _	36
Surrogate	*Rec	Limi	ts.		<u>-</u>	
Hexacosane	81	48-1	42			

# Column to be used to flag recovery and RPD values with an asterisk

\* Values outside of QC limits RPD: 0 out of 1 outside limits

Spike Recovery: 0 out of 2 outside limits

Curtis & Tompkins, Ltd.

SAMPLE ID: SP-1-5 LAB ID: 133232-001

CLIENT: Golder Associates LOCATION: Spieker Emeryville

MATRIX: Soil

DATE SAMPLED: 04/16/98 DATE RECEIVED: 04/17/98 DATE REPORTED: 04/23/98

#### California TITLE 26 Metals

Compound	Result (mg/Kg)	Reporting Limit (mg/Kg)	IDF	QC Batch	Method	Analysis Date
Antimony Arsenic Barium Beryllium Cadmium Chromium (total) Cobalt Copper Lead Mercury Molybdenum Nickel Selenium Silver Thallium Vanadium Zinc	ND 4.0 130 0.39 0.35 45 12 32 66 ND	2.8 0.24 0.47 0.094 0.094 0.47 0.94 0.14 0.080 0.94 0.94 0.24 0.47 0.24 0.47	1 1 1 1 1 1 1 1 1 1 1	40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355	EPA 6010A	04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98
	<u> </u>	<u> </u>	<u></u>	<u> </u>		<del> </del>

ND = Not detected at or above reporting limit



CLIENT: Golder Associates

JOB NUMBER: 133232

## BATCH QC REPORT PREP BLANK

Compound	Result	Reporting Limit	Units	IDF	QC Batch	Method	Analysis Date
Antimony Arsenic Barium Beryllium Cadmium Chromium (total) Cobalt Copper Lead Mercury Molybdenum Nickel Selenium Silver Thallium Vanadium Zinc	ND N	3 0.25 0.5 0.1 0.1 0.5 0.15 0.15 0.1 1 0.25 0.5 0.5	mg/Kg	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355 40355	EPA 7471 EPA 6010A EPA 6010A EPA 6010A EPA 6010A EPA 6010A	04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98

ND = Not Detected at or above reporting limit

Curtis & Tompkins, Ltd.

DATE REPORTED: 04/23/98

CLIENT: Golder Associates

JOB NUMBER: 133232

# BATCH QC REPORT LABORATORY CONTROL SAMPLE

Compound	Spike Amt	Result	Units	% Rec.	QC Batch	Method	Analysis Date
Antimony Arsenic Barium Beryllium Cadmium Chromium (total) Cobalt Copper Lead Molybdenum Nickel Selenium Silver Thallium Vanadium Zinc	25 100 100 2.5 2.5 10 25 12.5 25 20 25 100 5 100 25 25	21.95 91 86.5 2.325 2.21 8.9 22.5 11.3 22.1 18.3 22.05 89.5 4.415 89.5 22.65 23.15	mg/Kg	88 91 87 93 88 89 90 88 90 88 90 91 93	40355 40355 40355 40355	EPA 6010A	04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98 04/22/98

Curtis & Tompkins, Ltd.
DATE REPORTED: 04/23/98

CLIENT: Golder Associates

JOB NUMBER: 133232

#### BATCH QC REPORT BLANK SPIKE / BLANK SPIKE DUPLICATE

Compound	Spike Amount	BS Result	BSD Result	Units	BS% Rec.	BSD% Rec.	Rec. Limits	RPD	RPD Limit	QC Batch	Method	Analysis Date
Mercury	2.500	2.636	2.584	mg/Kg	105	103	80-120	2	35	40397	EPA 7471	04/21/98

Lab#: 133232 Page 1 of 1



## Total Petroleum Hydrocarbons, BPA 418.1

Client: Golder Associates Analysis Method: EPA 418.1 Location: Spieker Emeryville Prep Method: EPA 418.1


Sample #	Client ID	Batch#	Sampled	Analyzed	Moisture
133232-001 QC68947	SP-1-5 Method Blank	40399 40399	16-APR-98	21-APR-98 21-APR-98	-

Analyte: Total Recoverable Hydrocarbons Matrix: Soil Units: mg/Kg

Sample #	Client ID	Result	Reporting Limit	Dilution Factor
133232-001	SP-1-5	650	25	1
QC68947	Method Blank	ND	25	

ND = None Detected at or above Reporting Limit

Lab#: 133232 Page 1 of 1



## Total Petroleum Hydrocarbons, EPA 418.1

Client: Golder Associates

Location : Spieker Emeryville

Analysis Method: EPA 418.1 Prep Method: EPA 418.1

Sample #	Client ID	Batch#	Sampled	Analyzed	Moisture
QC68948	Lab Control Sample	40399	-	21-APR-98	-

Units: mg/Kg Matrix: Soil Analyte: Total Recoverable Hydrocarbons

Sample #	Sample Type	Spike Amt.	Result	%Recovery	Limits
QC68948	Lab Control Sample	418.0	424.0	101	80-120

Lab#: 133232 Page 1 of 1



Curtis & Tompkins, Ltd.

## Total Petroleum Hydrocarbons, EPA 418.1

Client: Golder Associates

Location: Spieker Emeryville

Analysis Method: EPA 418.1

Prep Method: EPA 418.1

Sample #	Client ID	Batch#	Sampled	Analyzed	Moisture
QC68949	MS of 133232-001	40399	16-APR-98	21-APR-98	-
QC68950	MSD of 133232-001	40399	16-APR-98	21-APR-98	

Analyte: Total Recoverable Hydrocarbons Matrix: Soil Units: mg/Kg

Sample #	Client ID	Spikeamt	Result	%Rec	Limits	%RPD	Limit
QC68949 QC68950 133232-001	MS of 133232-001 MSD of 133232-001 SP-1-5	418.0 418.0	1117 1160 654.0	111 121	75-125 75-125	4	35

CHAIN OF CUSTODY RECORD SITE/LOCATION PROJ. NO. SPIEKER EMERYVILLE Signoture) NO. SAMPLERS: (Signature) REMARKS (with initials) OF CON-**TAINERS** MEDIA SAMPLE IDENTIFICATION TIME STA. NO. DATE 51-1-5 Received by: (Signature / Firm) Date / Time Relinquished by: (Signature / Firm) Received by: (Signature/Firm) Date / Time Relinquished by: (Signature/Firm) Date / Time Received by (Signature/Firm) Relinquished by: (Signoture/Firm) Received by: (Signature / Firm) Date/Time Relinguished by: (Signature / Firm) Remarks (ditachments it hecessary)

Golder Associater (510) 239-9000

fax (510) 239-9010

Results to Rojeev Cherwoo Date / Time Received by: (Signature/Firm) Date/Time Relinquished by: (Signature/Firm)

# ATTACHMENT B

Golder Report to RWQCB dated June 4, 1998

#### Golder Associates Inc.

180 Grand Avenue, Suite 250 Oakland, CA USA 94612 Telephone (510) 239-9000 Fax (510) 239-9010



June 4, 1998

Our Ref: 973-7187

Mr. Curtis Scott Regional Water Quality Control Board San Francisco Bay Region 2101 Webster Street, #500 Oakland, California 94612

Subject:

Asbestos Impacted Soils Watergate Office Complex

2200 Powell Street, Emeryville, California

Dear Mr. Scott

Golder Associates Inc. (Golder), submitted a letter to your attention on May 27, 1998 requesting your approval to move recently excavated asbestos impacted soils from one location at the site to an underground storage tank (UST) excavation at the site. Following submittal of that letter, we had a meeting and several telephone conversations with Mr. Alan Friedman of your office. Mr. Friedman agreed with our request in concept, however, indicated that we should seek the approval from Mr. Ravi Arulanantham at the Regional Water Quality Control Board (RWQCB).

On June 1, 1998, we contacted Mr. Arulanantham by telephone and discussed with him the details that we presented to you in our May 27, 1998 letter. Mr. Arulanantham stated that he is familiar with the environmental conditions of the site and the general area in which the site is located. A summary of relevant findings are listed below:

- 1. In the 1950s and 1960s, the site was developed by placing fill materials (construction debris, metal slugs, soils containing petroleum hydrocarbons, etc.) in diked areas within former San Francisco Bay tidelands. This fill material was historically placed at the site in order to expand the land surface west of the Highway 80 corridor. This fill material was capped by engineered fill prior to development.
- 2. The RWQCB has previously determined in a letter to Spieker Properties dated December 30, 1996, that the site does not pose an unacceptable threat to human health, and that the RWQCB is the appropriate agency for handling environmental regulatory activities for the site.
- 3. Asbestos encountered in soils at the site was not generated from manufacturing or hazardous waste operations (asbestos abatement) at the site.

Based on these findings and the fact that we are proposing to move the excavated soils from one location to another location at the site with similar random fill soils, and a clean soil cap will be placed over the translocated soils, Mr. Arulanantham concurred with recommendations made by Golder and

verbally approved the plan. Mr. Arulanantham directed us to prepare this letter as documentation of his decision and submit the letter to your office for your records.

Based on the approval from Mr. Ravi Arulanantham, we are proceeding with plans to move the recently excavated soils to the UST excavation at the site. We will notify the RWQCB and Bay Area Air Quality Management District (BAAQMD) prior to commencement of work. The work will be carried out under a plan in accordance with Occupational Safety and Health Agency (OSHA) regulations.

If you have any questions regarding this letter, please call us at (510) 239-9000.

Sincerely,

GOLDER ASSOCIATES INC.

Rajeev Cherwoo Project Engineer

Charles Almestad, R.G, C.Hg.

That hald

Associate

RC/CA/mcp

cc: Jeff White, Spieker Properties, Emeryville, California
Ravi Arulanantham, RWQCB, Oakland, California

Kevin Roberts, C.A.C., Golder Associates, Irvine, California