

ENVIRONMENTAL HEALTH SERVICE

November 18,2005

Ms. Donna Drogos

Supervisor for Toxic's Program
Alameda County Environmental Health Services Agency

Alameda CA

Subject:

Request to review

Limited Phase 11 Environmental Site Sampling Report

5105 East 8<sup>th</sup> Street

Oakland, CA

Dear Ms. Donovan;

My husband, Jeff Foreman, and I own a vacant lot at 5105 East 8<sup>th</sup> St. We had a phase 11 report done and lead was discovered in one of the bores that exceeds regulatory action levels. Our consultant, Donavan Tom of Basics Environmental recommended this report be forwarded to your agency.

I spoke with Barney and he directed me to request a review with you. Thank you for helping us. You can reach my husband at his work, 510-261-4626 or myself at home, 510-601-1237.

Sincerely,

Barbara Stewart

Carlain Stewart



ENVIRONMENTAL HEALTH SERVICES

# LIMITED PHASE II ENVIRONMENTAL SITE SAMPLING

5105 EAST 8TH STREET OAKLAND CALIFORNIA

FOR

MR. JEFF FOREMAN OAKLAND CALIFORNIA



SEPTEMBER 23, 2005 04-ENV578B



September 23, 2005 04-ENV578B

Mr. Jeff Foreman 5375 Bellgrave Place Oakland, California 94618

Subject:

Limited Phase II Environmental Site Sampling Report

5105 East 8th Street Oakland, California

Dear Mr. Foreman:

This report describes a Limited Phase II Environmental Site Sampling Report of the site located at 5105 East 8th Street in Oakland, California. The scope of work included a preliminary subsurface investigation within the subject site to evaluate potential environmental impacts from past hazardous materials handling operations conducted at the site.

On the basis of the information compiled from six shallow soil samples from six onsite test borings (SB-1 - SB-6), our findings indicate no significant levels of total petroleum hydrocarbons as gas, diesel, kerosene, and motor oil; volatile organic compounds; or heavy metals appear to be impacting the surface soil at depths of four feet below grade at the subject site. However, lead was discovered in one of the six borings at levels which exceed regulatory action levels. Therefore, we recommend this report be forwarded to the Alameda County Environmental Health Services Agency for review.

Should you have any questions regarding this report, please contact the undersigned.

Sincerely,

Basics Environmental, Inc.

Donavan G. Tom, M.B.A., R.E.A. II

Principal Consultant

# TABLE OF CONTENTS

### PROFESSIONAL CERTIFICATION

1.0	INTRODUCTION	. 1-1
1.1 1.2 1.3 1.4	Purpose of Investigation  Background  Scope of Work  Permits and Regulatory Compliance	. 1-1 1-1
2.0	SOIL SAMPLING	2-1
2.1	Field Activities	2-1
3.0	CHEMICAL ANALYSES AND RESULTS	3-1
3.1 3.2	Chemical Analyses Analytical Results	3-1 3-1
4.0	CONCLUSIONS AND RECOMMENDATIONS	. 4-1
4.1 4.2	ConclusionsRecommendations	4-1 4-2

# List of Drawings

Drawing 1: Site Location
Drawing 2: Test Boring Locations

### **Appendices**

APPENDIX A: Laboratory Analytical Results and Chain of Custody

### PROFESSIONAL CERTIFICATION

# REPORT LIMITED PHASE II ENVIRONMENTAL SITE SAMPLING 5105 EAST 8TH STREET OAKLAND, CALIFORNIA 04-ENV578B SEPTEMBER 23, 2005

This report has been prepared by the staff of Basics Environmental, Inc. (Basics) under the professional supervision of the Principal Consultant whose seal and signature appears hereon. The findings, interpretations of data, recommendations, specifications or professional opinions are presented within the limits prescribed by available information at the time the report was prepared, in accordance with generally accepted professional environmental practice and within the requirements by the Client. There is no other warranty, either expressed or implied.

The data and findings of this report are based on the data and information obtained from the agreed upon scope of work between Basics and the Client. Because contamination is not necessarily evenly distributed across the property's soils and ground water, it can easily remain undetected. Additional scope of services (at greater cost) may or may not disclose information which may significantly modify the findings of this report. We accept no liability on completeness or accuracy of the information presented and or provided to us, or any conclusions and decisions which may be made by the Client or others regarding the subject site.

This report was prepared solely for the benefit of Basic's Client. Basics consents to the release of this report to third parties involved in the evaluation of the property for which the report was prepared, including without limitation, lenders, title companies, public institutions, attorneys, and other consultants. However, any use of or reliance upon this report shall be solely at the risk of such party and without legal recourse against Basics, or its subcontractors, affiliates, or their respective employees, officers, or directors, regardless of whether the action in which recovery of damage is sought is based upon contract, tort (including the sole, concurrent or other negligence and strict liability of Basics), statute or otherwise. This report shall not be used or relied upon by a party that does not agree to be bound by the above statements.



Donavan G. Tom, M.B.A., R.E.A. II Principal Consultant

### 1.0 INTRODUCTION

### 1.1 Purpose of Assessment

Basics Environmental, Inc. (Basics) has performed this Limited Phase II Environmental Site Sampling (Phase II) for Mr. Jeff Foreman pursuant to our letter of engagement signed August 5, 2005. The "subject site" is at 5105 East 8th Street in Oakland, California (See Drawing 1).

### 1.2 Background

On the basis of the information compiled within a previous Environmental Transaction Screen + Local Regulatory Agency File Review conducted by Basics on July 27, 2004, our findings indicated:

(1) The subject site has a history of utilizing appreciable amounts of hazardous materials (waste oils, waste oil filters, waste antifreeze, waste batteries, used tires, etc.) as part of former R & G Dismantlers onsite auto wrecking and salvage operations from at least 1989 to 2000.

Inspections conducted by the local regulatory enforcing agencies indicated "hazardous materials were improperly stored, heavy oily residues were noted throughout the facility, and waste management practices were terrible. In addition, oil covered engine parts and lead acid batteries were noted throughout the site and large areas of soil contamination was present." Subsequently, R & G Dismantlers was required to cease operations in August 2000.

### 1.3 Scope of Work

To address the subsurface issues pertinent to the subject site, Basics recommended conducting a preliminary subsurface assessment within the subject site to evaluate potential impacts to the shallow surface. Areas of concern include the associated unpaved yard areas.

The scope of work performed for this Limited Phase II Environmental Site Sampling consisted of the following tasks:

- Under the direction of a California Registered Environmental Assessor II, six shallow exploratory borings were to be advanced at the subject site (SB-1 SB-6). The areas of concern included:
- Associated Yard. The associated yard has a history of being unpaved and utilized for miscellaneous storage of hazardous materials (waste oils, waste oil filters, waste antifreeze, waste batteries, used tires, etc.) as part of former R & G Dismantlers onsite auto wrecking and salvage operations from at least 1989 to 2000.

To evaluate possible impacts to the surface below, at least six exploratory borings should be collected and analyzed for hazardous materials related to onsite auto wrecking and salvage operations (petroleum hydrocarbons, heavy metals and volatile organic compounds).

Note: Due to the limited historical information of the onsite auto wrecking and salvage operations within the associated yard, borings were to be advanced within representative areas of the associated yard. In addition, analytical analysis was intended to screen for likely residual environmental impacts from onsite auto wrecking and salvage operations operations.

- Soil samples were to be collected within the native soil at depths of four and eight feet below ground surface. If deemed waranted from visual observations of the samples, additional soil samples may be collected from the exploratory borings;
- The samples were to be collected, labeled, placed in a cooler with chemical ice, and transported under Chain of Custody control to McCampbell Analytical Laboratory, a certified laboratory with the Department of Toxic Substances Control (DTSC) of the California Environmental Protection Agency, for analysis; and
- The samples were to be analyzed for Total Recoverable Petroluem Hydrocarbons as g/d/k/mo/ss (EPA Method 8015C); Volatile Organic Compounds (EPA Method 8260B); and CAM 17 Metals (EPA 6010C).

The work for this Limited Phase II Environmental Site Sampling was performed within the client approved scope of work and budget for the assessment. Note: This scope of work only screens the potential of inadvertent residual discharges of potential hazardous materials from likely hazardous materials handling operations to the shallow soil and not the presence of former underground storage tanks. Based on the visual inspection, no obvious evidence of underground storage tanks and/or its appurtenances have been noted for the subject site. In addition, due to the proximity of the subject site to an adjacent known leaky underground fuel tank site (the Western Stucco site (located at 5209-5115 East 8th Street, adjacent to the south and perceived cross gradient to the subject site), the potential impact to ground water is high from off site sources, therefore, this assessment is intended to only address onsite shallow surface soil impacts. If future plans include the major redevelopment of the subject site, a search for any unforseen underground storage tanks and/or additional subsurface environmental sampling may be warranted prior to excavation activities due to the industrial history of the subject site area.

### 1.4 Permits and Regulatory Compliance

Several regulatory agencies were contacted prior to the beginning of this work and the permits necessary to proceed were obtained. Permits and/or approvals were obtained from the following agencies:

- Alameda County Public Works Agency Water Resources Section (James Yoo)
  Permit #W2005-0849. Confirmation for a grouting inspection for September 7,
  2005 at 3PM was confirmed with Mr. Mike Chun at least 24 hours prior to the
  drilling; and
- Underground Services Alert (U.S.A.), U.S.A. Job# 333525

### 2.0 SOIL SAMPLING

### 2.1 Field Activities

### 2.1.1 Preliminary Subsurface Investigation

On September 7, 2005, six test borings were advanced by Vironex, Inc. (Vironex; San Leandro, California) under the direction of a California Registered Environmental Assessor II. The borings were specifically designed to sample the shallow subsurface. The targeted areas of concern are shown on Drawing 2 and include:

Associated Yard. The associated yard has a history of being unpaved and utilized for miscellaneous storage of hazardous materials (waste oils, waste oil filters, waste antifreeze, waste batteries, used tires, etc.) as part of former R & G Dismantlers onsite auto wrecking and salvage operations from at least 1989 to 2000.

To evaluate possible impacts to the surface below, six exploratory borings (SB-1 - SB-6) were collected and analyzed for hazardous materials related to onsite auto wrecking and salvage operations (petroleum hydrocarbons, heavy metals and volatile organic compounds).

These limited locations were intended to screen and provide subsurface chemistry data regarding the potential of inadvertent discharges of typical hazardous materials associated with past hazardous materials handling operations. No geologic interpretation was performed during this phase of assessment.

The sampling locations were marked at the site in white paint, however, due to the locations within private property, U.S.A. was only able to clear areas near the street prior to drilling activities. Vironex utilized Geoprobe® 5400 Direct Penetration Technology (DPT) drilling methods. DPT uses dry impact methods to drive boring tools into the subsurface.

A soil sample was collected in 2-inch diameter, four foot steel continuous core sampler. Polyethylene terephthalate glycol (PETG) soil liners were utilized within the inner sample barrel. PETG soil liners are transparent and inert to petroleum hydrocarbons, metals, solvents, pesticides and most hazardous materials (except high levels of phenols). After advancing both the drive-casing and sample barrel four feet, the sampler was retracted, and the sample removed. Selected samples then were sealed and labeled for analytical purposes; the remainder of the samples were scrutinized for field characterization. The drive-casing and sample barrel were advanced in this manner until the total depth of the borehole was reached.

A soil sample from SB-1 through SB-6, was retrieved from the discrete depths of approximately four and eight feet below ground surface (bgs.) within the native soil below within the target areas of concern. Test borings SB-1 through SB-6 were advanced to a total depth of eight feet bgs. No odor or discoloration was detected within the deeper soil borings at four feet bgs. Therefore, no additional soil samples were collected within the borings. No ground water was encountered within test borings SB-1 through SB-6.

The samples for analytical purposes were covered on each end with Teflon, capped, sealed with tape, labeled, and placed in an insulated chest containing ice.

An inspector from the Alameda County Public Works Agency - Water Resources Section (ACPWA) was scheduled to inspect the grouting procedures conducted by Vironex at 3 pm, however never showed for the appointment. After several attempts to contact the ACPWA with no reply, the boreholes were backfilled to the surface with a neat cement slurry under the protocols set forth by the ACPWA. The drill cuttings were collected and placed in a 5-gallon pail, which was labeled and set aside until further notice.

Once collected in the field, all samples were maintained under chain of custody until delivered to the laboratory. The soil samples were immediately delivered to McCampbell Analytical Laboratory, Inc. (McCampbell; Pacheco, California), a State-certified laboratory.

### 3.0 CHEMICAL ANALYSES AND RESULTS

### 3.1 Chemical Analyses

The samples taken from the test borings were analyzed for the following:

- Total Petroleum Hydrocarbons as Gasoline, Diesel, Kerosene, Motor Oil, Stoddard Solvent (TPH-g, TPH-d, TPH-k, TPH-mo, TPH-ss) (EPA 8015C);
- Volatile Organic Compounds (VOCs) (EPA Method 8260B); and
- CAM 17 Metals (Antimony (Sb), Arsenic (As), Barium (Ba), Berryllium (Be), Cadmium (Cd), Chromium (Cr), Cobalt (Co), Copper (Cu), Lead (Pb), Mercury (Hg), Molybdenum (Mo), Nickel (Ni), Selenium (Se), Silver (Ag), Thallium (Tl), Vanadium (V) and Zinc (Zn) (EPA 6020A).

### 3.2 Analytical Results

Results of chemical analyses on the samples collected on September 7, 2005 are presented in Tables 1 - 3. Certified laboratory reports are presented in Appendix B, including chain-of-custody record data.

Table 1. Soil Analytical Results - Petroleum Hydrocarbons

Sample <u>ID</u>	Depth <u>Feet</u>	TPH-g mg/kg	TPH-d mg/kg	TPH-k mg/kg	TPH-mo mg/kg	TPH-ss mg/kg
SB-1	4	ND	1.4	ND	ND	ND
SB-2	4	ND	ND	ND	ND	ND
SB-3	4	ND	ND	ND	ND	ND
SB-4	4	ND	ND	ND	ND	ND
SB-5	4	ND	ND	ND	ND	ND
SB-6	4	ND	ND	ND	ND	ND

ND means not detected above the reporting limit. NA means not analyzed.

Table 2. Soil Analytical Results - Volatile Organic Constituents

Sample	Depth	VOCs
<u>ID</u>	<u>Feet</u>	mg/kg
CD 1	<b>A</b>	ND
SB-1	4	ND
SB-2	4	ND
SB-3	4	ND
SB-4	4	ND
SB-5	4	ND
SB-6	4	ND

ND means not detected above the reporting limit. No detectable amounts of volatile organic compounds (VOCs) analyzed as part of EPA 8260B were discovered in the soil samples taken.

Table 3. Soil Analytical Results - Inorganic Constituents (TTLC Extraction)

Sample <u>ID</u>	Depth <u>Feet</u>	Sb mg/kg	As <u>mg/kg</u>	Ba mg/kg	Be mg/kg	Cd mg/kg	Cr mg/kg	Co mg/kg	Cu <u>mg/kg</u>	Pb <u>mg/k</u> g
SB-1	4	ND	2.9	160	ND	ND	51	7.9	16	4.0
SB-2	4	1.1	96	190	ND	0.90	47	10	16	15
SB-3	4	25	190	230	ND	6.5	49	9.7	32	1,400*
SB-4	4	ND	20	310	ND	ND	45	14	18	12
SB-5	4	2.2	22	190	ND	0.75	40	11	15	14
SB-6	4	4.6	27	190	ND	4.8	42	5.4	20	24
Sample	Depth	Hg	Mo	Ni	Se	Ag	Tl	V	Zn	
<u>ID</u>	<u>Feet</u>	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	mg/kg	
										·
SB-1	4	ND	ND	66	ND	ND	ND	40	25	
SB-2	4	0.62	1.7	58	ND	ND	ND	54	62	
SB-3	4	0.96	10	54	0.66	1.9	ND	40	410	
SB-4	4	0.052	ND	53	0.56	ND	ND	54	31	
SB-5	4	0.052	ND	40	ND	ND	ND	35	45	
SB-6	4	0.11	0.79	49	0.51	ND	ND	31	130	

<sup>\*</sup> Due to the TTLC level of lead detected within the soil sample collected at 4' within SB-3, the sample was analyzed for the STLC level of lead. The STLC level of lead detected within 4' with SB-3 was 26 mg/L.

### 4.0 CONCLUSIONS AND RECOMMENDATIONS

### 4.1 Conclusions

### 4.1.1 Soil

Based on the results of the soil testing reported herein, detectable amounts of total petroleum hydrocarbons as diesel were discovered within the soil samples collected at 4 feet bgs. within SB-1. No other detectable amounts of total petroleum hydrocarbons as gasoline, diesel, kerosene, or motor oil were discovered within the other soil samples collected. Analytical results indicate the level of total petroleum hydrocarbons as diesel in the soil are not considered significant and below regulatory action. The level of total petroleum hydrocarbons as diesel and motor oil are below the Risk Based Screening Levels set forth by the Regional Water Quality Control Board for industrial/commercial sites in which ground water is not a current or potential source of drinking water (400 mg/kg TPH gasolines; 500 mg/kg TPH middle distillates; and 1,000 mg/kg TPH residual fuels).

No detectable amounts of volatile organic compounds analyzed as part of EPA 8260B were discovered within the soil samples collected.

Detectable amounts of antimony, arsenic, barium, cadmium, chromium, cobalt, copper, lead, mercury, molybdenum, nickel, selenium, silver, vanadium and zinc were discovered within the soil samples collected at 4 feet bgs within SB-1 - SB-6.

Analytical results indicate the level of antimony, arsenic, barium, cadmium, chromium, cobalt, copper, mercury, molybdenum, nickel, selenium, silver, vanadium and zinc in the soil are below the Total Threshold Limit Concentration (TTLC) set forth by the California Administration Code, Title 22 (500 mg/kg for antimony, 500 mg/kg for arsenic, 10,000 mg/kg for barium, 75 mg/kg for beryllium, 100 mg/kg for cadmium, 2,500 mg/kg for chromium, 8,000 mg/kg for cobalt, 2,500 mg/kg for copper, 1,000 mg/kg for lead, 20 mg/kg for mercury, 3,500 mg/kg for molybdenum, 2,000 mg/kg for nickel, 100 mg/kg for selenium, 2,400 mg/kg for vanadium and 5,000 mg/kg for zinc).

However, analytical results indicate the level of lead detected at 4 feet bgs within SB-3 at 1,400 mg/kg, is above the Total Threshold Limit Concentration (TTLC) set forth by the California Administration Code, Title 22 (1,000 mg/kg for lead). Due to the TTLC level of lead detected within the soil sample collected at 4' within SB-3, the sample was analyzed for the STLC level of lead. Analytical results indicate the level of lead detected at 4 feet bgs within SB-3 at 26 mg/L, is above the Soluble Threshold Limit Concentration (STLC) set forth by the California Administration Code, Title 22 (5.0 mg/L for lead).


### 4.2 Recommendations

On the basis of the information compiled from six shallow soil samples from six onsite test borings (SB-1 - SB-6), our findings indicate no significant levels of total petroleum hydrocarbons as gas, diesel, kerosene, and motor oil; or volatile organic compounds appear to be impacting the surface soil at depths of four feet below grade at the subject site at this time. However, lead was discovered in one of the six borings (SB-3 at 4 feet bgs) at levels which exceed regulatory action levels. Therefore, we recommend this report be forwarded to the Alameda County Environmental Health Services Agency Local Oversight Program (510-567-6700) for review.

It should be noted that the quality of soil and ground water beneath the entire west Oakland area has been degraded over the last few decades, and in an urban setting, background levels of lead in soil may be considerably higher that what is considered normal. Lead can originate from many sources including paint, and until recently, automobile emissions. Actual "cleanup levels" or "acceptable levels" for lead in soil are set by the California Environmental Protection Agency, Department of Toxic Substance Control (Cal-EPA, DTSC), and are site specific depending on the intended use of the property, combined with other potential exposure pathways to humans.

It should be also noted that due to the documented history of the subject site associated with onsite auto wrecking and salvage operations and relative size of the subject site, impacts to the subsurface not discovered within this scope of work may still exist at the site eventhough no substantial impacts to the subsurface, except for lead, have been discovered. Although, the limited environmental site sampling conducted herein did not reveal any evidence of substantial impacts to the shallow subsurface soil, except for lead, contamination is not necessarily evenly distributed across the subsurface soil and ground water. Therefore, localized impacts to subsurface from

former auto wrecking and salvage yard sites such as this can easily remain undetected. In addition, due to the proximity of the subject site to an known adjacent leaky underground storage tank site, the potential impact to ground water is high from off site sources. Based on the de minium condition stated above, additional environmental subsurface sampling may be warranted in localized areas to be disturbed and/or excavated prior to redevelopment activities to further evaluate potential environmental impacts from past auto wrecking and salvage yard operations.



Site Location



Limited Phase II Environmental Site Sampling 5105 East 8th Street Oakland, California PROJECT NO. 04-ENV578B

ORAWING NO.

1



Limited Phase II Environmental Site Sampling 5105 East 8th Street Oakland, California PROJECT NO 04-ENV578B

DRAWING NO.

2

DATE 8/26/05

REVIEWED BY

DGT

PREPARED BY

# APPENDIX A



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560
Telephone: 925-798-1620 Fax: 925-798-1622
Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST. Oakland	Date Sampled: 09/07/05
116 Glorietta Blvd.		Date Received: 09/07/05
Orinda, CA 94563	Client Contact: Donavan Tom	Date Reported: 09/13/05
Official CA 94303	Client P.O.:	Date Completed: 09/13/05

WorkOrder: 0509151

September 13, 2005

### Dear Donavan:

### Enclosed are:

- 1). the results of 6 analyzed samples from your 5105 E.8th ST. Oakland project,
- 2). a QC report for the above samples
- 3), a copy of the chain of custody, and
- 4). a bill for analytical services.

All analyses were completed satisfactorily and all QC samples were found to be within our control limits. If you have any questions please contact me. McCampbell Analytical Laboratories strives for excellence in quality, service and cost. Thank you for your business and I look forward to working with you again.

Angela Rydelius, Lab Manager

truly



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST. Oakland	Date Sampled: 09/07/05
116 Glorietta Blvd.		Date Received: 09/07/05
Orinda, CA 94563	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Orinda, CA 94303	Client P.O.:	Date Analyzed: 09/08/05

xtraction method: SW	5030B		Analytical methods: SW8015C	m	Work O	rder: 0509151
Lab ID	Client ID	Matrix	TPH(g)	TPH(ss)	DF	% SS
0509151-001A	SB1 @ 4'	s	ND	ND	1	85
0509151-003A	SB2 @ 4'	S	ND	ND	ı	81
0509151-005A	SB3 @ 4'	S	ND	ND	1	87
0509151-007A	SB4 @ 4'	s	ND	ND	1	80
0509151-009A	SB5 @ 4'	S	ND	ND	1	91
0509151-011A	SB6 @ 4'	S	ND	ŇĎ	I	80
						1
						i i
						:
· · · · · · · · · · · · · · · · · · ·				<u> </u>		
· · · · · · · · · · · · · · · · · · ·			······································			1
:						!
<del></del>	, , ,			<u> </u>		
	· · · · · · · · · · · · · · · · · · ·					<del> </del>
						!
	mit for DF =1;	W	NA	NA	L	ıg/L
	ot detected at or eporting limit	S	1.0	1.0	m	g/Kg

- water and vapor samples and all TCLP & SPLP extracts are reported in μg/L, soil/sludge/solid samples in mg/kg, w	/ipe samples in μg/wipe,
product/oil/non-aqueous liquid samples in mg/L.	

<sup>#</sup> cluttered chromatogram; sample peak coelutes with surrogate peak.

<sup>+</sup>The following descriptions of the TPH chromatogram are cursory in nature and McCampbell Analytical is not responsible for their interpretation: a) unmodified or weakly modified gasoline is significant, b) heavier gasoline range compounds are significant(aged gasoline?); c) lighter gasoline range compounds (the most mobile fraction) are significant; d) gasoline range compounds having broad chromatographic peaks are significant; biologically altered gasoline?; e) TPH pattern that does not appear to be derived from gasoline (stoddard solvent / mineral spirit?); f) one to a few isolated non-target peaks present; g) strongly aged gasoline or diesel range compounds are significant; h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~1 vol. % sediment; j) reporting limit raised due to high MTBE content; k) TPH pattern that does not appear to be derived from gasoline (aviation gas). m) no recognizable pattern; n) TPH(g) range non-target isolated peaks subtracted out of the TPH(g) concentration at the alient's request



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST. Oakland	Date Sampled: 09/07/05
116 Glorietta Blvd.	1	Date Received: 09/07/05
Orinda, CA 94563	Client Contact: Donavan Tom	Date Extracted: 09/07/05
	Client P.O.:	Date Analyzed: 09/08/05-09/09/05

xtraction met	hod: SW3550C		Analytic	al methods: SW8015C		Work Order	: 050915
Lab ID	Client ID	Matrix	TPH(d)	TPH(k)	TPH(mo)	DF	% SS
001A	SB1 @ 4'	S	1.4,b	ND	ND	1	101
003A	SB2 @ 4'	S	ND	ND	ND	l	94
005A	SB3 @ 4'	s	ND	ND	ND	ı	94
007A	SB4 @ 4'	S	ND	ND	ND	1	93
009A	SB5 @ 4'	S	ND	ND	ND	1	93
011A	SB6 @ 4'	s	ND	ND	ND	ı	94
							:
1							1
:							
:							
				,			:
	Limit for DF =1;	w	NA	NA	NA	u	ıg/L
	not detected at or reporting limit	S	1.0	1.0	5.0	m	g/Kg

<sup>\*</sup> water samples are reported in μg/L, wipe samples in μg/wipe, soil/solid/sludge samples in mg/kg, product/oil/non-aqueous liquid samples in mg/L, and all DISTLC / STLC / SPLP / TCLP extracts are reported in µg/L.

<sup>+</sup>The following descriptions of the TPH chromatogram are cursory in nature and McCampbell Analytical is not responsible for their interpretation: a) unmodified or weakly modified diesel is significant; b) diesel range compounds are significant; no recognizable pattern; c) aged diesel? is significant); d) gasoline range compounds are significant; e) unknown medium boiling point pattern that does not appear to be derived from diesel; f) one to a few isolated peaks present; g) oil range compounds are significant; h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than -1 vol. % sediment; k) kerosene/kerosene range; l) bunker oil; m) fuel oil; n) stoddard solvent/mineral spirit.



<sup>#</sup> cluttered chromatogram resulting in coeluted surrogate and sample peaks, or; surrogate peak is on elevated baseline, or; surrogate has been diminished by dilution of original extract.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST.	Date Sampled: 09/07/05
	Oakland	Date Received: 09/07/05
116 Glorietta Blvd.	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Orinda, CA 94563	Client P.O.:	Date Analyzed: 09/10/05

### Volatile Organics by P&T and GC/MS (Basic Target List)\*

Extraction Method: SW5030B Analytical Method: SW8260B Work Order: 0509151

Lab ID	i			0509151-001A			
Client ID				SB1 @ 4'			
Matrix	!			Soil			
Compound	Concentration *	DF	Reporting Limit	Compound	Concentration *	DF	Reporting Limit
Acetone	ND	0.1	0.05	Acrolein (Propenal)	ND	1.0	0.05
Acrylonitrile	ND	1.0	0.02	tert-Amyl methyl ether (TAME)	ND	1.0	0.005
Benzene	ND	1.0	0.005	Bromobenzene	ND	1.0	0.005
Bromochloromethane	ND	1.0	0.005	Bromodichloromethane	ND	1.0	0.005
Bromoform	ND	1.0	0.005	Bromomethane	ND	1.0	0.005
2-Butanone (MEK)	ND	1.0	0.02	t-Butyl alcohol (TBA)	ND	1.0	0.05
n-Butyl benzene	ND	1.0	0.005	sec-Butyl benzene	ND	1.0 -	0.005
tert-Butyl benzene	ND	1.0	0.005	Carbon Disulfide	ND	1.0	0.005
Carbon Tetrachloride	ND	1.0	0.005	Chlorobenzene	ND	1.0	0.005
Chloroethane	ND ND	1.0	0.005	2-Chloroethyl Vinyl Ether	ND :	1.0	0.01
Chloroform	ND	1.0	0.005	Chloromethane	ND	1.0	0.005
2-Chlorotoluene	ND	1.0	0.005	4-Chlorotoluene	ND	0.1	0.005
Dibromochloromethane	ND	1.0	0.005	1,2-Dibromo-3-chloropropane	ND	1.0	0.005
1.2-Dibromoethane (EDB)	ND	1.0	0.005	Dibromomethane	ND	1.0	0.005
1.2-Dichlorobenzene	ND	1.0	0.005	1.3-Dichlorobenzene	ND	1.0	0.005
1,4-Dichlorobenzene	ND	1.0	0.005	Dichlorodifluoromethane	ND	1.0	0.005
1,1-Dichloroethane	ND	1.0	0.005	1,2-Dichloroethane (1,2-DCA)	ND	1.0	0.005
1,1-Dichloroethene	ND	1.0	0.005	cis-1,2-Dichloroethene	ND.	1.0	0.005
trans-1,2-Dichloroethene	ND	1.0	0.005	1,2-Dichloropropane	ND	0.1	0.005
1,3-Dichloropropane	ND	1.0	0.005	2,2-Dichloropropane	ND	1.0	0.005
1,1-Dichloropropene	ND	1.0	0.005	cis-1,3-Dichloropropene	ND	1.0	0.005
trans-1,3-Dichloropropene	ND	1.0	0.005	Diisopropyl ether (DIPE)	ND	1.0	0.005
Ethylbenzene	ND	1.0	0.005	Ethyl tert-butyl ether (ETBE)	ND	1.0	0.005
Freon 113	ND	1.0	0.1	Hexachlorobutadiene	ND	1.0	0.005
Hexachloroethane	ND	1.0	0.005	2-Hexanone	ND	1.0	0.005
Isopropylbenzene	ND	1.0	0.005	4-Isopropyi toluene	ND	1.0	0.005
Methyl-t-butyl ether (MTBE)	ND	1.0	0.005	Methylene chloride	ND	1.0	0.005
4-Methyl-2-pentanone (MIBK)	ND	1.0	: 0.005	Naphthalene	ND	1.0	0.005
Nitrobenzene	ND	1.0	0.1	n-Propyl benzene	ND	1.0	0.005
Styrene	. ND	1.0	0.005	1,1,1,2-Tetrachloroethane	ND	1.0	0.005
1,1,2,2-Tetrachloroethane	ND	1.0	0.005	Tetrachloroethene	ND	1.0	0.005
Toluene	ND	1.0	0.005	1,2,3-Trichlorobenzene	ND	1.0	0.005
1,2,4-Trichlorobenzene	ND	1.0	0.005	1,1,1-Trichloroethane	ND	1.0	0.005
1,1,2-Trichloroethane	ND	1.0	0.005	Trichloroethene	ND	1.0	0.005
Trichlorofluoromethane	ND	1.0	0.005	1,2,3-Trichloropropane	ND	1.0	0.005
1,2,4-Trimethylbenzene	. ND	1.0	0.005	1,3,5-Trimethylbenzene	ND	1.0	0.005
Vinyl Chloride	ND	1.0	0.005	Xylenes	: ND	1.0	0.005
		Su	rrogate R	ecoveries (%)			
%SS1:	36			%SS2:	10	1	
%SS3:	105	:					

Comments:

ND means not detected above the reporting limit; N/A means analyte not applicable to this analysis.

# surrogate diluted out of range or coelutes with another peak; &) low surrogate due to matrix interference.

h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~1 vol. % sediment; j) sample diluted due to high organic content/matrix interference; k) reporting limit near, but not identical to our standard reporting limit due to variable Encore sample weight; m) reporting limit raised due to insufficient sample amount; n) results are reported on a dry weight basis; p) see attached narrative.



<sup>\*</sup> water and vapor samples are reported in μg/L, soil/sludge solid samples in mg/kg, product/oil/non-aqueous liquid samples and all TCLP & SPLP extracts are reported in mg/L, wipe samples in μg/wipe.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560
Telephone: 925-798-1620 Fax: 925-798-1622
Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST.	Date Sampled: 09/07/05	
116 Glorietta Blvd.	Oakland	Date Received: 09/07/05	
	Client Contact: Donavan Tom	Date Extracted: 09/07/05	
Orinda, CA 94563	Client P.O.:	Date Analyzed: 09/13/05	

Volatile Organics by P&T and GC/MS (Basic Target List)\* Analytical Method: SW8260B Extraction Method: SW5030B Work Order: 0509151 Lab ID 0509151-003A Client ID SB2 @ 4' Matrix Soil Reporting Reporting Limit Compound Concentration \* DF Compound Concentration \* DF Acetone ND 1.0 0.05 Acrolein (Propenal) ND 1.0 0.05 ND Acrylonitrile 1.0 0.02tert-Amyl methyl ether (TAME) ND 1.0 0.005 ND 1.0 Benzene 0.005 Bromobenzene ND 1.0 0.005 Bromochloromethane ND 1.0 0.005 Bromodichloromethane ND 1.0 0.005 Bromoform ND 1.0 0.005 Bromomethane 0.005 ND 1.0 2-Butanone (MEK) ΝD 1.0 0.02 t-Butyl alcohol (TBA) ND 1.0 0.05 ND n-Butyl benzene 1.0 0.005 sec-Butyl benzene ND 1.0 0.005 tert-Butyl benzene ND 1.0 0.005 Carbon Disulfide ND 1.0 0.005 Carbon Tetrachloride ND 1.0 0.005 Chlorobenzene ND 1.0 0.005 Chloroethane ND 1.0 0.005 2-Chloroethyl Vinyl Ether ND 1.0 10.0 Chloroform ND 1.0 0.005 Chloromethane ND 1.0 0.005 2-Chlorotoluene ND 1.0 0.005 4-Chlorotoluene ND 1.0 0.005 Dibromochloromethane ND 1.0 0.005 1,2-Dibromo-3-chloropropane ND 1.0 0.005 1.2-Dibromoethane (EDB) ND 1.0 0.005 Dibromomethane ND 1.0 0.005 1,2-Dichlorobenzene ND 1.0 0.005 1,3-Dichlorobenzene ND 1.0 0.005 ND 1,4-Dichlorobenzene 1.0 0.005 Dichlorodifluoromethane 0.005 ND 1.0 1,1-Dichloroethane ND 1.0 0.005 1,2-Dichloroethane (1,2-DCA) ND 1.0 0.005 ND 1,1-Dichloroethene 1.0 0.005 cis-1,2-Dichloroethene ND 1.0 0.005 ND trans-1,2-Dichloroethene 1.0 0.005 1,2-Dichloropropane ND 1.0 0.005 1,3-Dichloropropane ND 1.0 0.005 2,2-Dichloropropane ND 1.0 0.005 1,1-Dichloropropene ND 1.0 0.005 cis-1,3-Dichloropropene ND 1.0 0.005 trans-1,3-Dichloropropene ND 1.0 0.005 Diisopropyl ether (DIPE) ND 1.0 0.005 Ethylbenzene ND 1.0 0.005 Ethyl tert-butyl ether (ETBE) ND 1.0 0.005 Freon 113 ND 1.0 1.0 Hexachlorobutadiene ND 1.0 0.005 ND Hexachloroethane 1.0 0.005 2-Hexanone ND 1.0 0.005 ND Isopropylbenzene 1.0 0.0054-Isopropyl toluene ND 1.0 0.005 Methyl-t-butyl ether (MTBE) ND 1.0 0.005 Methylene chloride ND 1.0 0.005 4-Methyl-2-pentanone (MIBK) ND 1.0 0.005 Naphthalene ND 1.0 0.005 Nitrobenzene ND 1.0 0.1 n-Propyl benzene ND 1.0 0.005 Styrene ND 1.0 0.005 1,1,1,2-Tetrachioroethane ND 1.0 0.0051,1,2,2-Tetrachloroethane ND 1.0 0.005 Tetrachloroethene ND 1.0 0.005 ND 1.0 0.005 Toluene 1,2,3-Trichlorobenzene ND 1.0 0.005 1,2,4-Trichlorobenzene ND 1.0 0.005 1,1,1-Trichloroethane ND 1.0 0.005 1,1,2-Trichloroethane ND 1.0 0.005 Trichloroethene ND 1.0 0.005 Trichlorofluoromethane ND 1.0 0.005 1,2,3-Trichloropropane ND 1.0 0.005 1,2,4-Trimethylbenzene ND 1.0 0.005 1,3,5-Trimethylbenzene ND 1.0 0.005 Vinyl Chloride ND 1.0 0.005Xylenes ND 1.0 0.005

 Surrogate Recoveries (%)

 %SS1:
 94
 %SS2:
 101

 %SS3:
 105
 105
 101

ND means not detected above the reporting limit; N/A means analyte not applicable to this analysis.

# surrogate diluted out of range or coelutes with another peak; &) low surrogate due to matrix interference.

h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~I vol. % sediment; j) sample diluted due to high organic content/matrix interference; k) reporting limit near, but not identical to our standard reporting limit due to variable Encore sample weight; m) reporting limit raised due to insufficient sample amount; n) results are reported on a dry weight basis; p) see attached narrative.

Comments:

<sup>\*</sup> water and vapor samples are reported in µg/L, soil/sludge solid samples in mg/kg, product/oil/non-aqueous liquid samples and all TCLP & SPLP extracts are reported in mg/L, wipe samples in µg/wipe.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

4		
Basics Environmental	Client Project ID: 5105 E.8th ST.	Date Sampled: 09/07/05
	Oakland	Date Received: 09/07/05
116 Glorietta Blvd.	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Orinda, CA 94563	Client P.O.:	Date Analyzed: 09/10/05

### Volatile Organics by P&T and GC/MS (Basic Target List)\*

Extraction Method: SW5030B	Analytical Method: SW8260B	Work Order: 0509151
Lab ID	0509151-005A	
Client ID	SB3 @ 4'	
Matrix	Soil	
		Perceting

Matrix	Soil						
Compound	Concentration *	DF	Reporting Limit	Compound	Concentration *	DF	Reporting Limit
Acetone	ND	1.0	0.05	Acrolein (Propenal)	ND	1.0	0.05
Acrylonitrile	ND	1.0	0.02	tert-Amyl methyl ether (TAME)	ND	1.0	0.005
Benzene	ND	1.0	0.005	Bromobenzene	ND	1.0	0.005
Bromochloromethane	ND	1.0	0.005	Bromodichloromethane	ND	1.0	0.005
Bromoform	ND	1.0	0.005	Bromomethane	ND	1.0	0.005
2-Butanone (MEK)	ND	1.0	0.02	t-Butyl alcohol (TBA)	ND	0.1	0.05
n-Butyl benzene	ND	1.0	0.005	sec-Butyl benzene	ND	1.0	0.005
tert-Butyl benzene	ND	1.0	0.005	Carbon Disulfide	ND	1.0	0.005
Carbon Tetrachloride	ND	1.0	0.005	Chlorobenzene	ND	1.0	0.005
Chloroethane	ND	1.0	0.005	2-Chloroethyl Vinyl Ether	ND	1.0	0.01
Chloroform	ND	1.0	0.005	Chloromethane	ND	1.0	0.005
2-Chlorotoluene	ND	1.0	0.005	4-Chlorotoluene	ND	1.0	0.005
Dibromochloromethane	ND	1.0	0.005	1,2-Dibromo-3-chloropropane	ND	1.0	0.005
1,2-Dibromoethane (EDB)	ND	1.0	0.005	Dibromomethane	ND	1.0	0.005
1.2-Dichlorobenzene	· ND	1.0	0.005	1,3-Dichlorobenzene	ND	1.0	0.005
1.4-Dichlorobenzene	ND	1.0	0.005	Dichlorodifluoromethane	ND	1.0	0.005
1,1-Dichloroethane	ND	1.0	: 0.005	1,2-Dichloroethane (1,2-DCA)	ND	1.0	0.005
1.1-Dichloroethene	ND	1.0	0.005	cis-1,2-Dichloroethene	ND	1.0	0.005
trans-1,2-Dichloroethene	ND	1.0	0.005	1,2-Dichloropropane	ND	0.1	0.005
1,3-Dichloropropane	: ND	1.0	0.005	2,2-Dichloropropane	ND	1.0	0.005
1,1-Dichloropropene	ND	1.0	0.005	cis-1,3-Dichloropropene	ND	1.0	0.005
trans-1,3-Dichloropropene	ND	1.0	0.005	Diisopropyl ether (DIPE)	ND	1.0	0.00
Ethylbenzene	ND	1.0	0.005	Ethyl tert-butyl ether (ETBE)	ND	1.0	0.00:
Freon 113	ND	1.0	0.1	Hexachlorobutadiene	ND	1.0	0.00
Hexachloroethane	ND	1.0	0.005	2-Hexanone	ND	1.0	0.00
Isopropylbenzene	ND	1.0	0.005	4-Isopropyl toluene	ND	1.0	0.00
Methyl-t-butyl ether (MTBE)	ND	1.0	0.005	Methylene chloride	ND	1.0	0.00:
4-Methyl-2-pentanone (MIBK)	ND	1.0	0.005	Naphthalene	ND	1.0	0.00
Nitrobenzene	ND	1.0	0.1	n-Propyl benzene	ND	1.0	0.00
Styrene	ND	1.0	0.005	1,1,1,2-Tetrachloroethane	ND	1.0	0.00
1,1,2,2-Tetrachloroethane	ND	. 1.0	0.005	Tetrachloroethene	ND	1.0	0.00
Toluene	ND	1.0	0.005	1,2,3-Trichlorobenzene	ND	0.1	0.00
1.2.4-Trichlorobenzene	ND	1.0	0.005	1,1,1-Trichloroethane	ND .	1.0	0.00
1.1.2-Trichloroethane	ND	1.0	0.005	Trichloroethene	ND	1.0	0.00
Trichlorofluoromethane	ND	1.0	0.005	<del> </del>	ND	1.0	0.00
1,2,4-Trimethylbenzene	ND	1.0	0.005		ND	1.0	0.00
Vinyl Chloride	ND	1.0	0.005		ND	1.0	0.00
- myr chiorida		Su		ecoveries (%)			
%SS1:	3	6	9	%SS2:	16	00	
7,0001.		7.5		<del> </del>			

%SS3: 105
Comments:

\* water and vapor samples are reported in μg/L, soil/sludge/solid samples in mg/kg, product/oil/non-aqueous liquid samples and all TCLP & SPLP extracts are reported in mg/L, wipe samples in μg/wipe.

ND means not detected above the reporting limit; N/A means analyte not applicable to this analysis.

# surrogate diluted out of range or coelutes with another peak; &) low surrogate due to matrix interference.

h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~1 vol. % sediment; j) sample diluted due to high organic content/matrix interference; k) reporting limit near, but not identical to our standard reporting limit due to variable Encore sample weight; m) reporting limit raised due to insufficient sample amount; n) results are reported on a dry weight basis; p) see attached narrative.



Extraction Method: SW5030B

# McCampbell Analytical, Inc.

110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

Work Order: 0509151

Basics Environmental	Client Project ID: 5105 E.8th ST.	Date Sampled: 09/07/05
116 Glorietta Blvd.	Oakland	Date Received: 09/07/05
	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Orinda, CA 94563	Client P.O.:	Date Analyzed: 09/13/05

### Volatile Organics by P&T and GC/MS (Basic Target List)\* Analytical Method: SW8260B

C1: . ID	Ī .		0509151-007A				
Client ID		SB4 @ 4'					
Matrix		Soil					
Compound	Concentration *	DF	Reporting Limit	Compound	Concentration *	DF	Reporting Limit
Acetone	ND :	1.0	0.05	Acrolein (Propenal)	ND	1.0	0.05
Acrylonitrile	ND	1.0	0.02	tert-Amyl methyl ether (TAME)	ND	0.1	0.005
Benzene	ND .	1.0	0.005	Bromobenzene	ND	1.0	0.005
Bromochloromethane	ND	1.0	0.005	Bromodichloromethane	מא	1.0	0.005
Bromoform	ND .	1.0	0.005	Bromomethane	ND	1.0	0.005
2-Butanone (MEK)	ND	1.0	0.02	t-Butyl alcohol (TBA)	ND	1.0	0.05
n-Butyl benzene	ND	1.0	0.005	sec-Butyl benzene	ND	1.0	0.005
tert-Butyl benzene	ND	1.0	0.005	Carbon Disulfide	ND	1.0	0.005
Carbon Tetrachloride	ND	1.0	0.005	Chlorobenzene	ND	1.0	0.005
Chloroethane	ND	0.1	0.005	2-Chloroethyl Vinyl Ether	ND	1.0	0.01
Chloroform	DN	1.0	0.005	Chloromethane	ND	1.0	0.005
2-Chlorotoluene	ND	1.0	0.005	4-Chlorotoluene	ND	1.0	0.005
Dibromochloromethane	ND	1.0	0.005	1,2-Dibromo-3-chloropropane	ND	1.0	0.005

Dibromochloromethane	ND	1.0	0.005	1.2-Dibromo-3-chloropropane	ND	∹ 1.0 ∜	0.005
1,2-Dibromoethane (EDB)	ND	1.0	0.005	Dibromomethane	ND	1.0	0.005
1,2-Dichlorobenzene	ND	1.0	0.005	1,3-Dichlorobenzene	ND	1.0	0.005
1,4-Dichlorobenzene	ND	1.0	0.005	Dichlorodifluoromethane	ND	1.0	0.005
I,I-Dichloroethane	ND	1.0	0.005	1,2-Dichloroethane (1,2-DCA)	ND	1.0	0.005
1,1-Dichloroethene	ND	1.0	0.005	cis-1,2-Dichloroethene	ND	1.0	0.005
trans-1,2-Dichloroethene	ND	1.0	0.005	1,2-Dichloropropane	ND	1.0	0.005
1,3-Dichloropropane	ND	1.0	0.005	2,2-Dichloropropane	ND	1.0	0.005
1,1-Dichloropropene	ND	1.0	0.005	cis-1,3-Dichloropropene	ND	1.0	0.005
trans-1,3-Dichloropropene	ND	1.0	0.005	Diisopropyl ether (DIPE)	ND	1.0	0.005
Ethylbenzene	ND	1.0	0.005	Ethyl tert-butyl ether (ETBE)	ND	1.0	0.005
Freon 113	ND	1.0	0.1	Hexachlorobutadiene	ND	1.0	0.005
Hexachioroethane	ND	1.0	0.005	2-Hexanone	ND.	1.0	0.005
Isopropyibenzene	ND	1.0	0.005	4-Isopropyl toluene	ND	1.0	0.005
Methyl-t-butyl ether (MTBE)	ND	1.0	0.005	Methylene chloride	ND	1.0	0.005
4-Methyl-2-pentanone (MIBK)	ND	1.0	0.005	Naphthalene	ND	1.0	0.005
Nitrobenzene	ND	1.0	0.1	n-Propyl benzene	ND	1.0	0.005
Styrene	ND	1.0	0.005	1,1,1,2-Tetrachioroethane	ND	1.0	0.005
1,1,2,2-Tetrachloroethane	ND	: 1.0	0.005	Tetrachloroethene	ND	1.0	0.005
Toluene	ND	1.0	0.005	1,2,3-Trichlorobenzene	ND	1.0	0.005

Vinyl Chloride	ND	1.0	0.005 Xylenes	ND	1.0 0.005		
Surrogate Recoveries (%)							
%SS1:		95	%SS2:		101		
%SS3:		106					

0.005

0.005

0.005

0.005

1,1,1-Trichloroethane

1,2,3-Trichloropropane

1,3,5-Trimethylbenzene

Trichloroethene

1.0

1.0

1.0

1.0

Comments:

1,2,4-Trichlorobenzene

Trichlorofluoromethane

1,2,4-Trimethylbenzene

1,1,2-Trichloroethane

ND means not detected above the reporting limit; N/A means analyte not applicable to this analysis.

ND

ND

ND

ND

h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~1 vol. % sediment; j) sample diluted due to high organic content/matrix interference; k) reporting limit near, but not identical to our standard reporting limit due to variable Encore sample weight; m) reporting limit raised due to insufficient sample amount; n) results are reported on a dry weight basis; p) see attached narrative.



ND

ND

ND

ND

1.0

1.0

1.0

1.0

0.005

0.005

0.005

0.005

<sup>\*</sup> water and vapor samples are reported in µg/L, soil/sludge/solid samples in mg/kg, product/oil/non-aqueous liquid samples and all TCLP & SPLP extracts are reported in mg/L, wipe samples in µg/wipe.

<sup>#</sup> surrogate diluted out of range or coelutes with another peak; &) low surrogate due to matrix interference.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

<del>-</del>		
Basics Environmental	Client Project ID: 5105 E.8th ST.	Date Sampled: 09/07/05
116 Glorietta Blvd.	Oakland	Date Received: 09/07/05
	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Orinda, CA 94563	Client P.O.:	Date Analyzed: 09/13/05

### Volatile Organics by P&T and GC/MS (Basic Target List)\*

Extraction Method: SW 5030B	Analytical Method: SW8260B	Work Order: 0509151
Lab ID	0509151-009A	
Client ID	SB5 @ 4'	
Matrix	Soil	
	B	

Manx				2011			
Compound	Concentration *	DF	Reporting Limit	Compound	Concentration *	DF	Reporting Limit
Acetone	. ND	1.0	0.05	Acrolein (Propenal)	ND	1.0	0.05
Acrylonitrile	. ND	1.0	0.02	tert-Amyl methyl ether (TAME)	ND	1.0	0.005
Benzene	ND	1.0	0.005	Bromobenzene	ND	1.0	0.005
Bromochloromethane	; ND	1.0	0.005	Bromodichloromethane	ND	1.0	0.005
Bromoform	ND	1.0	0.005	Bromomethane	ND	1.0	0.005
2-Butanone (MEK)	ND	1.0	0.02	t-Butyl alcohol (TBA)	ND	1.0	0.05
n-Butyl benzene	ND	1.0	0.005	sec-Butyl benzene	ND	1.0	0.005
tert-Butyl benzene	ND	1.0	0.005	Carbon Disulfide	ND	1.0	0.005
Carbon Tetrachloride	ND	1.0	0.005	Chlorobenzene	ND	1.0	0.005
Chloroethane	ND	1.0	0.005	2-Chloroethyl Vinyl Ether	ND	1.0	0.01
Chloroform	ND	1.0	0.005	Chloromethane	ND	1.0	0.005
2-Chlorotoluene	ND	1.0	0.005	4-Chlorotoluene	ND	1.0	0.005
Dibromochloromethane	ND	1.0	0.005	1,2-Dibromo-3-chloropropane	ND	1.0	0.005
1,2-Dibromoethane (EDB)	ND	1.0	0.005	Dibromomethane	ND	1.0	0.005
1,2-Dichlorobenzene	ND	1.0	0.005	1,3-Dichlorobenzene	ND	1.0	0.005
1,4-Dighlorobenzene	ND	0.1	0.005	Dichlorodifluoromethane	ND	0.1	0.005
1,1-Dichloroethane	ND	1.0	0.005	1,2-Dichloroethane (1,2-DCA)	ND	1.0	0.005
1.1-Dichloroethene	ND	1.0	0.005	cis-1,2-Dichloroethene	ND	1.0	0.005
trans-1,2-Dichloroethene	ND	1.0	0.005	1,2-Dichloropropane	ND	1.0	0.005
1,3-Dichloropropane	ND	1.0	0.005	2,2-Dichloropropane	ND	1.0	0.005
1,1-Dichloropropene	ND	1.0	0.005	cis-1,3-Dichloropropene	ND	1.0	0.005
trans-1,3-Dichloropropene	ND	1.0	0.005	Diisopropyl ether (DIPE)	ND	1.0	0.005
Ethylbenzene	· ND	1.0	0.005	Ethyl tert-butyl ether (ETBE)	ND	1.0	0.005
Freon 113	ND	1.0	0.1	Hexachlorobutadiene	ND	1.0	0.005
Hexachloroethane	ND	1.0	0.005	2-Hexanone	ND	1.0	0.005
Isopropylbenzene	ND	1.0	0.005	4-Isopropyl toluene	ND	1.0	0.005
Methyl-t-butyl ether (MTBE)	ND	1.0	0.005	Methylene chloride	ND	1.0	0.005
4-Methyl-2-pentanone (MIBK)	ND	0.1	0.005	Naphthalene	ND	1.0	0.005
Nitrobenzene	ND	1.0	1.0	n-Propyl benzene	ND	1.0	0.00
Styrene	ND	1.0	0.005	1,1,1,2-Tetrachloroethane	ND	1.0	0.003
1,1,2,2-Tetrachloroethane	ND	1.0	0.005	Tetrachloroethene	ND	1.0	0.00
Toluene	ND	1.0	0.005	1,2,3-Trichlorobenzene	ND	1.0	0.005
1,2,4-Trichlorobenzene	ND	1.0	0.005	1,1,1-Trichloroethane	ND	1.0	0.005
1,1,2-Trichloroethane	ND	1.0	0.005	Trichloroethene	ND	1.0	0.00
Trichlorofluoromethane	ND	1.0	0.005	1,2.3-Trichloropropane	ND	1.0	0.00
1.2.4-Trimethylbenzene	ND	1.0	0.005	1,3.5-Trimethylbenzene	ND	1.0	0.003
							V.VV.

· myr omorius	(12)	000   10,0000			1.0	0.005		
Surrogate Recoveries (%)								
%SS1:	92	%SS2:			101			
%SS3:	. 106							
G								

ND means not detected above the reporting limit; N/A means analyte not applicable to this analysis.

h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than -1 vol. % sediment; j) sample diluted due to high organic content/matrix interference; k) reporting limit near, but not identical to our standard reporting limit due to variable Encore sample weight; m) reporting limit raised due to insufficient sample amount; n) results are reported on a dry weight basis; p) see attached narrative.



<sup>•</sup> water and vapor samples are reported in μg/L, soil/sludge solid samples in mg/kg, product/oil/non-aqueous liquid samples and all TCLP & SPLP extracts are reported in mg/L, wipe samples in μg/wipe.

<sup>#</sup> surrogate diluted out of range or coelutes with another peak; &) low surrogate due to matrix interference.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

<del></del>	<del></del>	
Basics Environmental	Client Project ID: 5105 E.8th ST.	Date Sampled: 09/07/05
116 Glorietta Blvd.	Oakland	Date Received: 09/07/05
	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Orinda, CA 94563	Client P.O.:	Date Analyzed: 09/10/05

Orinda, CA 94363 Client P.O.: Date Analyzed: 09/10/05								
Extraction Method: SW5030B	Volatile Organi			d GC/MS (Basic Target List	•	· O - 4		
····	,	Alla	nytical Me		work	Order: 0.	509151	
Lab ID				0509151-011A				
Client ID				SB6 @ 4'				
Matrix				Soil				
Compound	Concentration *	DF	Reporting Limit	Compound	Concentration *	DF	Reporting Limit	
Acetone	ND	1.0	0.05	Acrolein (Propenal)	ND	0.1	0.05	
Acrylonitrile	ND	1.0	0.02	tert-Amyl methyl ether (TAME)	ND	1.0	0.005	
Benzene	ND	1.0	0.005	Bromobenzene	ND	1.0	0.005	
Bromochloromethane	ND	1.0	0.005	Bromodichloromethane	ND	1.0	0.005	
Bromoform	ND	1.0	0.005	Bromomethane	ND	1.0	0.005	
2-Butanone (MEK)	ND	1.0	0.02	t-Butyl alcohol (TBA)	ND	1.0	0.05	
n-Butyl benzene	ND	1.0	0.005	sec-Butyl benzene	ND	1.0	0.005	
tert-Butyl benzene	ND	1.0	0.005	Carbon Disulfide	ND	1.0	0.005	
Carbon Tetrachloride	ND	1.0	0.005	Chlorobenzene	ND	1.0	0.005	
Chloroethane	ND	1.0	0.005	2-Chloroethyl Vinyl Ether	ND	1.0	0.003	
Chloroform	ND	1.0	0.005	Chloromethane	ND	1.0	0.005	
2-Chlorotoluene	ND	1.0	0.005	4-Chlorotoluene	ND	1.0	0.003	
Dibromochloromethane	ND	1.0	0.005	1,2-Dibromo-3-chloropropane	ND	1.0	0.003	
1,2-Dibromoethane (EDB)	, ND	1.0	0.005	Dibromomethane	ND	1.0	0.003	
1,2-Dichlorobenzene	ND	1.0	0.005	1,3-Dichlorobenzene	ND	1.0	-	
1,4-Dichlorobenzene	ND	1.0	0.005	Dichlorodifluoromethane	ND	1.0	0.005	
1,1-Dichloroethane	ND	1.0	0.005	1,2-Dichloroethane (1,2-DCA)	<del></del>		0.005	
1,1-Dichloroethene	ND	1.0	0.005	cis-1,2-Dichloroethene	ND ND	1.0	0.005	
trans-1,2-Dichloroethene	ND	1.0	0.005	1,2-Dichloropropane	ND	1.0	0.005	
1,3-Dichloropropane	ND	1.0	0.005	2,2-Dichloropropane	<del></del>	0.1	0.005	
1,1-Dichloropropene	ND	1.0	0.005		ND	0.1	0.005	
trans-1,3-Dichloropropene	ND	1.0	+	cis-1,3-Dichloropropene	ND ND	1.0	0.005	
	ND ND	1.0	0.005	Diisopropyl ether (DIPE)	ND	1.0	0.005	
Ethylbenzene Freon 113	ND ND		0.005	Ethyl tert-butyl ether (ETBE)	ND ND	1.0	0.005	
	·	1.0	0.1	Hexachlorobutadiene	ND ND	1.0	0.005	
Hexachloroethane	ND ND	1.0	0.005	2-Hexanone	ND	1.0	0.005	
Isopropylbenzene	ND	1.0	0.005	4-Isopropyl toluene	ND	1.0	0.005	
Methyl-t-butyl ether (MTBE)	· ND	1.0	0.005	Methylene chloride	ND ND	1.0	0.005	
4-Methyl-2-pentanone (MIBK)	ND	1.0	0.005	Naphthalene	ND	1.0	0.005	
Nitrobenzene	ND ND	1.0	0.1	n-Propyl benzene	ND	1.0	0.005	
Styrene	ND	1.0	0.005	1,1,1,2-Tetrachloroethane	ND	1.0	0.005	
1,1,2,2-Tetrachloroethane	ND	1.0	0.005	Tetrachloroethene	ND	1.0	0.005	
Toluene	ND	1.0	0.005	1,2,3-Trichlorobenzene	ND	1.0	0.005	
1,2,4-Trichlorobenzene	ND	1.0	0.005	1,1,1-Trichloroethane	ND	1.0	0.005	
1,1,2-Trichloroethane	ND	1.0	0.005	Trichloroethene	ND	1.0	0.005	
Trichlorofluoromethane	ND	1.0	0.005	1,2,3-Trichloropropane	ND	1.0	0.005	
1,2,4-Trimethylbenzene		1.0	0.005	1,3,5-Trimethylbenzene	ND	1.0	0.005	
Vinyl Chloride	ND	1.0	0.005	Xylenes	ND	1.0	0.005	
		Sur	rogate R	ecoveries (%)				
%SS1:	85	;		%SS2:	10	1		
%SS3:	: 10	5					· · · · · ·	

		gate Recoveries (%)	
%SS1:	 85	%SS2:	101
%SS3:	 105		· · · · · · · · · · · · · · · · · · ·
Comments:	 		

<sup>\*</sup> water and vapor samples are reported in µg/L, soil/sludge/solid samples in mg/kg, product/oil/non-aqueous liquid samples and all TCLP & SPLP extracts are reported in mg/L, wipe samples in ug/wipe.

ND means not detected above the reporting limit; N/A means analyte not applicable to this analysis.

<sup>#</sup> surrogate diluted out of range or coelutes with another peak; &) low surrogate due to matrix interference.

h) lighter than water immiscible sheen/product is present; i) liquid sample that contains greater than ~1 vol. % sediment; j) sample diluted due to high organic content/matrix interference; k) reporting limit near, but not identical to our standard reporting limit due to variable Encore sample weight; m) reporting limit raised due to insufficient sample amount; n) results are reported on a dry weight basis; p) see attached narrative.




110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST. Oakland	Date Sampled: 09/07/05
116 Glorietta Blvd.		Date Received: 09/07/05
Orinda, CA 94563	Client Contact: Donavan Tom	Date Extracted: 09/07/05
	Client P.O.:	Date Analyzed: 09/10/05-09/12/05

	CAM / CCR 17 Metals*												
Lab ID	0509151-001A	0509151-003A	0509151-005A	0509151-007A	Reporting Limit for DF =1;								
Client ID	SB1 @ 4'	SB2 @ 4'	SB3 @ 4'	SB4 @ 4'	ND means not detected above the reporting limit								
Matrix	S	S	S	S	s w								
Extraction Type	TTLC	TTLC	TTLC	TTLC	mg/Kg mg/L								

		<u> </u>			1					
ICP-MS Metals, Concentration*  Analytical Method: 6020A Extraction Method: SW3050B Work Order: 0509151										
Dilution Factor	1	1	t !	1	t t	1				
Antimony	ND	1.1	25	ND	0.5	NA				
Arsenic	2.9	96	190	20	0.5	NA				
Barium	160	190	230	310	5.0	NA				
Beryllium	ND	ND	ND	ND	0.5	NA				
Cadmium	ND	0.90	6.5	ND	0.25	NA				
Chromium	51	47	49	45	0.5	NA				
Cobalt	7.9	10	9.7	14	0.5	NA				
Copper	16	16	32	18	0.5	NA				
Lead	4.0	15	1400	-12	0.5	NA				
Mercury	ND	0.62	0.96	0.052	0.05	NA				
Molybdenum	ND	1.7	10	ND	0.5	NA				
Nickel	66	58	54	. 53	0.5	NA				
Selenium	ND	DN	0.66	0.56	0.5	NA				
Silver	ND	ND	1.9	ND	0.5	NA				
Thallium	ND	ND	ND	ND	0.5	NA				
Vanadium	40	54	40	54	0.5	NA				
Zinc	25	62	410	31	5.0	NA				
%SS:	93	99	96	99						

# \*water samples are reported in µg/L, product/oil/non-aqueous liquid samples and all TCLP / STLC / DISTLC / SPLP extracts are reported in mg/L, soil/sludge/solid samples in mg/kg, wipe samples in µg/wipe, filter samples in µg/filter.



<sup>#</sup> means surrogate diluted out of range; ND means not detected above the reporting limit; N/A means not applicable to this sample or instrument.

i) aqueous sample containing greater than ~1 vol. % sediment; for DISSOLVED metals, this sample has been preserved prior to filtration; for TTLC metals, a representative sediment-water mixture was digested; j) reporting limit raised due to insufficient sample amount; k) reporting limit raised due to matrix interference; m) estimated value due to low/high surrrogate recovery, caused by matrix interference; n) results are reported on a dry weight basis; p) see attached narrative.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560
- Telephone: 925-798-1620 Fax: 925-798-1622
Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST. Oakland	Date Sampled: 09/07/05
116 Glorietta Blvd.	·	Date Received: 09/07/05
Orinda, CA 94563	Client Contact: Donavan Tom	Date Extracted: 09/07/05
Offida, CA 94303	Client P.O.:	Date Analyzed: 09/10/05-09/12/05


	C	CAM / CCR 17 Metals*	
Lab (D	0509151-009A	0509151-011A	Reporting Limit for DF =1;
Client ID	SB5 @ 4'	SB6 @ 4'	ND means not detected above the reporting limit
Matrix	S	S	S W
Extraction Type	TTLC	TTLC	mg/Kg mg/L

ICP-MS Metals, Concentration*								
Analytical Method: 6020A	Ext	raction Method: SW3050B		Work Ord	er: 0509151			
Dilution Factor	1	ì		1	1			
Antimony	2.2	4.6		0.5	NA			
Arsenic	22	27		0.5	NA			
Barium	190	190		5.0	NA			
Beryllium	ND	ND		0.5	NA			
Cadmium	0.75	4.8		0.25	NA			
Chromium	40	42		0.5	NA			
Cobalt	11	5.4		0.5	NA			
Copper	15	20		0.5	NA			
Lead	14	24		0.5	NA			
Mercury	0.052	0.11		0.05	NA			
Molybdenum	ND	0.79		0.5	NA			
Nickel	40	49		0.5	NA .			
Selenium	ND	0.51		0.5	NA			
Silver	ND	ND		0.5	NA			
Thallium	ND	ND		0.5	NA			
Vanadium	35	31		0.5	NA			
Zinc	45	130		5.0	NA			
%SS:	88	103			1			

\*water samples are reported in µg/L, product/oil/non-aqueous liquid samples and all TCLP / STLC / DISTLC / SPLP extracts are reported in mg/L, soil/sludge/solid samples in mg/kg, wipe samples in µg/wipe, filter samples in µg/filter.

# means surrogate diluted out of range; ND means not detected above the reporting limit; N/A means not applicable to this sample or instrument.

i) aqueous sample containing greater than ~1 vol. % sediment; for DISSOLVED metals, this sample has been preserved prior to filtration; for TTLC metals, a representative sediment-water mixture was digested; j) reporting limit raised due to insufficient sample amount; k) reporting limit raised due to matrix interference; m) estimated value due to low/high surrrogate recovery, caused by matrix interference; n) results are reported on a dry weight basis; p) see attached narrative.





110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

### QC SUMMARY REPORT FOR SW8021B/8015Cm

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: SW8021B/	: SW5030	B	BatchID: 17905			Spiked Sample ID: 0509169-003A				
Analyte	Sample	Spiked	MS	MS MSD	MS-MSD LCS I	LCSD	LCS-LCSD	Acceptance Criteria (%)		
·	mg/Kg	mg/Kg	% Rec.	% Rec.	% RPD % Rec.		% Rec.	% Rec. % RPD		LCS / LCSD
TPH(btex) <sup>£</sup>	DN	0.60	111	112	1.35	111	111	0	70 - 130	70 - 130
МТВЕ	ND	0.10	93.5	95.7	2.41	102	103	1.24	70 - 130	70 - 130
Benzene	ND	0.10	94.4	97.6	3.43	99.2	99.4	0.230	70 - 130	70 - 130
Toluene	ND	0.10	94.5	97.8	3.38	99.5	100	0.694	70 - 130	70 - 130
Ethylbenzene	ND	0.10	99.3	102	2.91	103	103	0	70 - 130	70 - 130
Xylenes	ND	0.30	100	103	3.28	103	103	0	70 - 130	70 - 130
%SS:	97	0.10	105	107	1.89	110	112	1.80	70 - 130	70 - 130

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### BATCH 17905 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-011A	9/07/05 1:00 PM	9/07/05	9/08/05 1:46 PM				

IMS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

£ TPH(btex) = sum of BTEX areas from the FID.

# cluttered chromatogram; sample peak coelutes with surrogate peak.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

# QC SUMMARY REPORT FOR SW8021B/8015Cm

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: SW8021B/8015Cm Extraction: SW5030B					BatchiD: 17896 Spiked S				iample ID: 0509141-005A		
A II A -	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance	e Criteria (%)	
Analyte mg/K	mg/Kg	mg/Kg	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	MS / MSD	LCS / LCSD	
TPH(btex) £	ND	0.60	110	112	1.50	112	111	0.522	70 - 130	70 - 130	
МТВЕ	ND	0.10	99.4	97.6	1.81	98.2	99.9	1.75	70 - 130	70 - 130	
Benzene	ND	0.10	97.5	96.l	1.47	93.6	96.9	3.43	70 - 130	70 - 130	
Toluene	ND	0.10	97.8	96.4	1.49	94.5	97.3	2.87	70 - 130	70 - 130	
Ethylbenzene	ND	0.10	102	100	1.71	99.5	101	1.88	70 - 130	70 - 130	
Xylenes	ND	0.30	103	100	3.28	100	100	0	70 - 130	70 - 130	
%\$S:	96	0.10	108	104	3.77	103	107	3.81	70 - 130	70 - 130	

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### BATCH 17896 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-001A	9/07/05 1:00 PM	9/07/05	9/08/05 10:25 AM	0509151-003A	9/07/05 1:00 PM	9/07/05	9/08/05 1:13 PM
0509151-005A	9/07/05 1:00 PM	9/07/05	9/08/05 9:35 AM	0509151-007A	9/07/05 1:00 PM	9/07/05	9/08/05 12:39 PM
0509151-009A	9/07/05 1:00 PM	9/07/05	9/08/05 9:05 AM				·

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

£ TPH(btex) = sum of BTEX areas from the FID.

# cluttered chromatogram; sample peak coelutes with surrogate peak.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.

LA QA/QC Officer



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

### QC SUMMARY REPORT FOR SW8015C

W.O. Sample Matrix: Soil

QC Matrix; Soil

WorkOrder: 0509151

EPA Method: SW8015C	E	xtraction	SW3550	С	Batc	hID: 17904	,	0 70 - 130 70 - 130		9157-001A
Analyte	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance	Criteria (%)
- Analyto	mg/Kg	mg/Kg	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	LCS/LCSD	
TPH(d)	ND	20	104	105	1.07	102	102	0	70 - 130	70 - 130
%SS:	98	50	93	94	0.993	93	93	0	70 - 130	70 - 130

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### **BATCH 17904 SUMMARY**

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-003A	9/07/05 1:00 PM	9/07/05	9/09/05 8:04 AM	0509151-005A	9/07/05 1:00 PM	9/07/05	9/09/05 9:13 AM
0509151-007A	9/07/05 1:00 PM	9/07/05	9/09/05 2:01 PM	0509151-009A	9/07/05 1:00 PM	9/07/05	9/08/05 11:55 PM
0509151-011A	9/07/05 1:00 PM	9/07:05	9/09/05 1:05 AM	1			, , , , , , , , ,

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

# **QC SUMMARY REPORT FOR SW8015C**

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: SW8015C	E	xtraction:	SW3550	С	Batci	hID: 17885		0 70 - 130 70 - 13		9141-005A
Analyte	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance	Criteria (%)
Ailalyte	mg/Kg	mg/Kg	% Rec.	% Rec.	% RPD	% RPD				LCS / LCSD
TPH(d)	ND	20	104	105	1.30	103	103	0	70 - 130	70 - 130
%SS:	100	50	93	94	0.661	93	94	0.286	70 - 130	70 - 130

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### **BATCH 17885 SUMMARY**

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-001a	9/07/05 1:00 PM	9/07/05	9/08/05 7:19 AM				

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to light matrix or analyte content.

110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

### QC SUMMARY REPORT FOR SW8260B

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: SW8260B	Е	xtraction	SW5030	В	Batci	hID: 17906	ì	Spiked San	nple ID: 050	9154-001A
Analyte	Sample	Spiked	мѕ	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance	Criteria (%)
, w.a., 10	mg/kg	mg/kg	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	MS / MSD	LCS / LCSD
tert-Amyl methyl ether (TAME)	ND	0.050	81.9	82.9	1.25	95	94.5	0.602	70 - 130	70 - 130
Benzene	ND	0.050	108	110	2.10	112	113	0.488	70 - 130	70 - 130
t-Butyl alcohol (TBA)	ND	0.25	103	105	1.83	94.4	99.4	5.16	70 - 130	70 - 130
Chlorobenzene	ND	0.050	114	115	0.962	117	118	0.771	70 - 130	70 - 130
1,2-Dibromoethane (EDB)	ND	0.050	87.3	88.1	0.881	98.3	99.2	0.927	70 - 130	70 - 130
1,2-Dichloroethane (1,2-DCA)	ND	0.050	101	101	0	113	113	0	70 - 130	70 - 130
1,1-Dichloroethene	ND	0.050	119	118	1.12	116	116	0	70 - 130	70 - 130
Diisopropyl ether (DIPE)	ND	0.050	113	li6	2.89	117	118	0.466	70 - 130	70 - 130
Ethyl tert-butyl ether (ETBE)	ND	0.050	85.9	88.3	2.83	103	101	2.35	70 - 130	70 - 130
Methyl-t-butyl ether (MTBE)	ND	0.050	38.2	87.2	1.17	105	103	2.49	70 - 130	70 - 130
Toluene	ИD	0.050	99.8	102	2.51	102	104	2.31	70 - 130	70 - 130
Trichloroethene	ИD	0.050	34.6	85.7	1.35	93.3	91.9	1.46	70 - 130	70 - 130
%SS1:	102	0.050	105	103	1.53	108	107	1.33	70 - 130	70 - 130
%SS2:	102	0.050	96	97	0.898	101	100	1.07	70 - 130	70 - 130
%SS3:	106	0.050	101	101	0	102	104	1.91	70 - 130	70 - 130

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### BATCH 17906 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-009A	9/07/05 I:00 PM	9/07/05	9/13/05 8:30 AM	0509151-011A	9/07/05 1:00 PM	9/07/05	9/10/05 4:58 AM

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.

Laboratory extraction solvents such as methylene chloride and acetone may occasionally appear in the method blank at low levels.

110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

### QC SUMMARY REPORT FOR SW8260B

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: SW8260B	E	xtraction:	SW5030	В	Batch	nID: 17867	•	c. % RPD MS / MSD LCS / LCSD  0.653 70 - 130 70 - 130  0.491 70 - 130 70 - 130  3.32 70 - 130 70 - 130  2.06 70 - 130 70 - 130  1.30 70 - 130 70 - 130  0.785 70 - 130 70 - 130  0 70 - 130 70 - 130  0 70 - 130 70 - 130  0 70 - 130 70 - 130  0 0.946 70 - 130 70 - 130			
Analyte	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance	Criteria (%)	
Analyte	mg/kg	mg/kg	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	MS / MSD	LCS / LCSD	
tert-Amyl methyl ether (TAME)	ND	0.050	82.6	85.1	2.96	85.7	86.3	0.653	70 - 130	70 - 130	
Benzene	ND	0.050	108	108	0	108	109	0.491	70 - 130	70 - 130	
t-Butyl alcohol (TBA)	ND	0.25	87.7	87.8	0.101	92.7	95.8	3.32	70 - 130	70 - 130	
Chlorobenzene	ND	0.050	116	114	1.13	115	117	2.06	70 - 130	70 - 130	
1,2-Dibromoethane (EDB)	ND	0.050	87.2	88.2	1.14	87.5	88.7	1.30	70 - 130	70 - 130	
1,2-Dichloroethane (1,2-DCA)	ND	0.050	105	102	3.76	106	107	0.785	70 - 130	70 - 130	
1,1-Dichloroethene	ND	0.050	119	118	0.938	119	119	0	70 - 130	70 - 130	
Diisopropyl ether (DIPE)	ND	0.050	112	117	3.55	115	115	0	70 - 130	70 - 130	
Ethyl tert-butyl ether (ETBE)	ND	0.050	88	90.9	3.26	90.2	91	0.946	70 - 130	70 - 130	
Methyl-t-butyl ether (MTBE)	ND	0.050	\$7.7	88.1	0.475	88.6	90.9	2.46	70 - 130	70 - 130	
Toluene	ND	0.050	99.6	101	1.75	101	103	2.24	70 - 130	70 - 130	
Trichloroethene	ND	0.050	84.8	85.7	1.07	85.7	85.3	0.503	70 - 130	. 70 - 130	
%SS1:	90	0.050	103	104	0.237	104	104	0	70 - 130	70 - 130	
%SS2:	97	0.050	96	98	2.49	97	99	2.08	70 - 130	70 - 130	
%SS3:	93	0.050	101	102	0.668	104	100	3.60	70 - 130	70 - 130	

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### BATCH 17867 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-001A	9/07/05 1:00 PM	9/07/05	9/10/05 1:25 AM	0509151-003A	9/07/05 1:00 PM	9/07/05	9/13/05 7:06 AM
0509151-005A	9/07/05 1:00 PM	9/07/05	9/10/05 2:50 AM	0509151-007A	9/07/05 1:00 PM	9/07/05	9/13/05 7:48 AM

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not enough sample to perform matrix spike and matrix spike duplicate.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.

Laboratory extraction solvents such as methylene chloride and acetone may occasionally appear in the method blank at low levels.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

## QC SUMMARY REPORT FOR 6020A

### BATCH 17895 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted	Date Analyzed
0509151-001A	9/07/05 1:00 PM	9/07/05	9/10/05 3:05 AM	0509151-003A	9/07/05 1:00 PM	9/07/05	9/10/05 3:14 AM
0509151-005A	9/07/05 1:00 PM	9/07/05	9/10/05 4:15 AM	0509151-005A	9/07/05 1:00 PM	9/07/05	9/10/05 4:24 AM
0509151-007A	9/07/05 1:00 PM	9/07/05	9/10/05 4:34 AM	0509151-009A	9/07/05 1:00 PM	9/07/05	9/10/05 4:43 AM
0509151-011A	9/07/05 1:00 PM	9/07/05	9/12/05 4:28 PM				

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not applicable to this method.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.

110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

### QC SUMMARY REPORT FOR 6020A

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: 6020A		Extract	tion: SW	3050B		Batch	BatchID: 17895 Spiked Sample ID: 0509135-00					
Analyte .	Sample	Spiked	MS	MSD	MS-MSD	Spiked	LCS	LCSD	LCS-LCSD	Acceptance	Criteria (%)	
	mg/Kg	mg/Kg	% Rec.	% Rec.	% RPD	mg/Kg	% Rec.	% Rec.	% RPD	MS / MSD	LCS / LCS	
Antimony	0.87	50	102	103	0.803	10	106	104	2.47	75 - 125	80 - 120	
Arsenic	3.7	50	99.3	110	9.63	10	105	104	1.15	75 - 125	80 - 120	
Barium	48	500	98.7	100	1.41	100	103	101	1.87	75 - 125	80 - 120	
Beryllium	ND	50	96.2	97.9	1.79	10	104	102	2.43	75 - 125	80 - 120	
Cadmium	ND	50	95.2	95.5	0.378	10	100	98	2.22	75 - 125	80 - 120	
Chromium	41	50	94.6	113	1.01	10	103	102	1.07	75 - 125	80 - 120	
Cobalt	7.4	50	93.8	94.9	0.970	10	99	98.8	0.202	75 - 125	80 - 120	
Соррег	17	50	96.6	111	: 10.2	10	104	102	1.65	75 - 125	80 - 120	
Lead	20	50	93.8	98	3.08	10	99.3	98.3	1.01	75 - 125	80 - 120	
Mercury	0.082	2.5	101	104	3.40	0.50	106	104	1.90	75 - 125	80 - 120	
Molybdenum	ND	50	93.2	94.2	1.11	10	96	94.7	1.36	75 - 125	80 - 120	
Nickel	26	50	97.7	115	10.7	10	106	104	1.71	75 - 125	80 - 120	
Selenium	ND	50	102	111	8.39	10	104	107	3.13	75 - 125	80 - 120	
Silver	ND	50	97.1	98.3	1.17	10	103	101	1.66	75 - 125	80 - 120	
Thallium	ND	50	94.2	96.9	2.80	10	95	94.2	0.846	75 - 125	80 - 120	
Vanadium	44	50	94.8	114	9.85	10	104	. 102	1.55	75 - 125	80 - 120	
Zinc	66	500	96.4	98.4	1.77	100	100	98.9	1.12	75 - 125	80 - 120	
%SS:	108	250	105	lil	5.36	250	106	104	2.03	70 - 130	70 - 130	

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not applicable to this method.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to High matrix or analyte content.

# **CHAIN-OF-CUSTODY RECORD**

Page 1 of 1

110 Second Avenue South, #D7 Pacheco, CA 94553-5560 (925) 798-1620

WorkOrder: 0509151

Bill to:

ClientID: BEO

EDF: NO

Report to:

Donavan Tom

**Basics Environmental** 

116 Glorietta Blvd.

TEL:

(925) 258-9099

(925) 258-9098

FAX: ProjectNo: 5105 E.8th ST. Oakland

PO:

Accounts Payable

**Basics Environmental** 

116 Glorietta Blvd. Orinda, CA 94563

Date Received: Date Printed:

Requested TAT:

09/07/2005

5 days

09/07/2005

Orinda, CA 94563 Requested Tests (See legend below) 5 10 11 12 13 14 15 Collection Date Hold Matrix Sample ID ClientSamplD 09/07/2005 Α Α Α 0509151-001 SB1 @ 4' Soil Α Α Α 09/07/2005 0509151-003 SB2 @ 4' Soil Α Α 0509151-005 SB3 @ 4' Soil 09/07/2005 Α 09/07/2005 Α 0509151-007 SB4 @ 4' Soil Α Α Α 09/07/2005 Α 0509151-009 SB5 @ 4' Soil Α 09/07/2005 SB6 @ 4' Soil 0509151-011

### Test Legend:

1	8260B_S
6	
11	

2	CAM17MS_S
7	
12	

3	G-MBTEX_S
8	
13	

4	
9	
14	

5	 	 	 	_
10	 	 	 	
15	 	 	 	

Prepared by: Rosa Venegas

### Comments:

NOTE: Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.

McCAMPBELL ANALYTICAL, INC. 110 2nd AVENUE SOUTH, #D7								7	יונים		AR						r C	US			Y 2	R	EC	COI									
Wah	site: <u>www.mc</u>	PACHE	CO, CA 94	1553-55	60 .i			11						1	UF	CIN .	AK	υt	INL	) T	IM	E		≓ عباتا	-		Æ HR		48 F		77	a HR	5 DAY
Telephor	ie: (925) 798	-1620	<u>i.com</u> En	iant ma					om 98-1	622				EI	DF I	Regi	aire	d? (	Coel	t (ľ	Vori	mal)								No		ш	JUNIN
Report To: Dax	JAVAN	(6W)_		Bill To	:								_						A	nal	ysis	Re	Auc:	1						O	ther	Т	Comments
Company: BASIC	S ENVIPO	NME	MAL,	INC																										$\Box$	$\neg \uparrow$	_	<del></del>
6551	29 51, 4	十12心					~ · · · ·							3E		<u></u>										ا ا	ı	-				•	Filter Samples
DAKL	AND C	A 9												MTI	/55	E&F/B&F)	8.1)									831	7						for Metals
Tele: (50) &	34-909	9		Fax: (			<u> ૭૩</u>	4-	40	96	<u>-</u>			8015),MTBE	/K/MV/	E&	Total Petroleum Hydrocarbons (418.1)									625/8270/8310	14				,		analysis:
Project #: Project Location:	500 0	2)13		Projec	t Nan	ne:							_	*	T	Total Petroleum Oil & Grease (5520	Sons		BTEX ONLY (EPA 602 / 8020)		>					/ 82	l.	<u> </u>				-	Yes / No
Sampler Signature		- 0 -	>١.	CAL		₩.	·					_	-	/8020	4/4/	ase (	cari		18/7		Z	ŀ	1	-		625	602	905(	<u> </u>			-	
Sampler Signatur	5. 30 1.					<del>,                                    </del>				1 8	иет	HO	<del></del>	(602		Gre	ydro	77	.09		B's		!	( နွ	٥	PA	107	0	09/			İ	
	•	SAM.	PLING	] s	ers	L	MA	rri	X	PR	ESE	RV	ED	Gas	801	3) I.C	H H	08/	EPA		2	_	1	180	827	by E	9) (	99	6.0	i		ł	
SAMPLE ID				Containers	Containers		İ							H as	TPH as Diesel (8015)	E	leur	EPA 601 / 8010 / 8021	۲ (	EPA 608 / 8081	EPA 608 / 8082 PCB's ONLY	EPA 8140 / 8141	EPA 8150 / 8151	EPA 524.2 / 624 8260	EPA 525 / 625 / 8270	PAH's / PNA's by EPA	CAM-17 Metals (6010 / 6020)	LUFT 5 Metals (6010 / 6020)	Lead (200.8 / 200.9 / 6010)			ĺ	
(Field Point Name)	LOCATION	Date	Time	ita	Con	_			. Lu					TPH	Die	trole	etro	11/8	ONI	8/8	% %	\$	50	5	5/6	NA /	7.M	Me	00.8	i [		-	
		Date	1 fine	Cor	Type	Water	Soil	Air	the the	ICE	HCL	HNO,	ther	BTEX &	H a	al Pe	tal P	A 6(	ΕX	A 60	A 60	A 81	A 81	A 52	A 52	H,s	<u>-</u>	FT (	, D				
			<u> </u>	#	T	M	S	Air	ā Ö	≌	Ä	Ξ	Ö	TE.	TP	Tot	Ę.	EP	BT	EP.	EP	ם	EP	EP	EP	P.	CA	LU	Le	.	}	İ	
5B1241		9/7/05	IPM				X			X					X									X			X		$\sqcap$		$\top$	T	
531 681		1	1				7			7			$\neg$		7									7			7					7	1017
SB2 641		(					7	1		T)							- :							7			7				1	_	
SB2 = e1							$\mathbf{I}$			T		T			$\Box$									/1				_			1	1	JOLD
5B3C41			7				7			17					7			$\neg$				_		7	.	-1	7					+	
SB3 CB1							(		1	$\Pi$		$\neg$			71									1			1					1	0 -7
SB4 e41												1												$\mathcal{A}$			$\dagger \dagger$			_	$\top$	- ['	<u>-                                    </u>
504C81							(			15		$\dashv$	$\neg$		71				$\neg$					$\top$			$\forall$				-	V	1027
5BJ e41	·					$\exists$	1	-	_			7	7		)			_						-}		-	1		-			╁	
50500		1					1		<del> </del>			1	_		$f \dashv$				-					-}			╂┤					-	PULD
SB6041	···	to	V				\$	+	+	4		+	$\dashv$		l -				一十					7			)					- -	<u> </u>
, SB DA E'		9/7/05					<b>Y</b>  -		1-		$\dashv$				7				$\dashv$					V		-	0				+	19	~Lp
Relinquished By:			Time:	Recei	ved By			$\hbar$	Д	11		- {	十	ICE	/t"						1				CON	имн	NTS	L S:	<u> </u>			111	
120	`	9/7/05	475pm	17	راسري	[/	v( )	IU	W	/			1	GO	op (	COM	DITI E AI														•		
Relinquished By:		Date:	Time:	Recei	ved By	<u> </u>	_/	ــــــــــــــــــــــــــــــــــــــ					$\dashv$	DEC	CHL	ORI	NAT	EĐ I	NLA			/											
	,				-												TE ( ) IN			NER	.S_ <u>_</u>		-										
Dation and a D			day	<u></u>			·						_						AS	 	1	ME	TAI	e l .	റസ	ED.			•				j
Relinquished By:		Date:	Time:	Recei	чеа Ву	:											rion	!				pH<		,	J. 11	en.		-					
																	:le w					<b>.</b>		_						<u>.</u>			
	1													GΚ	UÜ	IYU	Y	YAS	IE	Ţ	JKI.	NK.	uNG	1	Ά	KE.	ATI	IUN	AL	E	FFLU	UŁľ	41.



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560
Telephone: 925-798-1620 Fax: 925-798-1622
Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environmental	Client Project ID: 5105 E.8th ST. Oakland	Date Sampled: 09/07/05
116 Glorietta Blvd.		Date Received: 09/07/05
Orinda, CA 94563	Client Contact: Donavan Tom	Date Reported: 09/13/05
Official, CA 74303	Client P.O.:	Date Completed: 09/19/05

WorkOrder: 0509151

September 19, 2005

### Dear Donavan:

### Enclosed are:

- 1). the results of 1 analyzed sample from your 5105 E.8th ST. Oakland project,
- 2). a QC report for the above sample
- 3). a copy of the chain of custody, and
- 4). a bill for analytical services.

All analyses were completed satisfactorily and all QC samples were found to be within our control limits. If you have any questions please contact me. McCampbell Analytical Laboratories strives for excellence in quality, service and cost. Thank you for your business and I look forward to working with you again.

Angela Rydelius, Lab Manager



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560 Telephone: 925-798-1620 Fax: 925-798-1622 Website: www.mccampbell.com E-mail: main@mccampbell.com

Basics Environm	ental	Client Pro	ject ID: 5105	E.8th ST. Oakland	Date Sampled: 09/07/05							
116 Glorietta Bl	vd.				Date Received: 09/0	7/05						
0:1 0:0:5:5		Client Co	ntact: Donava	n Tom	Date Extracted: 09/1	4/05-09/16/0	05					
Orinda, CA 9456		Client P.C	).:		Date Analyzed: 09/19/05							
Extraction method: CA	Title 22			l by ICP* methods: SW6010C		Work Order:	0509151					
Lab ID	Client ID	Matrix	Extraction		Lead	DF	% SS					
0509151-005A	SB3 @ 4'	S	STLC		26	l l	N/A					
					<del></del>	 						
· · · · · · · · · · · · · · · · · · ·			·									
			····									
<del></del>						<del></del>	<del> </del>					
			<del> </del>			<del></del>	ļ					
:		1			<u> </u>		<u> </u>					
		<u> </u>										
:	<del></del>	i i										
		ŗ			·	:	·					
Reporting L	imit for DF =1;	w	TTLC		NA	n	ıg/L					
	ot detected at or reporting limit	S	STLC		0.2		ig/L					

soil/sludge/solid samples in mg/kg, wipe samples in µg/wipe, filter samples in µg/filter.

# means surrogate diluted out of range; ND means not detected above the reporting limit; N/A means not applicable to this sample or instrument.

i) aqueous sample containing greater than ~1 vol. % sediment; for DISSOLVED metals, this sample has been preserved prior to filtration; for TTLC metals, a representative sediment-water mixture was digested; j) reporting limit raised due to insufficient sample amount; k) reporting limit raised due to matrix interference; m) estimated value due to low/high surrrogate recovery, caused by matrix interference; n) results are reported on a dry weight basis; p) see attached narrative.

Angela Rydelius, Lab Manager



110 2nd Avenue South, #D7, Pacheco, CA 94553-5560
Telephone: 925-798-1620 Fax: 925-798-1622
Website: www.mccampbell.com E-mail: main@mccampbell.com

### QC SUMMARY REPORT FOR SW6010C

W.O. Sample Matrix: Soil

QC Matrix: Soil

WorkOrder: 0509151

EPA Method: SW6010C	E	xtraction:	CA Title	22	Batc	hID: 18013	}	Spiked Sample ID: N/A					
Analyte	Sample	Spiked	MS	MSD	MS-MSD	LCS	LCSD	LCS-LCSD	Acceptance	: Criteria (%)			
	mg/L	mg/L	% Rec.	% Rec.	% RPD	% Rec.	% Rec.	% RPD	MS / MSD	LCS / LCSD			
Lead	N/A	1	N/A	N/A	N/A	104	110	5.68	N/A	85 - 115			

All target compounds in the Method Blank of this extraction batch were ND less than the method RL with the following exceptions:

NONE

### BATCH 18013 SUMMARY

Sample ID	Date Sampled	Date Extracted	Date Analyzed	Sample ID	Date Sampled	Date Extracted .	Date Analyzed
0509151-005A	9/07/05 1:00 PM	9/14/05	9/19/05 12:27 PM				

MS = Matrix Spike; MSD = Matrix Spike Duplicate; LCS = Laboratory Control Sample; LCSD = Laboratory Control Sample Duplicate; RPD = Relative Percent Deviation.

% Recovery = 100 \* (MS-Sample) / (Amount Spiked); RPD = 100 \* (MS - MSD) / ((MS + MSD) / 2).

MS / MSD spike recoveries and / or %RPD may fall outside of laboratory acceptance criteria due to one or more of the following reasons: a) the sample is inhomogenous AND contains significant concentrations of analyte relative to the amount spiked, or b) the spiked sample's matrix interferes with the spike recovery.

N/A = not applicable to this method.

NR = analyte concentration in sample exceeds spike amount for soil matrix or exceeds 2x spike amount for water matrix or sample diluted due to high matrix or analyte content.

DHS Certification No. 1644



110 Second Avenue South, #D7 Pacheco, CA 94553-5560 (925) 798-1620

# **CHAIN-OF-CUSTODY RECORD**

Page 1 of 1

WorkOrder: 0509151

ClientID: BEO

EDF: NO

Report to:

Donavan Tom **Basics Environmental** 116 Glorietta Blvd.

Orinda, CA 94563

TEL: FAX:

(925) 258-9099

(925) 258-9098 ProjectNo: 5105 E.8th ST. Oakland

PO:

Bill to:

Accounts Payable

**Basics Environmental** 116 Glorietta Blvd.

Orinda, CA 94563

Requested TAT:

Date Printed:

Date Received: 09/07/2005

Date Add-On:

09/14/2005

5 days

09/14/2005

									· · · · · · · - ·	Reques	ted Te	ests (	See le	gend	below)					
Sample ID	ClientSampID	Matrix	Collection Date	Hold	1	2	.3	4	5	6	7		8	9	10	11	12	13	14	15
0509151-005	SB3 @ 4'	Soil	9/7/05 1:00:00 PM		_A				1	T	T	_1_		l			1	1 .		

### Test Legend:

1 PB_STLC_Soil	2
6	7
11	12

3	
8	
13	

4	5
9	10
14	15

5	
10	
15	

Prepared by: Rosa Venegas

Comments:

Pb Stlc added 9/14/05 per fax 5 day

NOTE: Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.

McCAMPBELL ANALYTICAL, INC.										CHAIN OF CUSTODY RECORD																					
110 2 <sup>™</sup> AVENUE SOUTH, #D7										1	TURN AROUND TIME Q Q Q																				
PACHECO, CA 94553-5560  Website: www.mccampbell.com Email: main@mccampbell.com											RUSH 24 HR 48 HR 72 HR 5 D. EDF Required? Coelt (Normal) No ) Write Ou (DW) No												IR 5 D								
Telephone: (925) 798-1620 Fax: (925) 798-1622											$\dashv$																				
Report To: Denay Tow Bill To:												_{	1					A	nal	ysis	Rec	ues	<u>'</u>				_		0	ther	Comments
Company: BASICS ENVIRONMENTAL, INC													İ		}	İ															Filter -
CAKLAND CA 94607 E-Mail: Dasics Cad. com													186	N.	(SE)										310	1			7		Samples
Tele: (510) 834-9099 Fax: (510) 834-9098												8015)/MTBE	3	& F/B	8.								1	8/0	7716		<u>.</u>	4	'	for Metals analysis:	
Tele: (5h) 834-9099       Fax: (5h) 834-9098         Project #:       Project Name:													801	1/11/35	Total Petroleum Oil & Grease (5520 E&F/B&F)	Total Petroleum Hydrocarbons (418.1)		6							625 / 8270 / 8310	•			52		Yes / No
Project Location: 5105 E. 812 ST. CALLAND												+ 021	8/1	e (55	odr		802		N.		,			25 /	CAM-17 Metals (6010 / 6020)	LUFT 5 Metals (6010 / 6020)	<u> </u>	1/6	•	1	
Sampler Signature:												02/80	3	reas	rocs	_	02 /		O S		{	<u>.</u>		9 V	9/0	)9/	601	1 1		<u>,</u>	
· · ·	SAMPLING & MATRIX METHOD										Gas (602/8020	TPH as Diesel (8015)	8	Hyd	EPA 601 / 8010 / 8021	PA (		3			8260	270	y Ei	69	901	Lead (200.8 / 200.9 / 6010)	\$	1			
	JAMI	JAMI DING		Type Containers	171711117					PRESERVED			S	1 (8(	ő	E I	10 /	BTEX ONLY (EPA 602 / 8020)	18	EPA 608 / 8082 PCB's ONLY	141	151	EPA 524.2 / 624	EPA 525 / 625 / 8270	PAH's / PNA's by EPA	ais	sls (	200	pappe		
SAMPLE ID LOCATION	•		Containers	nta								1	H d	iese	leun	role	08/	\Z\	EPA 608 / 8081	/ 80	EPA 8140 / 8141	EPA 8150 / 8151	2 / 6	7 62	N.	Met	Met	0.8 /	1 1		1
(Field Point Name) LOCATION	Date	Time	nta	ပိ	늄	-	8	ᇷ			5	ia ai	7.	as D	Petro	Pet	601	lO x	809	809	814	815	524	525	.s / I	1.7	1.5	(20	웅	ľ	
1				ype	Water	Soil	Air		ICE		ž	到	втех & трн	ЪН	otal	Ota	PA	TE	3PA	)PA	βPA	3PA	PA	3PA	AH	A A	15	ead	يم		İ
			#				1, 0	1	+			$\dashv$			-												├	_	-		<del></del>
5B1 e4	9/7/5	1814				X		$\perp$	X			$\dashv$		X								·	X			X	ļ	<u> </u>			13 -1 2-
5131 68'	_/_					4			ΙÇ					(_												Κ.					Hora
SB2 64'						4			12											<u> </u>			)			1				_	
582 4 81									$\perp$					)									$\triangle$		·						Hora
5B3C41	l <i>)</i>					$\mathcal{L}$			Ц														)			$\coprod$	<u> </u>	_	S		
SB3 CB'									$\prod$		ļ															$\coprod$					HOLD
589 241						$\prod$			$\prod$					$  \setminus  $																	
SP4C81						11			15					[ ]							T										40'LD
5BJe41					$\Box$	1	_		11																	17					
SDSC EI	<del>                                     </del>	<del>                                     </del>	<b></b> -			+	-		$\dagger \dagger$														$\rightarrow$		····						HULD
SB1041	2	V	<del> </del>			V		+	V					t									-			<i> </i>	<del>                                     </del>	_			
SO A GI	9/7/					<u> </u>			+					7						-	<u> </u>		V			V	$\vdash$				H-1-12
Relinguished By	Date:	Time:	Rece	ived B	V: -		+		1	<u> </u>		H	IC	E/t°_				لــــا	_	!	L	L		co	MM	ENT	`S:	<u> </u>	L		1/1 - 7
The state of the s	19/1	<b>]</b> 2.	X	11 ~/	$I_{I}$	Ň١	V()	W	✓			ļ	$\mathbf{GC}$	OD AD S	CON				_											•	
	77/3	4.15p.	1 1 0 ° 1/2										DE	CHI.	ORI.	[AA]	ED	IN L			_/										
Relinquished By: Date: Time: Received By:										- 1		PRO ESE					INE	RS	_	_											
													- ••			_ ••••				ا م		nan Ar	ا ی	A201	a to to	,					
Relinquished By:	Date:	Time:	Rece	ived B	у:								PR	ESE	RVA	TIO		OAS	10	œG .	_pH		L3	U I I	1LK	· 					
											*P	lease	e cir	cle	wate						_		00.	n . ~	or		, ,	י אראיקונים	HONSTO		
	1	1	1										CI	ROL	IND	,	WΑ	STE		DR.	INK	IN(	;	RE	CRI	EA 1	[10]	NΑΙ	և յ	ヒドドレ	UENT