

Sacramento, California 95818

September 16, 2011

### **RECEIVED**

10:51 am, Sep 19, 2011 Alameda County Environmental Health

Ms. Barbara Jakub Alameda County Health Care Services Agency 1131 Harbor Bay Parkway Alameda, California 94502-6577

Re: Quarterly Monitoring Report – Third Quarter 2011
76 Service Station No. 1028
5300 Broadway
Oakland, California
Alameda County LOP Case #: RO0002967
Antea Group Project No. I40251028

Dear Ms. Jakub:

I declare under penalty of perjury that to the best of my knowledge the information and/or recommendations contained in the attached report is/are true and correct.

If you have any questions or need additional information, please call Ms. Lia Holden at (408) 826-1863.

Sincerely,

Eric G. Hetrick Site Manager

1.A. =

Risk Management & Remediation



# **Quarterly Monitoring Report Third Quarter 2011**

76 Service Station No. 1028
5300 Broadway
Oakland, California
Alameda County Health Care Services Agency
File Case #: RO0002967

Antea Group Project No. 140251028 September 16, 2011

Prepared for: Barbara Jakub

Hazardous Materials Specialist Alameda County Health Care Services Agency 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502-6577 Prepared by: Antea<sup>TM</sup>Group 312 Piercy Road San Jose, CA 95138 +1 800 477 7411





## **Quarterly Monitoring Report Third Quarter 2011**

76 Service Station No. 1028 5300 Broadway, Oakland, California Alameda County Health Care Services Agency Case #: RO0002967

Antea Group Project No. 140251028 September 16, 2011

### Prepared for:

### **Barbara Jakub**

Hazardous Materials Specialist Alameda County Health Care Services Agency 1131 Harbor Bay Parkway, Suite 250 Alameda, California 94502-6577

Prepared by: Antea<sup>TM</sup>Group 312 Piercy Road San Jose, CA 95138 +1 800 477 7411



### **Table of Contents**

1.0	SITE DESCRIPTION	1
1.1	Work Performed in the Third Quarter 2011	1
1.2	Work Proposed for the Fourth Quarter 2011	1
• •	·	
2.0	CURRENT PROJECT STATUS	
2.1	Regulatory Correspondence	2
2.2	Groundwater Monitoring	2
2.2		2
2.2		3
2.2		3
2.2		
2.2		
3.0	CONCLUSIONS AND RECOMMENDATIONS	4
4.0	LIMITATIONS	_
7.0		_

### **Tables**

Table 1 Current Groundwater Gauging and Analytical DataTable 2 Historic Groundwater Gauging and Analytical Data

### **Figures**

Figure 1 Site Location Map

Figure 2 Site Map

Figure 3 Groundwater Elevation Map – August 8, 2011
Figure 4 Groundwater Concentration Map – August 8, 2011

### **Appendices**

Appendix A Summary of Previous Investigations

Appendix B Blaine Tech Services' Standard Operating Procedures

Appendix C Blaine Tech Services' Field Notes from Groundwater Monitoring and Sampling

Appendix D Laboratory Analytical Report and Validation Form



## **Quarterly Monitoring Report Third Quarter 2011**

76 Service Station No. 1028 5300 Broadway, Oakland, California Alameda County Health Care Services Agency Case# RO0002967

#### 1.0 SITE DESCRIPTION

The subject site is an active service station located on the northeast corner of the intersection of Broadway and Broadway Terrace in Oakland, California (Figure 1). Aboveground facilities consist of two dispenser islands and repair shop. Two gasoline underground storage tanks (USTs) share a common pit located in the southwest corner of the property. One waste oil tank is located in front of the station building (Figure 2). The site is bordered to the north and east by residential buildings. Commercial properties are located to the west of the site across Broadway and to the south across Broadway Terrace.

### 1.1 Work Performed in the Third Quarter 2011

- Blaine Tech Services (Blaine Tech) conducted a quarterly monitoring event.
- Antea Group prepared and submitted a Quarterly Monitoring Report.

### 1.2 Work Proposed for the Fourth Quarter 2011

- Antea Group will submit the Quarterly Monitoring Report, Third Quarter 2011 (contained herein) to the Alameda County Department of Environmental Health (ACEH).
- Antea Group to continue communications with Alameda County Environmental Health Department (ACEH) to obtain case closure.
- Pending regulatory concurrence, Antea Group will cease monitoring and sampling activities.

### 2.0 CURRENT PROJECT STATUS

Current phase of project:	Case Closure Evaluation
Local Oversight Program (LOP) -	Alameda County Environmental Health
Lead Agency for Cleanup Oversight:	Department (ACEH)
Secondary Agency(s):	San Francisco Bay Regional Water Quality Control
	Board
Monitoring well gauging schedule:	All wells gauged quarterly
Monitoring well sampling schedule:	Quarterly: MW-1, MW-2, MW-3
Total number of monitoring/remediation wells:	Three monitoring wells (MW-1, MW-2, MW-3)
Total depths of wells (feet below ground surface):	All wells are 12 feet deep
Wells with historical measurable LNAPL	None
(light non-aqueous phase liquid):	



Generalized site geology:	Upper 1 to 5 feet of subsurface is weathered shale and clay deposits with cobbles of chert and shale. Shale bedrock below to total depth explored.
Historic depth to water range (feet below top of casing (btoc):	4.72 (Current well MW-2 on 8/8/2011) to 1.16 (current well MW-1 on 12/21/2011)
Historic groundwater elevation range (ft above mean sea level):	172.88 (MW-3 on 8/8/2011) to 181.36 (MW-2 on 4/4/2011)
Nearby Sensitive Receptors:	None (Delta 2008) (Appendix A)
Current remediation technique	None

### 2.1 Regulatory Correspondence

No correspondence was sent or received in the current quarter.

### 2.2 Groundwater Monitoring

During the third quarter 2011 groundwater monitoring and sampling event on August 8<sup>th</sup>, 2011, all wells were gauged and sampled by subcontractor Blaine Tech per standard sampling protocol (**Appendix B**). Copies of Blaine Tech's field data sheets are included in **Appendix C**. The recent gauging and sampling data are summarized below.

Well gauging and sampling date:	August 8, 2011
Wells gauged:	MW-1, MW-2, MW-3
Wells sampled:	MW-1, MW-2, MW-3
Purge Method:	3 casing volumes via electric, submersible pump
Sample collection method:	Disposable bailer
Groundwater field parameters measured:	Temperature, pH, Conductivity, Oxidation-reduction potential (ORP), Dissolved Oxygen (DO),
Wells with measurable LNAPL:	None
	Min: 2.5 feet (MW-1)
Current depth to water range (ft btoc):	Max: 4.72 feet (MW-2)
	Min: 172.88 (MW-3)
Current groundwater elevation range (ft):	Max: 176.64 (MW-2)
Change in groundwater elevation from previous event (average change for all	
wells)	0.57 foot decrease from April 2011 to August 2011.
Groundwater flow direction and gradient:	0.048 feet per foot to the Northwest ( <b>Figure 3</b> )

### 2.2.1 Groundwater Flow Gradient and Directional Trends

In the third quarter 2011, depth to water in wells varied from 2.50 feet btoc in MW-1 to 4.72 feet in MW-2, and groundwater flow direction was to northwest (**Figure 3**). Depths to water and flow directions reported in the

2 www.anteagroup.com



current quarter are consistent with those reported during the April 2011 sampling event, and also with historic depths to water and flow directions reported prior to the site's closure in 1994.

### 2.2.2 Groundwater Quality Data

Groundwater samples collected during the third quarter 2011 were submitted under chain-of-custody protocol to Pace Analytical Services, Inc. (PACE), a state of California Environmental Laboratory Accreditation Program (ELAP) certified laboratory (Certification No. 01153CA). The complete analytical report is included in **Appendix D**. Groundwater samples were analyzed for the following:

- Gasoline Range Organics (GRO) by Environmental Protection Agency (EPA) Method 8260B;
- Benzene, toluene, ethylbenzene, xylenes (BTEX Compounds) by EPA Method 8260B.
- Fuel oxygenates: methyl tertiary butyl ether (MTBE), di-isopropyl ether (DIPE), tertiary amyl methyl ether (TAME), tertiary butyl alcohol (TBA), ethyl tertiary butyl ether (ETBE) and ethanol by EPA Method 8260B.
- Lead scavengers: 1, 2-dichloroethane (1, 2-DCA) and ethylene dibromide (EDB) by EPA Method 8260B.

Current groundwater analytical results are presented in **Table 1** and historic groundwater monitoring results are presented in **Table 2**. A groundwater concentration map is included as **Figure 4**. Only MTBE was reported above laboratory reporting limits, at a concentration of  $1.2 \mu g/l$  in MW-3.

No other analytes were reported above laboratory reporting limits in any of the site wells.

### 2.2.3 Groundwater Contaminant Trends

During the site's short monitoring period from 1990 to 1991, concentrations decreased to below detection limits after the first monitoring event. Analyte concentrations reported by ATC in their 2007 investigation were elevated, and results of the December 2010, February 2011, April 2011 and August 2011 sampling events confirm that the reported concentrations related to the 2007 investigation were not representative of actual groundwater conditions. Data from recent sampling events show that conditions are similar to those reported during the site's closure in 1994.

Contaminants onsite are generally located in the lower, northwest portion of the site near MW-3 and MW-1; however, MTBE (the only detected analyte in the current quarter) was reported below the ESL of 5  $\mu$ g/l.

### 2.2.3 Waste Disposal Summary

Purge water generated during well purging/sampling and equipment cleaning in the third quarter 2011 event was transported to Blaine Tech's bulk facility in San Jose, California. After the batching process, the wastewater was transported to Seaport Environmental in Redwood City, California for disposal. Blaine Tech's standard operating procedures for purge water handling are included in **Appendix B**.



### 2.2.4 Quality Assurance/ Quality Control

Antea Group's QA/QC measures included a detailed QA/QC data validation check on the Pace Laboratory analytical results for the August 2011 sampling event. Antea Group's laboratory data validation checklist and the Pace laboratory report are included in **Appendix D**.

Laboratory QA/QC Performed?	Yes (validated by Antea Group)
	M5: A matrix spike/matrix spike duplicate was not
	performed for this batch due to insufficient sample
	volume. Laboratory control samples were used in lieu
	of MS/MSDS.
	B-: Analyte detected in method blank but was not
	detected in the associated samples. Since analytes
	were not reported in the sample, this does not affect
Laboratory Data Qualifiers:	the data.
Are the data valid for their intended purpose?	Yes, the data are valid.

Based on a review of the laboratory's analytical report, including their QA/QC procedures and those implemented by Antea Group, we conclude that the laboratory data obtained during this groundwater sampling event are valid for their intended purpose.

### 3.0 CONCLUSIONS AND RECOMMENDATIONS

- Antea Group and subcontractors conducted a quarterly monitoring event on August 8th, 2011.
- Groundwater flow was directed to the Northwest at a hydraulic gradient of 0.048 feet per foot.
- Only MTBE was reported above laboratory reporting limits, at a concentration below the ESL.
- Antea Group submitted a Soil and Groundwater Investigation Report and Request for Case Closure dated
  February 22<sup>nd</sup>, 2011. The report documented the installation of the site's three monitoring wells and
  recommended case closure based on the site conditions and closure criteria.
- Concentrations reported during the site's environmental case closure in 1994 are generally consistent
  with data associated with the well installation investigation and with the current quarter's groundwater
  results. Antea Group believes that elevated concentrations reported during the 2007 ATC investigation
  were false positives, not representative of actual groundwater conditions, and that the site meets the
  criteria for case closure.
- The third quarter 2011 marks four consecutive quarters of groundwater monitoring and five total groundwater sampling events since the site's wells were installed.
- Antea Group continues to recommend case closure by the ACEH.



 Antea Group requests that monitoring and sampling is allowed to cease while the agency reviews the case for closure.

### 4.0 LIMITATIONS

The findings contained in this report represent Antea Group's professional opinions based upon the currently available information and are arrived at in accordance with currently acceptable professional standards. For any reports cited that were not generated by Antea USA, Inc., the data from those reports are used "as is" and is assumed to be accurate. Antea USA, Inc does not guarantee the accuracy of this data for the referenced work performed nor the inferences or conclusions stated in these reports. This report is based upon a specific scope of work requested by the client. The Contract between Antea Group and its client outlines the scope of work, and only those tasks specifically authorized by that contract or outlined in this report were performed. This report is intended only for the use of Antea Group's Client and anyone else specifically listed on this report. Antea Group will not and cannot be liable for unauthorized reliance by any other third party. Other than as contained in this paragraph, Antea Group makes no express or implied warranty as to the contents of this report.

LIA HOLDEN

No. 8584

**Nadine Periat** 

**Project Professional** 

Reviewed by:

Lia Holden, P.G. No. 8584

Geologist - Project Manager



### **Tables**

Table 1	Current Groundwater Gauging and Analytical Data
Table 2	Historic Groundwater Gauging and Analytical Data

### TABLE 1

## CURRENT GROUNDWATER GAUGING AND ANALYTICAL DATA 76 Service Station No. 1028 5300 BROADWAY AVE

OAKLAND, CALIFORNIA



		GR	OUNDWAT	ER GAUGING D	ATA							GROUNDWATI	R ANALYTICA	L DATA					
Well I.D.	Date	TOC Elevation (ft)	-		Water Elevation* (ft)	DRO (ug/L)	GRO (ug/L)	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	Total Xylenes (ug/L)	MTBE (ug/L)	DIPE (ug/L)	ETBE (ug/L)	TAME (ug/L)	TBA (ug/L)	Ethanol (ug/L)	1,2- Dibromoethane (EDB) (ug/L)	1,2- Dichloroethane (ug/L)
MW-1	8/8/2011	176.62	2.50	NP	174.12	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
MW-2	8/8/2011	181.36	4.72	NP	176.64	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
MW-3	8/8/2011	176.40	3.52	NP	172.88	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	1.2	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0

**Gauging Notes:** 

TOC - Top of Casing

ft - Feet

NP - LNAPL not present

LNAPL - Light non-aqueous phase liquid

\* - Corrected for LNAPL if present (assumes LNAPL specific gravity = 0.75)

-- - No information available

Analytical Notes:

< - Not detected at or above indicated laboratory reporting limit

ug/L - micrograms/liter

DRO- diesel range organics

GRO- gasoline range organics

MTBE- Methyl tertiary-butyl ether

TBA- Tertiary-butyl alcohol


DIPE- Di-isopropyl ether

ETBE- Ethyl tertiary-butyl ether

TAME- Tertiary-amyl methyl ether

### TABLE 2

### HISTORICAL GROUNDWATER GAUGING AND ANALYTICAL DATA 76 Service Station No. 1028





		GROUNDWATER GAUGING DATA					GROUNDWATER ANALYTICAL DATA												
Well I.D.	Date	TOC Elevation (ft)	Depth to Water (ft)	LNAPL Thickness (ft)	Water Elevation* (ft)	DRO (ug/L)	GRO (ug/L)	Benzene (ug/L)	Toluene (ug/L)	Ethylbenzene (ug/L)	Total Xylenes (ug/L)	MTBE (ug/L)	DIPE (ug/L)	ETBE (ug/L)	TAME (ug/L)	TBA (ug/L)	Ethanol (ug/L)	1,2- Dibromoethane (EDB) (ug/L)	1,2- Dichloroethane (ug/L)
	12/21/2010	176.62	1.16	NP	175.46	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
MW-1	2/17/2011	176.62	1.29	NP	175.33	56.8	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
IVIVV-T	4/4/2011	176.62	1.53	NP	175.09	<50.0	119	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
	8/8/2011	176.62	2.50	NP	174.12	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
	12/21/2010	181.36	4.19	NP	177.17	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
MW-2	2/17/2011	181.36	4.10	NP	177.26	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
10100-2	4/4/2011	181.36	4.35	NP	177.01	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
	8/8/2011	181.36	4.72	NP	176.64	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	<0.50	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
	12/21/2010	176.40	2.08	NP	174.32	74.4	<50.0	<0.50	<0.50	<0.50	<1.5	0.87	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
MW-3	2/17/2011	176.40	2.20	NP	174.20	<50.0	52.1	<0.50	<0.50	<0.50	<1.5	2.5	<0.50	<0.50	<0.50	7.5	<250	<1.0	<1.0
10100-3	4/4/2011	176.40	3.15	NP	173.25	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	0.92	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0
	8/8/2011	176.40	3.52	NP	172.88	<50.0	<50.0	<0.50	<0.50	<0.50	<1.5	1.2	<0.50	<0.50	<0.50	<5.0	<250	<1.0	<1.0

Gauging Notes:

TOC - Top of Casing

ft - Feet

NP - LNAPL not present

LNAPL - Light non-aqueous phase liquid
\* - Corrected for LNAPL if present (assumes LNAPL specific gravity = 0.75)

-- - No information available

Analytical Notes:

< - Not detected at or above indicated laboratory reporting limit

ug/L - micrograms/liter

DRO- diesel range organics

GRO- gasoline range organics

MTBE- Methyl tertiary-butyl ether

TBA- Tertiary-butyl alcohol

DIPE- Di-isopropyl ether


ETBE- Ethyl tertiary-butyl ether


TAME- Tertiary-amyl methyl ether



### **Figures**

Figure 1	Site Location Map
Figure 2	Site Map
Figure 3	Groundwater Elevation Map – August 8, 2011
Figure 4	Groundwater Concentration Map – August 8, 2011





- APPROXIMATE PROPERTY BOUNDARY

 $ATC-5 \rightarrow$  SOIL BORING LOCATION (ATC 2007)

MW−3 


MONITORING WELL LOCATION (DELTA 2010)


B-3 SOIL BORING LOCATION (DELTA 2010)

76 STATION NO. 1028 5300 BROADWAY OAKLAND, CALIFORNIA

PROJECT NO.	PREPARED BY	DRAWN BY
140251028	NP	KYM
DATE	REVIEWED BY	FILE NAME
07/07/10	LH	1028-Site







### LEGEND:

ATC-5 → SOIL BORING (ATC 2007)

MW−3 

MONITORING WELL (DELTA 2010)

B-3 ● SOIL BORING (DELTA 2010)

(172.88) GROUNDWATER ELEVATON IN FEET ABOVE MEAN SEA LEVEL (ft/msl)

GROUNDWATER ELEVATION CONTOUR LINE - 173 — (ft/msl) (CONTOUR INTERVAL: 1 ft)


GROUNDWATER FLOW DIRECTION AND HYDRAULIC GRADIENT (ft/ft)

SITE MAP ADAPTED FROM A SURVEY BY MIDCOAST ENGINEERS, DECEMBER 2010 AND A SITE MAP BY ATC ASSOCIATES, 2007.

FIGURE 3
GROUNDWATER ELEVATION MAP
AUGUST 8, 2011
76 STATION NO. 1028
5300 BROADWAY
OAKLAND, CALIFORNIA

PROJECT NO.	PREPARED BY	DRAWN BY	Г
140251028	NaP	JH	
DATE	REVIEWED BY	FILE NAME	
09/08/11	LH	1028-Site	





09/08/11

CONCENTRATIONS IN MICROGRAMS PER LITER (µg/L).

LH

1028-Site

**antea**group



### Appendix A

**Summary of Previous Site Investigations** 

#### **Summary of Previous Site Investigations**

1989 – Soil samples were collected by Kaprealian Engineering, Inc. (KEI) following the removal of two fuel USTs, their associated piping, and a waste-oil UST. Ground water was encountered in the tank pit at a depth of approximately 7 to 8 feet. Analytical results from the soil samples showed total petroleum hydrocarbons as gasoline (TPH-G) ranged from non-detectable above laboratory reporting limits to 22 parts per million (ppm) in the fuel UST excavation, and from non-detectable to 5.7 ppm in the waste-oil UST excavation. All total petroleum hydrocarbons as diesel (TPH-D) concentrations were less than 10 ppm and all total oil and grease (TOG) concentrations in the waste-oil UST excavation were less than 50 ppm (KEI January 1990).

1990 – Three two-inch diameter monitoring wells (MW-1 through MW-3) were installed at the site. TPH-G was not detected above the laboratory reporting limit in soil samples from well borings. Benzene was reported in the soil samples at concentrations ranging from non-detectable to 0.0066 ppm. TPH-G, benzene, toluene, ethylbenzene, and total xylenes (BTEX) were not detected above the laboratory reporting limits in groundwater samples collected from MW-1 and MW-2. TPH-G and benzene were reported in the groundwater sample from MW-3 at concentrations of 590 parts per billion (ppb) and 2.5 ppb, respectively. TPH-D was reported in monitoring well MW-1 at a concentration of 5.4 ppb (KEI May 1990).

1998 – Environmental Resolutions, Inc. (ERI), oversaw the removal of product lines and dispensers. Product lines consisted of double-walled fiberglass piping and showed no visible evidence of damage or straining. The piping was removed only in the dispenser area. Residual petroleum hydrocarbons were not reported above the laboratory reporting limits in soil samples collected adjacent to former dispensers D-1 and D-2 with the exception of methyl tertiary-butyl ether (MTBE) which was reported at a concentration of 0.46 milligrams per kilogram (mg/kg). Lead was reported in the sample collected adjacent to dispenser D-1 at 6.4 mg/kg (ERI 1998).

2007 – ATC observed the advancement of three soil borings (ATC-2, ATC-4, and ATC-5) in the vicinity of the existing fuel USTs and dispensers. TPH-G was reported at concentrations of 1.4 mg/kg and 5.2 mg/kg in soil samples collected at approximately five feet below ground surface (bgs) in borings ATC-2 and ATC-5, respectively. TPH-D was reported in boring ATC-2 at a depth of five feet bgs at a concentration of 23 mg/kg. TPH-G was reported at concentrations of 73 micrograms per liter ( $\mu$ g/L), 69  $\mu$ g/L, and 5,300  $\mu$ g/L in groundwater samples collected from ATC-2 (including duplicate B-2) and ATC-5, respectively. TPH-D was reported at concentrations of 15,000  $\mu$ g/L, 25,000  $\mu$ g/L, and 18,000  $\mu$ g/L in groundwater samples collected from ATC-2 (including duplicate B-2) and ATC-5, respectively (ATC 2007).

December 1st through 8th 2010: Delta oversaw the installation of three groundwater monitoring wells (MW-1, MW-2 and MW-3) and the advancement of four soil borings (CPT-1, B-1, B-2 and B-3) located near the dispenser islands and fuel USTs. In soil samples, only DRO was reported above the laboratory reporting limit, with a maximum concentration of 447 mg/kg in MW-2 at a depth of 7.5 feet. In groundwater samples, only DRO and MTBE were reported in MW-3 at concentrations 74.4  $\mu$ g/L and 0.87  $\mu$ g/L, respectively. Groundwater was reported at depths of approximately 1 to 4 feet below top of casing in the wells, and groundwater was directed to the northwest. Further details regarding the investigation are included in Antea Group's Soil and Groundwater Investigation Report dated February 22, 2011.

### SENSITIVE RECEPTORS

In 2008, Delta performed a water well survey to locate all water supply wells within a half-mile of the site. The survey included a request to the Department of Water Resources (DWR) to provide well log records. No water supply wells were identified in the search.

A preferential pathway study was performed to determine whether trench backfill for utilities beneath the site or in the site vicinity could potential conduits for contaminant migration. Delta concluded that due to shallow groundwater and location of identified utilities, a nearby sewer line/trench and water line/trench could provide a direct conduit for groundwater migration from the site to neighboring sites (Delta 2008).

#### **REFERENCES CITED**

- Kaprealian Engineering, Inc., Soil Sampling Report, Unocal Service Station #1028, 5300 Broadway, Oakland, California, January 29, 1990.
- Kaprealian Engineering, Inc., Preliminary Groundwater Investigation, Unocal Service Station #1028, 5300 Broadway, Oakland, California, May 14, 1990.
- Environmental Resolutions, Inc., Environmental Work Related to EPA Retrofit, Tosco (Union) 76 Service Station 1028, 5300 Broadway Avenue, Oakland, California, June 16, 1998.
- ATC Associates Inc., Due Diligence Site Assessment Report, ConocoPhillips Site No. 251028, 5300 Broadway Avenue, Oakland, California, November 1, 2007.
- San Francisco Bay Regional Water Quality Control Board, California EPA, Screening For Environmental Concerns at Sites With Contaminated Soil and Groundwater (November 2007), http://www.waterboards.ca.gov/sanfranciscobay/esl.htm, Revised May 2008.
- Delta Consultants, Additional Site Assessment Work Plan First Phase, Fuel Leak Case No. RO00002967, GeoTracker Global ID T0619732490, Unocal #1028 / ConocoPhillips # 251028, 5300 Broadway, Oakland, CA 94618, October 29, 2008
- Alameda County Heath Care Services Agency, Fuel Leak Case No. RO00002967 and Geotracker Global ID T0619732490, Unocal #1028 / ConocoPhillips # 251028, 5300 Broadway, Oakland, CA 94618, March 6, 2009.
- Delta Consultants, Soil and Water Investigation Work Plan Addendum, Fuel Leak Case No. RO00002967, GeoTracker Global ID T0619732490, Unocal #1028 / ConocoPhillips # 251028, 5300 Broadway, Oakland, CA 94618, April 3, 2009.
- Delta Consultants, Soil and Water Investigation Work Plan Addendum dated April 3, 2009 (60 day Notification), Fuel Leak Case No. RO00002967, GeoTracker Global ID T0619732490, Unocal #1028 / ConocoPhillips # 251028, 5300 Broadway, Oakland, CA 94618, October 2, 2009.
- Alameda County Environmental Health, Email Correspondence: RO00002967, 5300 Broadway, Oakland, October 29, 2009.
- Delta Consultants, Work Plan for Preliminary Site Assessment, 76 Service Station No. 1028, 5300 Broadway Oakland, California Alameda County LOP Case #: RO0002967 Delta Project No. 140251028, July 6<sup>th</sup>, 2010.
- Delta Consultants, Email Correspondence, 5300 Broadway, Oakland, CA RO#02697, September 20<sup>th</sup>, 2010
- Alameda County Environmental Health, Email Correspondence: RO00002967, 5300 Broadway, Oakland, September 20<sup>th</sup>, 2010

Antea Group, Soil and Groundwater Investigation Report and Case Closure Request, 76 Service Station No. 1028, 5300 Broadway Oakland, California Alameda County LOP Case #: RO0002967 Delta Project No. I40251028, February 22, 2011



### Appendix B

Blaine Tech Services Standard Operating Procedures

## BLAINE TECH SERVICES, INC. METHODS AND PROCEDURES FOR THE ROUTINE MONITORING OF GROUNDWATER WELLS

### SAMPLING PROCEDURES OVERVIEW

### SAFETY

All groundwater monitoring assignments performed for DELTA comply with safety guidelines, 29 CFR 1910.120 and SB-198 Injury and Illness Prevention Program (IIPP). All Field Technicians receive the full 40 hour 29CFR 1910.120 OSHA SARA HAZWOPER course, medical clearance and on-the-job training prior to commencing any work on any DELTA COP/ELT site.

### INSPECTION AND GAUGING

Wells are inspected prior to evacuation and sampling. The condition of the wellhead is checked and noted according to a wellhead inspection checklist.

Standard measurements include the depth to water (DTW) and the total well depth (TD) obtained with industry standard electronic sounders which are graduated in increments of hundredths of a foot

The water in each well is inspected for the presence of Immiscibles or sheen and when free product is suspected, it is confirmed using an electronic interface probe (e.g. MMC). No samples are collected from a well containing free product.

### **EVACUATION**

Depth to water measurements are collected by our personnel prior to purging and minimum purge volumes are calculated anew for each well based on the height of the water column and the diameter of the well. Expected purge volumes are never less than three case volumes and are set at no less than four case volumes in some jurisdictions.

Well purging devices are selected on the basis of the well diameter and the total volume to be evacuated. In most cases the well will be purged using an electric submersible pump (i.e. Grundfos) suspended near (but not touching) the bottom of the well. Small volumes of purgewater are often removed by hand bailing with a disposable bailer.

### PARAMETER STABILIZATION

Well purging completion standards include minimum purge volumes, but additionally require stabilization of specific groundwater parameters prior to sample collection. Typical groundwater parameters used to measure stability are electrical conductivity, pH, and temperature. Instrument readings are obtained at regular intervals during the evacuation process (no less

than once per case volume).

Stabilization standards for routine quarterly monitoring of fuel sites include the following: Temperature is considered to have stabilized when successive readings do not fluctuate more than +/- 1 degree Celsius. Electrical conductivity is considered stable when successive readings are within 10%. pH is considered to be stable when successive readings remain constant or vary no more than 0.2 of a pH unit.

### **DEWATERED WELLS**

Normal evacuation removes no less than three case volumes of water from the well. However, less water may be removed in cases where the well dewaters and does not recharge.

Wells known to dewater are evacuated as early as possible during each site visit in order to allow for the greatest amount of recovering. Any well that does not recharge to 80% of its original volume will be sampled prior to the departure of our personnel from the site in order to eliminate the need of a return visit.

In jurisdictions where a certain percentage of recovery is included in the local completion standard, our personnel follow the regulatory expectation.

### PURGEWATER CONTAINMENT

All non-hazardous purgewater evacuated from each groundwater monitoring well is captured and contained in on-board storage tanks on the Sampling Vehicle and/or special water hauling trailers. Effluent from the decontamination of reusable apparatus (sounders, electric pumps and hoses etc.), consisting of groundwater combined with deionized water and non-phosphate soap, is also captured and pumped into effluent tanks.

Non hazardous purgewater is transported under standard Bill of Lading or Non-Hazardous manifest to a Blaine Tech Services, Inc. facility before being transported to an approved disposal facility.

### SAMPLE COLLECTION DEVICES

All samples are collected using disposable bailers.

### SAMPLE CONTAINERS

Sample material is decanted directly from the sampling bailer into sample containers provided by the laboratory which will analyze the samples. The type of sample container, material of construction, method of closure and filling requirements are specific to the intended analysis. Chemicals needed to preserve the sample material are commonly placed inside the sample containers by the laboratory or glassware vendor prior to delivery of the bottle to our personnel. The laboratory sets the number of replicate containers.

### TRIP BLANKS

Upon request, a Trip Blank is carried to each site and is kept inside the cooler for the duration of the sampling event. It is turned over to the laboratory for analysis with the samples from that site.

### **DUPLICATES**

Upon request, one Duplicate sample is collected at each site. It is up to the Field Technician to choose the well at which the Duplicate is collected. Typically, a duplicate is collected from one of the most contaminated wells. The Duplicate sample is labeled DUP thus rendering the sample blind.

### SAMPLE STORAGE

All sample containers are promptly placed in food grade ice chests for storage in the field and transport (direct or via our facility) to the analytical laboratory that will perform the intended analytical procedures. These ice chests contain quantities of restaurant grade ice as a refrigerant material. The samples are maintained in either an ice chest or a refrigerator until relinquished into the custody of the laboratory or laboratory courier.

### **DOCUMENTATION CONVENTIONS**

Each and every sample container has a label affixed to it. In most cases these labels are generated by our office personnel and are partially preprinted. Labels can also be hand written by our field personnel. The site is identified with the store number and site address, as is the particular groundwater well from which the sample is drawn (e.g. MW-1, MW-2, S-1 etc.). The time at which the sample was collected and the initials of the person collecting the sample are handwritten onto the label.

Chain of Custody records are created using client specific preprinted forms following USEPA specifications.

Bill of Lading records are contemporaneous records created in the field at the site where the non-hazardous purgewater is generated. Field Technicians use preprinted Bill of Lading forms.

### **DECONTAMINATION**

All equipment is brought to the site in clean and serviceable condition and is cleaned after use in each well and before subsequent use in any other well. Equipment is decontaminated before leaving the site.

The primary decontamination device is a commercial steam cleaner. The steam cleaner is detuned to function as a hot pressure washer which is then operated with high quality deionized water which is produced at our facility and stored onboard our sampling vehicle. Cleaning is facilitated by the use of proprietary fixtures and devices included in the patented workstation that is incorporated in each sampling vehicle. The steam cleaner is used to decon reels, pumps

and bailers.

Any sensitive equipment or parts (i.e. Dissolved Oxygen sensor membrane, sounder etc.) that cannot be washed using the hot high pressure water, will be sprayed with a non-phosphate soap and deionized water solution and rinsed with deionized water.

EXAMPLE: The sounder is cleaned between wells using the non-phosphate soap and deionized water solution followed by deionized water rinses. The sounder is then washed with the steam cleaner between sites or as necessitated by use in a particularly contaminated well.

### DISSOLVED OXYGEN READINGS

All Dissolved Oxygen readings are taken using YSI meters (e.g. YSI Model 550 meter). These meters are equipped with membrane probe that enables them to collect accurate in-situ readings.

The probe and reel is decontaminated between wells as described above. The meter is calibrated as per the instructions in the operating manual. The probe is lowered into the water column allowed to stabilize before use.

### OXYIDATON REDUCTION POTENTIAL READINGS

All readings are obtained with either Corning or Myron-L meters (e.g. Corning ORP-65 or a Myron-L Ultrameter GP). The meter is cleaned between wells as described above. The meter is calibrated at the start of each day according to the instruction manual. In use the probe is placed in a cup of freshly obtained monitoring well water and allowed to stabilize.

### Blaine Tech Services, Inc. Standard Operating Procedure

### **Purge Water Handling Procedure**

### **Purpose**

Control of non-hazardous purge water disposal. This procedure outlines the handling and disposing of non-hazardous purge water for the DELTA/COP portfolio.

### **Procedure**

- 1) All purge and rinsate water will be contained in onboard truck tanks or trailers. Water may be commingled with other sites in the same portfolio of DELTA/COP sites.
- 2) A Non-Hazardous Waste manifest will be generated prior to leaving site.
- 3) All water will be offloaded into a commingled DELTA/COP tank at BLAINE facility.
- 4) Water will then be offloaded from the DELTA/COP tank and the BLAINE facility and transported to a disposal facility.

For Southern California sites water will be disposed at Crosby and Overton in Wilmington, CA. For Northern California water will be disposed at Seaport Environmental in Redwood City, CA.

### Example Manifest:

П	se print or type (Form designed for use on rible NON-HAZARDOUS	1. Generator's US EPA ID No.			Manifest Document No.		2. Page 1	
	WASTE MANIFEST  3. Generator's Name and Maling Address						61	
					l			
	4. Generator's Phene ( )	G.	US GPA ID Namber		A State Towns			-
14	5. Transporter 1 Company Name	ů.	US EPA ID INDIRE		A. State Trans B. Transporter			_
	7. Transporter 2 Company Name	1	US EPA ID Number		C. State Trans			
ાં		1			D. Transporter			
3	9. Dosignated Facility Name and Elio Address	10.	US EPA ID Number		E. Siste Facilit	y's ID		
្យ	7				F. Facility's Fit			
	·				r. racinys rr	one		
1	11. WASTE DESCRIPTION			12. Co	miaisera	13. Tenal Quantity	1 .	1-1. leit LiVal.
Ņ				No.	Туре	Quenky	Wit	LiÑal.
4	Α.							
				İ				
á	h			+	<del></del>		-	
١	l "-							
ı								
į	c.							
41141141				1	1			
5				-				
3	a.				1			
Į	G. Additional Descriptions for Materials Listes Abo	we	- 11111		H. Handling C	odes for Wastes Livled Allow		
3								
į	15. Special Handbay Instructions and Additional Is	domation						
m, Zi								
d								
ens Ven								
	357 ANN 3797 ANN ASS	ASS ART NOT A	禁护 探明 祝的 西	F9 /5	V AST I	TO AN AN	2539	.03
	16. GENERATOR'S CERTIFICATION: I limitely of in proper condition for wansport. The materials			ed one are in	an respects			
		Contract on the state of the st						
	in projec containen er warsgott. The materials		intigen to lederal hazardous wash	e regularitans.				
				e regulations.			Date	
. VIII SEE	PrintedTyped Natio		Signature	e regulations.		Afron		You 1
C. C		Materials		e regularitors.		Liferal		You
0.57 5007 FRA	Printed/Typed Name	More folis		e regulations.		E front	Detail	1_
OSY SEY ERAZOR	PrintedTyped Namu  17. Transporter 1 Advandadgement of Receipt of PrintedTyped Name		Signature	e regulations.			Detail	1_
OBY SWY ENGROOM	PrintedTyped Name  17. Transporter 1 Advantedgement of Recodd of Related Palme  18. Transporter 2 Advantedgement of Recodd of Related Palme  18. Transporter 2 Advantedgement of Recodd of		Signature	e regularitans.		Afan	Dote Date Date	l res
CALL STATE CONTRACTOR CONTRACTOR	PrintedTyped Namu  17. Transporter 1 Advandadgement of Receipt of PrintedTyped Name		Signature	e regularitans.			Dote Date Date	l res
	Privated Typed Flams  17: Transporter 1 Advisorietgement of Roccide of Risked Typed Tame  18: Transporter 2 Advisorietgement of Roccide of Risked Typed Tame  18: Transporter 2 Advisorietgement of Roccide of Risked Typed Tame		Signature	e regularitano.		Afan	Dote Date Date	l res
F	PrintedTyped Name  17. Transporter 1 Advantedgement of Recodd of Related Palme  18. Transporter 2 Advantedgement of Recodd of Related Palme  18. Transporter 2 Advantedgement of Recodd of		Signature	e regularitans.		Afan	Dote Date Date	l res
FAC	PriesendTyped Flams  13 Tocopyodes Linkhowsingspread of Ricceld	Milleroots	Riyaster Graziure Graziure			Afan	Dote Date Date	l res
TRAZORORTER FACIL	Privated Typed Flams  17: Transporter 1 Advisorietgement of Roccide of Risked Typed Tame  18: Transporter 2 Advisorietgement of Roccide of Risked Typed Tame  18: Transporter 2 Advisorietgement of Roccide of Risked Typed Tame	Milleroots	Riyaster Graziure Graziure			Afan	Date Date Date	Yes 1
FAC	PriesendTyped Flams  13 Tocopyodes Linkhowsingspread of Ricceld	Milleroots	Riyaster Graziure Graziure			Afan	Date Date Date Date	l rea

PRINCE ON RECYCLED PAPER A DESIGNATION OF



### Appendix C

Blaine Tech Services Field Data Sheets for Groundwater Monitoring and Sampling

						We	:II-}	teac	Inspec	tion & V	/ell Gau	ging For	m	
٩nte	a Group Project No:	eline ( )	Daw	8	······			Site A	ddress:	300 3n	202 Jusy	100	<u>cloud</u>	
	(Print Full Nan	ne & C	ompa	(*עמו		13	loiv	e. 7	éela	Date: 5	5/8/11		···	Weather: Suny
	W	ell Co	nditio	on_	T	l	-		l .				T	
Sample Order	Field Point	Bolts	Seal	Lid Secure	Lock	Expanding Cap	Water in Well Box	Well Casing Dia.	Time Gauged	Depth to Water (Feet)	Depth to Bottom (Feet)	Depth to LNAPL (Feet)	LNAPL Thickness (Feet)	Comments
2000	MW-1	6	G.	G	G	6	A)	2	izHo	2.50	12.26	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
2_	<u>, , , , , , , , , , , , , , , , , , , </u>	G	Ó	6	6	C	Z_	2	1245	4.72	11.62			
2_ 3	<u> </u>	G	G	Ó	Gr	G	N	2	1260	3.52	12,56	******************************		
								***************************************						
						47)-			· .					
Votes														** All well caps opened at least 15 minutes or longer before gauging wells:
			**********			·····				·· <del>···································</del>				CIRCLE ONE: YES or NO**)



\*Form provided by Antea Group

		Ground	water S	ampling	Form			
Site Address:	5300	3 million	u i Ocil	Kland			WAS CONTRACTOR OF THE CONTRACT	
Project No:	2562	£**	Fie	ld Technician:	Padnic	k Han	r-s"	
Field Point:	1-cm			Date:	8/8/1	1		
Depth to Water (DTW) (ft bgs):	2.50		Well	Diameter (in):	<u>(3)</u>	4 6 8	******	
Depth to LNAPL (ft bgs):	organization, re		Thickness	of LNAPL (ft):	*DEPTOR DE MONTO		,	
Total Depth of Well (ft bgs):	12.26		Water Colun	nn Height (ft):	9.76			
				i Calculation:				
Purge Method:		Purge Eq	uipment:		5		ection Method	1
Low-Flow			ole Bailer ubmersible			None with the party of the last of the las	ble Bailer> tion Port	
3 casing volumes		Peristalt	ic Pump			Dedicat	ed Tubing	
		Bladde Other:	r Pump		Oth	Disposal ner:	ble Tubing	
				a-024 \$ -0.09E			3. 42	
Water Column Height (ft):								
Casing Volume (gal):	1.6	X Specified Vo	olumes:	26 j	_ = Calculated	Purge (gal):	Some 4 m	
Conversion Factors (	gal/ft): 2"	= 0.17 4"	= 0.66 6"	= 1.5 8" =		= radius² * 0		
Purge: Start		(2) T			Stop Time:			
Time	Temp (°C)	рН	Conductivity (µS/cm)	ORP (mV)	Turbidity (NTU)	D.O. (mg/L)	Volume Purged (gal)	Water Level (for Low-Flow only)
Pre-Purge								
1300	69.5	6.5	474	cipinate (Carlo	ettoette	-11-12-12-12-12-12-12-12-12-12-12-12-12-	2.0	
d Collins	71.2	6.5	471	epidentzino).	спожнять!	wysona kidwinia. S.	3.5	
1303	70.8	6.6	478	- Submission Color	Galanga Arabini	department.	5,0	
				**************************************				
								***************************************
Post-Purge								
Did Well dewater?	Yes (	Nb)	Total	Purge volume	(gal): 5			
	X27.0	24.45		ms/L				
Other Comments:				CH Voz				
	VIWS 4	71.16						
Sample Info:			I	_				
Sample ID:	<u> </u>	Czonos,		Sample Date	e and Time:	8/8/11	<u>। क्षेट्रा</u>	
Selected Analysis:	See (			NATIONAL AND	**************************************		und des med de la charles de la cilità de la Charles de	
This form was provided by Ant completed by: (Print Full Name	•		x ha	rus .	, a	n employee (	of Blaine Tech S	Services, Inc.
TO SECURITION OF THE PROPERTY			,		Account.	- A		
Signature:	<u> </u>	A Company of the Comp		Date:	<u> </u>	<u> </u>		PROTECTION OF THE PROTECTION O



LNAPL= light non-aqueous phase liquids bgs = below ground surface ORP = Oxidation-Reduction Potential

D.O.= dissolved oxygen

gal = gallon/s temp = temperature NTU = Nephelometric Turbidity Units mV = millivolts

Page \_\_\_\_\_ of \_\_\_\_

		Ground	water S	ampling	Form			
Site Address:	5300	Bosselwa	w, oe	olus				
Project No:	251028		market .	ld Technician:	Padrick	: Hawar		
Field Point:	ハルンーユ	99"		Date:	8/8/	'I\		
Depth to Water (DTW) (ft bgs):	Log 77 Zum		Well	Diameter (in):	2	4 6 8		
Depth to LNAPL (ft bgs):	entermental de		Thickness	of LNAPL (ft):	quiposant desta			
Total Depth of Well (ft bgs):	11-62		Water Colun	nn Height (ft):	6.90			
				l Calculations				
Purge Method:		Purge Eq	uipment:		S	iample Colle	ection Method	:
Low-Flow 3 casing volumes Other:		Electric St Peristalt Bladde Other:				Extract Dedicate Disposal her:		
	Water Column Height (ft): 6.90 X Conversion Factor (gal/ft): 9.77 = Casing Volume (gal): 1.2							
casing voicine (gary).								
Conversion Factors ( Purge: Start	gal/ft):		- U.UO D"		Stop Time:	= radius² * 0	personal de la companya de la compa	
Time	Temp (°C)	ρΗ	Conductivity (µS/cm)	ORP (mV)	Turbidity (NTU)	D.O. (mg/L)	Volume Purged (gal)	Water Level (for Low-Flow only)
Pre-Purge			Carto de Propins				-	
1332	69.5	7.0	472	al-Chambar	-ueria	eccentrate St	1.5	
1334	70.5	7.0	L(2)	+ycpotenskii	**************************************	epplicate (dr.) y	2.5	
1336	71.4	7.1	421	Townsouth	cherosensisis	Contains to	3.5	
								***
						***************************************		
				***************************************	~			
Dank Dane								
Post-Purge  Did Well dewater?	Yes 🔨	<u>6</u>	Total	Purge volume (	(asl): " *			
Did Well dewater:	\$5°25 €		TOTAL	range volume (	(gai)- 多、>			
Other Comments:	UNG							entronesse on event acco
Sample Info:			Jan 19 19 19					
Sample ID:	ハンーご。	इ.८०% व्ह	Ł .	Sample Date	and Time:	8/8/11	1340	
Selected Analysis:	30e c							
This form was provided by Anticompleted by: (Print Full Name	ea Group and	- Marian	rick t	laring	, a	n employee c	of Blaine Tech S	Services, Inc.
Signature:				Date:		/\$/\\		
E)		LNAPL= light non	-aqueous phase li	quids	gal = gallon/s			

anteagroup

Antea<sup>™</sup>Group, 1-800-477-7411

bgs = below ground surface ORP = Oxidation-Reduction Potential D.O.= dissolved oxygen temp = temperature NTU = Nephelometric Turbidity Units mV = millivoits

Page \_\_\_\_\_\_ of \_\_\_\_\_\_

		Ground	water S	ampling	Form					
Site Address:	5300	Books	<u>a</u> , 00	Kland						
Project No:	25102	<u>\$</u>	, Fie	eld Technician:	Pertn'	ck Ha	"Ne"			
Field Point:	E-UM			Date:	8/8/1	1				
Depth to Water (DTW) (ft bgs):	\$ 20% and and		Well	Diameter (in):	2	4 6, 8				
Depth to LNAPL (ft bgs):	entransportation (		Thickness	of LNAPL (ft):	ويري والمراجعة					
Total Depth of Well (ft bgs):	12.56		Water Colur	nn Height (ft):	9. di					
				i Calculations						
Purge Method:		Purge Eq	uipment:		5	Sample Colle	ection Method	:		
Low-Flow 3 casing volumes Other:		Electric Su Peristali Bladde	ic Pump r Pump		Disposable Bailer Extraction Port Dedicated Tubing Disposable Tubing					
	,	Other:	BATTETT TO THE LANGUAGE PLANTS AT ARABIS TRAVERS	•	Ot	her:	-1			
Water Column Height (ft):				):						
Casing Volume (gal):	vS	X Specified V	olumes:	3	_ = Calculated	l Purge (gal):	luci ve			
Conversion Factors (		PROCESSOR AND ADDRESS OF THE PROCESSOR AND AD	= 0.66 6"	= 1.5 8" =		= radius <sup>2</sup> * 0				
Purge: Start	Time:				Stop Time:_	1	<del></del>			
Time	Temp (°C)	рH	Conductivity (µS/cm)	ORP (mV)	Turbidity (NTU)	D.O. (mg/L)	Volume Purged (gal)	Water Level (for Low-Flow only)		
Pre-Purge										
1404	71.7	7.3	84	graphic to the second	waster.	electropics*	1.5			
1467	71.7	and the second	895	energy of the second	evoranja A	epopletation in the	3.0			
1411	72.5	7.3	917	Salananir.	\$Granderset	· ·	5.0			
								and the state of t		
					,					
				· · · · · · · · · · · · · · · · · · ·	***************************************					
Post-Purge										
Did Well dewater?	Vac A		Total	Duran valuma		· ·				
Did wen dewater?	CHARLES TO SECURE THE	10)	TOTAL	Purge volume (	gai): 'es	THE RESERVE OF THE PERSON OF T	STATE OF THE STATE			
Other Comments:	2020	80%C 5.32 TW= 5.21								
	ブル	j.Z.								
Sample Info:										
Sample ID:	ELLEN,	2011053	§ .	Sample Date	and Time:	8/8/1	1425			
Selected Analysis:	Se						-			
This form was provided by Anti	ea Group and	- mileting	· & ·b <			0-11	Westermon Control Cont			
completed by: (Print Full Name	2)	Teatr	ck Ho	dint	, а	n employee c	of Blaine Tech S	Services, Inc.		
Signature:				Date:	€/	<u> 78711 </u>				
\$2-5		LNAPL= light non	-aqueous phase l	iauids i	gal = gallon/s					

antea group Antea™Group, 1-800-477-7411

LNAPL= light non-aqueous phase liquid bgs = below ground surface ORP = Oxidation-Reduction Potential

D.O.= dissolved oxygen

tem = temperature

NTU = Nephelometric Turbidity Units

mV = millivoits

Page \_\_\_\_\_\_ of \_\_\_\_

### TEST EQUIPMENT CALIBRATION LOG

PROJECT NAI	WE 5300 3	adus 10ak	low	PROJECT NUMBER 1108/5-17H1						
EQUIPMENT NAME	EQUIPMENT NUMBER	DATE/TIME OF TEST		EQUIPMENT READING	CALIBRATED TO: OR WITHIN 10%:	TEMP.				
Morent Uthermote-II	6209575	8/8/1\ 1253	74 700 10-60 4.00	7.00	V V	TIEWF.	Ph			
			Conductivity 3000 when		-		PN			
				<i>*</i> .						
		. 2'		,						



### COP ELT CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed and accurate.

Page: 1 of Cooler# \_\_\_\_ of

3Q 2011 Event

Required Lab Information: Required Project Information: Regulred Invoice Information: Lab Name: Pace-Seattle Site ID#: 251028 Task: WG\_Q\_201108 Send Invoice to: Tara Bosch Address: AnteaGrp proj# 140251028 Address: 11050 White Rock Rd. Suite 110 Turn around time (days) 940 S. Hamey Street Seattle WA 98108 Site Address 5300 Broadway City/State Rancho Cordova CA 95670 Phone #: QC level Required: Standard 916-503-1267 Special Mark · Lab PM: Regina Ste. Marie Oakland City State Reimbursement project? Non-reimbursement project? Mark one NJ Reduced Deliverable Package? Phone/Fax: P: 206-957-2433 F: 206-767-5063 MA MCP Cert? AG PM Name: CT RCP Cert? Mark ( Send EDD to Lia Holden copeltdata@intelligentehs.com Lab PM email Regina.SteMarie@pacelabs.com P: 408 826 1863 F: Phone/Fax: CC Hardcopy report to Lab Project ID (lab use) Applicable Lab Quote #: AG PM Email: lia.holden@anteagroup.com CC Hardcopy report to Requested Valid Matrix Codes MATRIX
WATER
SURFACE WATER
WATER QC
SLUDGE
RINGEATE
OTHER
ANNAL TISSUE MATRIX DRINKING WATER Analyses Preservatives SAMPLE TYPE 3=GRAB C=COMP SAMPLE ID DRINKING WATER GROUND WATER WASTE WATER FREE PRODUCT MATRIX CODE W WS WD SL WH OT A One Character per box. SAMPLE DATE SAMPLE TIME (A-Z, 0-91,-) TEM Samples IDs MUST BE UNIQUE Comments/Lab 1,50, -INO3 PS CH õ Sample I.D. MW-1\_20110831 8/8/11 1310 12 WG Х Х 8015 TPHd is with silica MW-2 20110831 1340 ঠ WG Х gel cleanup MW-3 20110831 1420 WG х Х 7 Oxy's = DIPE, TBA, TAME, ETBE, 1,2-DC C EDB, and Ethanol C 10 111 Additional Comments/Special Instructions: RELINGUISHED BY / AFFILIATION TIME DATE ACCEPTED BY / AFFILIATION DATE TIME Sample Receipt Conditions 2~~ 1375 8/8/11/1600 Y/N Y/N Y/ Y/N Υ/ Y/N Y/NY/N YI Global ID: T0619732490 Y/ Y/N Y/N SHIPPING METHOD: (mark as appropriate) SAMPLER NAME AND SIGNATURE Trip Blank Patrick Harm DATE Signed 88/1 Time: 1605 Sample intact? UPS COURIER FEDEX SIGNATURE OF SAMPLER: US MAIL





### Appendix D

Laboratory Analytical Report and Validation Form





August 24, 2011

Lia Holden Antea USA 312 Piercy Rd San Jose, CA 95138

RE: Project: 251028

Pace Project No.: 258781

### Dear Lia Holden:

Enclosed are the analytical results for sample(s) received by the laboratory on August 10, 2011. The results relate only to the samples included in this report. Results reported herein conform to the most current TNI standards, where applicable, unless otherwise narrated in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Regina SteMarie

Regina Se. Marie

regina.stemarie@pacelabs.com Project Manager

**Enclosures** 

cc: Tara Bosch, Antea USA
Dennis Dettloff, Antea USA
Jonathon Fillingame, Antea USA
Dan Keltner, Antea USA
Josh Mahoney, Antea USA
Tony Perini, Antea USA
Nicole Persaud, Antea USA
Don Pinkerton, Antea USA
Doug Umland, Antea USA
Ed Weyrens, Antea USA







#### **CERTIFICATIONS**

Project: 251028 Pace Project No.: 258781

Washington Certification IDs 940 South Harney Street, Seattle, WA 98108 Alaska CS Certification #: UST-025 California Certification #: 01153CA

Florida/NELAP Certification #: E87617 Oregon Certification #: WA200007 Washington Certification #: C555



#### **SAMPLE ANALYTE COUNT**

Project: 251028 Pace Project No.: 258781

Lab ID	Sample ID	Method	Analysts	Analytes Reported	Laboratory
258781001	MW-1_20110831	EPA 8015B	DMT	3	PASI-S
		EPA 5030B/8260	LPM	16	PASI-S
		CA LUFT	LNH	2	PASI-S
258781002	MW-2_20110831	EPA 8015B	DMT	3	PASI-S
		EPA 5030B/8260	LPM	16	PASI-S
		CA LUFT	LNH	2	PASI-S
258781003	MW-3_20110831	EPA 8015B	DMT	3	PASI-S
		EPA 5030B/8260	LPM	16	PASI-S
		CA LUFT	LPM	2	PASI-S





#### **HITS ONLY**

Project: 251028 Pace Project No.: 258781

Lab Sample ID Client Sample ID

 Method
 Parameters
 Result
 Units
 Report Limit
 Analyzed
 Qualifiers

258781003 MW-3\_20110831

EPA 5030B/8260 Methyl-tert-butyl ether 1.2 ug/L 0.50 08/18/11 11:51



#### **ANALYTICAL RESULTS**

Project: 251028 Pace Project No.: 258781

Date: 08/24/2011 04:20 PM

Sample: MW-1_20110831	Lab ID: 25878	1001	Collected: 08/08/1	1 13:10	Received: 08	3/10/11 08:10	Matrix: Water	
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qua
8015B CA TPH DRO SG	Analytical Metho	d: EPA 8015	B Preparation Me	ethod: El	PA 3510 Modified	t		
TPH-DRO (C10-C24) SG	ND ug/L		50.0	1	08/12/11 09:50	08/16/11 18:25	5	
o-Terphenyl (S) SG	86 %		51-147	1	08/12/11 09:50	08/16/11 18:25	84-15-1	
n-Octacosane (S) SG	98 %		50-150	1	08/12/11 09:50	08/16/11 18:25	630-02-4	
8260 MSV	Analytical Metho	d: EPA 5030	B/8260					
tert-Amylmethyl ether	ND ug/L		0.50	1		08/18/11 11:14	994-05-8	
Benzene	ND ug/L		0.50	1		08/18/11 11:14	71-43-2	
tert-Butyl Alcohol	ND ug/L		5.0	1		08/18/11 11:14	75-65-0	
1,2-Dibromoethane (EDB)	ND ug/L		1.0	1		08/18/11 11:14	106-93-4	
1,2-Dichloroethane	ND ug/L		1.0	1		08/18/11 11:14	107-06-2	
Diisopropyl ether	ND ug/L		0.50	1		08/18/11 11:14	108-20-3	
Ethanol	ND ug/L		250	1		08/18/11 11:14	64-17-5	
Ethylbenzene	ND ug/L		0.50	1		08/18/11 11:14	100-41-4	
Ethyl-tert-butyl ether	ND ug/L		0.50	1		08/18/11 11:14		
Methyl-tert-butyl ether	ND ug/L		0.50	1		08/18/11 11:14		
Toluene	ND ug/L		0.50	1		08/18/11 11:14		
Xylene (Total)	ND ug/L		1.5	1		08/18/11 11:14		
4-Bromofluorobenzene (S)	97 %		79-121	1		08/18/11 11:14		
Dibromofluoromethane (S)	98 %		81-119	1		08/18/11 11:14		
1,2-Dichloroethane-d4 (S)	102 %		72-127	1		08/18/11 11:14		
. ,	102 %		72-127 77-120	1		08/18/11 11:14		
Toluene-d8 (S)			77-120	'		00/10/11 11.14	2037-20-3	
CA LUFT MSV GRO	Analytical Metho	d: CA LUFT						
TPH-Gasoline (C05-C12)	ND ug/L		50.0	1		08/20/11 15:45	5	
4-Bromofluorobenzene (S)	99 %		76-121	1		08/20/11 15:45	5 460-00-4	
Sample: MW-2_20110831	Lab ID: 25878	1002	Collected: 08/08/1	1 13:40	Received: 08	3/10/11 08:10	Matrix: Water	
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qua
8015B CA TPH DRO SG	Analytical Metho	d: EPA 8015	B Preparation Me	ethod: El	PA 3510 Modified	 d	_	
	,							
TDL DBO (C10 C24) SC	ND ua/l		50.0	4	00/10/11 00.50			
TPH-DRO (C10-C24) SG	ND ug/L		50.0	1	08/12/11 09:50			
o-Terphenyl (S) SG	82 %		51-147	1	08/12/11 09:50	08/16/11 18:41	84-15-1	
o-Terphenyl (S) SG n-Octacosane (S) SG	82 % 94 %	L ED4	51-147 50-150			08/16/11 18:41	84-15-1	
TPH-DRO (C10-C24) SG o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV	82 %	d: EPA 5030	51-147 50-150	1	08/12/11 09:50	08/16/11 18:41	84-15-1	
o-Terphenyl (S) SG n-Octacosane (S) SG	82 % 94 %	d: EPA 5030	51-147 50-150	1	08/12/11 09:50	08/16/11 18:41	84-15-1 630-02-4	
o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV	82 % 94 % Analytical Metho ND ug/L ND ug/L		51-147 50-150 B/8260 0.50 0.50	1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32 08/18/11 11:32	84-15-1 630-02-4 2 994-05-8 2 71-43-2	
o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV tert-Amylmethyl ether Benzene tert-Butyl Alcohol	82 % 94 % Analytical Metho ND ug/L		51-147 50-150 B/8260 0.50	1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32	84-15-1 630-02-4 2 994-05-8 2 71-43-2	
o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV tert-Amylmethyl ether Benzene	82 % 94 % Analytical Metho ND ug/L ND ug/L		51-147 50-150 B/8260 0.50 0.50	1 1 1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32 08/18/11 11:32	84-15-1 630-02-4 2 994-05-8 2 71-43-2 2 75-65-0	
o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV tert-Amylmethyl ether Benzene tert-Butyl Alcohol	82 % 94 % Analytical Metho ND ug/L ND ug/L ND ug/L		51-147 50-150 B/8260 0.50 0.50 5.0	1 1 1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32	84-15-1 630-02-4 994-05-8 71-43-2 75-65-0 106-93-4	
o-Terphenyl (S) SG n-Octacosane (S) SG  8260 MSV  tert-Amylmethyl ether Benzene tert-Butyl Alcohol 1,2-Dibromoethane (EDB)	82 % 94 % Analytical Metho ND ug/L ND ug/L ND ug/L ND ug/L		51-147 50-150 B/8260 0.50 0.50 5.0 1.0	1 1 1 1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32	84-15-1 630-02-4 2 994-05-8 2 71-43-2 2 75-65-0 2 106-93-4 2 107-06-2	
o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV tert-Amylmethyl ether Benzene tert-Butyl Alcohol 1,2-Dibromoethane (EDB) 1,2-Dichloroethane	82 % 94 % Analytical Metho ND ug/L ND ug/L ND ug/L ND ug/L		51-147 50-150 B/8260 0.50 0.50 5.0 1.0 1.0	1 1 1 1 1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32	84-15-1 630-02-4 2 994-05-8 2 71-43-2 2 75-65-0 2 106-93-4 2 107-06-2 2 108-20-3	
o-Terphenyl (S) SG n-Octacosane (S) SG 8260 MSV tert-Amylmethyl ether Benzene tert-Butyl Alcohol 1,2-Dibromoethane (EDB) 1,2-Dichloroethane Diisopropyl ether	82 % 94 % Analytical Metho ND ug/L ND ug/L ND ug/L ND ug/L ND ug/L		51-147 50-150 B/8260 0.50 0.50 5.0 1.0 1.0 0.50	1 1 1 1 1 1 1	08/12/11 09:50	08/16/11 18:41 08/16/11 18:41 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32 08/18/11 11:32	84-15-1 630-02-4 2 994-05-8 2 71-43-2 2 75-65-0 2 106-93-4 2 107-06-2 2 108-20-3 3 64-17-5	

#### **REPORT OF LABORATORY ANALYSIS**



#### **ANALYTICAL RESULTS**

Project: 251028 Pace Project No.: 258781

Sample: MW-2_20110831	Lab ID: 2587	81002	Collected: 08/08/1	1 13:40	Received: 0	8/10/11 08:10 N	Matrix: Water	
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8260 MSV	Analytical Metho	od: EPA 50	030B/8260					
Methyl-tert-butyl ether	ND ug/l	_	0.50	1		08/18/11 11:32	1634-04-4	
Toluene	ND ug/L	_	0.50	1		08/18/11 11:32	108-88-3	
Xylene (Total)	ND ug/L	_	1.5	1		08/18/11 11:32	1330-20-7	
4-Bromofluorobenzene (S)	98 %		79-121	1		08/18/11 11:32	460-00-4	
Dibromofluoromethane (S)	99 %		81-119	1		08/18/11 11:32	1868-53-7	
1,2-Dichloroethane-d4 (S)	103 %		72-127	1		08/18/11 11:32		
Toluene-d8 (S)	101 %		77-120	1		08/18/11 11:32		
CA LUFT MSV GRO	Analytical Metho	od: CA LU	FT					
TPH-Gasoline (C05-C12)	ND ug/l	_	50.0	1		08/20/11 16:03		
4-Bromofluorobenzene (S)	97 %		76-121	1		08/20/11 16:03	460-00-4	
Sample: MW-3 20110831	Lab ID: 2587	94002	Callastad: 09/09/1	1 11.05	Pagaired: 0	8/10/11 08:10 N	Antriv: Water	
Sample: MW-3_20110831	Lab ID: 25876	81003	Collected: 08/08/1				Matrix: Water	
Parameters	Results	Units	Report Limit	DF	Prepared	Analyzed	CAS No.	Qual
8015B CA TPH DRO SG	Analytical Metho	od: EPA 80	015B Preparation Me	ethod: El	PA 3510 Modifie	d		
TPH-DRO (C10-C24) SG	ND ug/l	_	50.0	1	08/12/11 09:50	08/16/11 19:30		
o-Terphenyl (S) SG	75 %		51-147	1	08/12/11 09:50	08/16/11 19:30	84-15-1	
n-Octacosane (S) SG	87 %		50-150	1	08/12/11 09:50	08/16/11 19:30	630-02-4	
8260 MSV	Analytical Metho	od: EPA 50	030B/8260					
tert-Amylmethyl ether	ND ug/l	_	0.50	1		08/18/11 11:51	994-05-8	
Benzene	ND ug/L	_	0.50	1		08/18/11 11:51	71-43-2	
tert-Butyl Alcohol	ND ug/L	_	5.0	1		08/18/11 11:51	75-65-0	
1,2-Dibromoethane (EDB)	ND ug/L	_	1.0	1		08/18/11 11:51	106-93-4	
1,2-Dichloroethane	ND ug/L	-	1.0	1		08/18/11 11:51	107-06-2	
Diisopropyl ether	ND ug/L	-	0.50	1		08/18/11 11:51	108-20-3	
Ethanol	ND ug/l	_	250	1		08/18/11 11:51	64-17-5	
Ethylbenzene	ND ug/l		0.50	1		08/18/11 11:51	100-41-4	
Ethyl-tert-butyl ether	ND ug/l		0.50	1		08/18/11 11:51	637-92-3	
Methyl-tert-butyl ether	<b>1.2</b> ug/l		0.50	1		08/18/11 11:51		
Toluene	ND ug/l		0.50	1		08/18/11 11:51		
Xylene (Total)	ND ug/l		1.5	1		08/18/11 11:51		
4-Bromofluorobenzene (S)	98 %	-	79-121	1		08/18/11 11:51		
Dibromofluoromethane (S)	99 %		81-119	1		08/18/11 11:51		
1,2-Dichloroethane-d4 (S)	103 %		72-127	1		08/18/11 11:51		
Toluene-d8 (S)	100 %		72-127 77-120	1		08/18/11 11:51		
CA LUFT MSV GRO	Analytical Metho	od: CA LU						
TDH Gasolino (COE C12)	· ·			1		08/18/11 11:51		
TPH-Gasoline (C05-C12) 4-Bromofluorobenzene (S)	ND ug/l 98 %	-	50.0 76-121	1		08/18/11 11:51 08/18/11 11:51	460.00.4	
4-Promonantonenzene (9)	90 %		70-121	1		00/10/11 11.51	400-00-4	

Date: 08/24/2011 04:20 PM

#### **REPORT OF LABORATORY ANALYSIS**



Project: 251028 Pace Project No.: 258781

QC Batch: OEXT/4200 Analysis Method: EPA 8015B

QC Batch Method: EPA 3510 Modified Analysis Description: 8015B CA DRO Silica Gel

Associated Lab Samples: 258781001, 258781002, 258781003

METHOD BLANK: 81693 Matrix: Water

Associated Lab Samples: 258781001, 258781002, 258781003

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
TPH-DRO (C10-C24) SG	ug/L	91.1	50.0	08/16/11 17:52	B-
n-Octacosane (S) SG	%	91	50-150	08/16/11 17:52	
o-Terphenyl (S) SG	%	79	51-147	08/16/11 17:52	

LABORATORY CONTROL SAMPLE: 81694

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
TPH-DRO (C10-C24) SG	ug/L	3120	2630	84	51-147	
n-Octacosane (S) SG	%			97	50-150	
o-Terphenyl (S) SG	%			83	51-147	



Project: 251028 Pace Project No.: 258781

QC Batch: MSV/5156 Analysis Method: EPA 5030B/8260

QC Batch Method: EPA 5030B/8260 Analysis Description: 8260 MSV Water 10 mL Purge

Associated Lab Samples: 258781001, 258781002, 258781003

METHOD BLANK: 82333 Matrix: Water

Associated Lab Samples: 258781001, 258781002, 258781003

		Blank	Reporting		
Parameter	Units	Result	Limit	Analyzed	Qualifiers
1,2-Dibromoethane (EDB)	ug/L	ND	1.0	08/18/11 10:20	
1,2-Dichloroethane	ug/L	ND	1.0	08/18/11 10:20	
Benzene	ug/L	ND	0.50	08/18/11 10:20	
Diisopropyl ether	ug/L	ND	0.50	08/18/11 10:20	
Ethanol	ug/L	ND	250	08/18/11 10:20	
Ethyl-tert-butyl ether	ug/L	ND	0.50	08/18/11 10:20	
Ethylbenzene	ug/L	ND	0.50	08/18/11 10:20	
Methyl-tert-butyl ether	ug/L	ND	0.50	08/18/11 10:20	
tert-Amylmethyl ether	ug/L	ND	0.50	08/18/11 10:20	
tert-Butyl Alcohol	ug/L	ND	5.0	08/18/11 10:20	
Toluene	ug/L	ND	0.50	08/18/11 10:20	
Xylene (Total)	ug/L	ND	1.5	08/18/11 10:20	
1,2-Dichloroethane-d4 (S)	%	102	72-127	08/18/11 10:20	
4-Bromofluorobenzene (S)	%	99	79-121	08/18/11 10:20	
Dibromofluoromethane (S)	%	99	81-119	08/18/11 10:20	
Toluene-d8 (S)	%	99	77-120	08/18/11 10:20	

LABORATORY CONTROL SAMPLE: 82334

		Spike	LCS	LCS	% Rec		
Parameter	Units	Conc.	Result	% Rec	Limits	Qualifiers	
1,2-Dibromoethane (EDB)	ug/L	20	18.4	92	65-123		
1,2-Dichloroethane	ug/L	20	19.2	96	63-131		
Benzene	ug/L	20	19.3	97	66-123		
Diisopropyl ether	ug/L	20	19.5	98	70-136		
Ethanol	ug/L	800	759	95	40-160		
Ethyl-tert-butyl ether	ug/L	20	19.1	96	65-135		
Ethylbenzene	ug/L	20	19.3	97	67-122		
Methyl-tert-butyl ether	ug/L	20	18.6	93	65-138		
tert-Amylmethyl ether	ug/L	20	16.8	84	68-138		
tert-Butyl Alcohol	ug/L	100	95.2	95	57-153		
Toluene	ug/L	20	18.6	93	64-118		
Xylene (Total)	ug/L	60	56.4	94	68-122		
1,2-Dichloroethane-d4 (S)	%			94	72-127		
4-Bromofluorobenzene (S)	%			98	79-121		
Dibromofluoromethane (S)	%			99	81-119		
Toluene-d8 (S)	%			100	77-120		



Project: 251028 Pace Project No.: 258781

MATRIX SPIKE & MATRIX SP	IKE DUPLICAT	E: 82595			82596						
			MS	MSD							
	2	258781001	Spike	Spike	MS	MSD	MS	MSD	% Rec		
Parameter	Units	Result	Conc.	Conc.	Result	Result	% Rec	% Rec	Limits	RPD	Qual
1,2-Dibromoethane (EDB)	ug/L	ND	20	20	20.3	19.1	102	96	61-127	6	
1,2-Dichloroethane	ug/L	ND	20	20	20.2	19.4	101	97	60-138	4	
Benzene	ug/L	ND	20	20	20.3	19.4	101	97	63-138	5	
Diisopropyl ether	ug/L	ND	20	20	20.4	19.3	102	97	68-146	5	
Ethanol	ug/L	ND	800	800	767	733	96	92	40-160	4	
Ethyl-tert-butyl ether	ug/L	ND	20	20	20.3	18.9	101	94	63-138	7	
Ethylbenzene	ug/L	ND	20	20	19.6	18.8	98	94	65-135	4	
Methyl-tert-butyl ether	ug/L	ND	20	20	20.4	19.0	101	93	59-143	7	
tert-Amylmethyl ether	ug/L	ND	20	20	18.8	17.0	94	85	62-142	10	
tert-Butyl Alcohol	ug/L	ND	100	100	103	100	103	100	46-156	3	
Toluene	ug/L	ND	20	20	19.4	18.6	97	93	64-128	4	
Xylene (Total)	ug/L	ND	60	60	56.9	55.3	95	92	65-133	3	
1,2-Dichloroethane-d4 (S)	%						97	97	72-127		
4-Bromofluorobenzene (S)	%						97	98	79-121		
Dibromofluoromethane (S)	%						100	99	81-119		
Toluene-d8 (S)	%						100	100	77-120		



Project:

251028

Pace Project No.:

258781

QC Batch:

MSV/5161

Analysis Method:

**CALUFT** 

QC Batch Method: **CALUFT** 

Parameter

Analysis Description:

CA LUFT MSV GRO

Associated Lab Samples: METHOD BLANK: 82407

258781003

Matrix: Water

Associated Lab Samples:

258781003

Blank Result Reporting Limit

539

82632

50.0

Qualifiers Analyzed

B-

TPH-Gasoline (C05-C12) 4-Bromofluorobenzene (S)

ug/L %

Units

Units

51.6 99

08/18/11 10:20 76-121 08/18/11 10:20

LABORATORY CONTROL SAMPLE:

Parameter

82408

Spike Conc.

LCS Result

LCS % Rec

% Rec Limits

Qualifiers

TPH-Gasoline (C05-C12) 4-Bromofluorobenzene (S)

ug/L %

Units

ug/L

%

500

108 98

57-139

76-121

MATRIX SPIKE & MATRIX SPIKE DUPLICATE:

82631

56.1

258915001

Result

MS

MSD

MS

MS

MSD % Rec % Rec

**RPD** Qual

TPH-Gasoline (C05-C12) 4-Bromofluorobenzene (S)

Parameter

Spike

Spike Conc.

MSD Result

% Rec 103

95

Limits 40-150

.2

Conc. 500 500

Result 572

573

103 98

76-121

Date: 08/24/2011 04:20 PM



Project: 251028 Pace Project No.: 258781

4-Bromofluorobenzene (S)

4-Bromofluorobenzene (S)

QC Batch: MSV/5186 Analysis Method: **CALUFT** 

QC Batch Method: **CALUFT** Analysis Description: CA LUFT MSV GRO

Associated Lab Samples: 258781001, 258781002

METHOD BLANK: 82788 Matrix: Water

%

Associated Lab Samples: 258781001, 258781002

Blank Reporting Limit Parameter Result Analyzed Qualifiers Units TPH-Gasoline (C05-C12) ug/L ND 50.0 08/20/11 15:27 %

LABORATORY CONTROL SAMPLE: 82789

Spike LCS LCS % Rec Parameter Units Conc. Result % Rec Limits Qualifiers TPH-Gasoline (C05-C12) ug/L 500 566 113 57-139 4-Bromofluorobenzene (S) % 97 76-121

99

76-121

08/20/11 15:27

97

97

76-121

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 83265 83266 MSD MS 258781002 Spike Spike MS MSD MS MSD % Rec Parameter Units Result Conc. Conc. Result Result % Rec % Rec Limits **RPD** Qual ND TPH-Gasoline (C05-C12) ug/L 500 500 613 609 120 119 40-150 .7

Date: 08/24/2011 04:20 PM



#### **QUALIFIERS**

Project: 251028 Pace Project No.: 258781

#### **DEFINITIONS**

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to changes in sample preparation, dilution of the sample aliquot, or moisture content.

ND - Not Detected at or above adjusted reporting limit.

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

S - Surrogate

1,2-Diphenylhydrazine (8270 listed analyte) decomposes to Azobenzene.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

**DUP - Sample Duplicate** 

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel Clean-Up

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

#### **LABORATORIES**

PASI-S Pace Analytical Services - Seattle

#### **BATCH QUALIFIERS**

Batch: GCSV/2799

[M5] A matrix spike/matrix spike duplicate was not performed for this batch due to insufficient sample volume.

#### **ANALYTE QUALIFIERS**

B- Analyte detected in method blank but was not detected in the associated samples.



#### **QUALITY CONTROL DATA CROSS REFERENCE TABLE**

Project: 251028 Pace Project No.: 258781

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
258781001	MW-1_20110831	EPA 3510 Modified	OEXT/4200	EPA 8015B	GCSV/2799
258781002	MW-2_20110831	EPA 3510 Modified	OEXT/4200	EPA 8015B	GCSV/2799
258781003	MW-3_20110831	EPA 3510 Modified	OEXT/4200	EPA 8015B	GCSV/2799
258781001	MW-1_20110831	EPA 5030B/8260	MSV/5156		
258781002	MW-2_20110831	EPA 5030B/8260	MSV/5156		
258781003	MW-3_20110831	EPA 5030B/8260	MSV/5156		
258781001	MW-1_20110831	CA LUFT	MSV/5186		
258781002	MW-2_20110831	CA LUFT	MSV/5186		
258781003	MW-3_20110831	CA LUFT	MSV/5161		

### COP ELT CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed and accurate.

Page: 1 of Cooler# of

3Q 2011 Event



Require	d Lab Information:	Required Project Information:		Required Invoice In	nformation:											
Lab Nar	ne: Pace-Seattle	Site ID #: 251028 Task:	WG_Q_201108	Send Invoice to:	Tara Bosch					1						
Address		AnteaGrp proj# 140251028		Address: 11050 V	hite Rock Rd. Suite	110				Turn a	round time	e (days)	10			
940 S. I	lamey Street Seattle WA 98108	Site Address 5300 Broadway		City/State	Rancho Cordova C	A 95670	Phone #: 916-503-	-1267		QC lev	el Require	ed: Standar	d	Special	1	Mark one
Lab PM	Regina Ste. Marie	City Oakland St	ate CA	Reimbursement pro	ject?	Non-reim	nbursement project?	v M	lark one	NJ Re	duced Del	liverable Pa	ckage	?		
Phone/F	ax: P: 206-957-2433 F: 206-767-5063	AG PM Name: Lia Hole		Send EDD to	copeltdata@intellig	ontobs c	om			MA M	CP Cert?	СТ	RCP C	Cert?	1	Mark One
Lab PM	email Regina SteMarie@pacelabs.com	AG PM Name: Lia Hole Phone/Fax: P: 408 826 1863		CC Hardcopy r		entens.c	0111			Lab P	roject ID (	(lab use)				
Applicat	le Lab Quote #:	AG PM Email: lia.holden@	anteagroup.com	CC Hardcopy r	eport to					_	Requested //////					
ITEM#	SAMPLE ID One Character per box. (A-Z, 0-9 /,-) Samples IDs MUST BE UNIQUE	Valid Mathix Codes  MATRIX CRIMAND WATER WATER WATER WATER WATER WATER WATER HOLD UP RISE MODIOL UP RISE MODION	MATRIX CODE SAMPLE TYPE G=GRAB C=COMP	SAMPLE DATE	SAMPLE TIME	#OF CONTAINERS	FIELD FILTERED? (YA)  Japaneserved 1,504 1403	Preservativ	Methanol	Anal	/			/	Comments	
	MW-1 20110831		wg	8/8/11	1310	12	NX	X		x x	х			8015 T	PHd is with	silica
	MW-2 20110831		wg	1	1340	8	1 X	X		x x	x		gel cleanup			
	MW-3_20110831		wg	1	14125	8	J X	X		x x	x					
4 5 6 7														TAME	s = DIPE, ETBE, 1, and Ethan	2-DCA,
8 9 10 11																-1
Addition	al Comments/Special Instructions:		RELINQUISHED BY	/ AFFILIATION	DATE	TIME	ACCEPTED BY / AF	FFILIATION	N	-	DATE	TIME	Samp	le Rece	pt Conditi	ons
			Fano	1375	E/8/11	1600	R	15	Tr		8/9/11	1450		Y/N	Y/N	Y/N
			FED EX	1 110	081011	0810	Colety Wear				081011	0810	1.2	N(Y)	(P)N	Y (N)
			120 24		001011	0010	Cours weren							Y/N	Y/N	Y/N
Glo	oal ID: T0619732490													Y/N	Y/N	Y/N
			SHIPPING METHO UPS COURIER US MAIL	FEDEX PRINT Na		Pa	Trick How		Signed &	TE/N	Time: 16	05'	Temp in <sup>0</sup> C	9 C	Sample intact?	Trip Blank?

ZPLC Ziploc Bag

## Sample Container Count

CLIENT:	F	tntea										_		Face Analytical
COC PAGE _														WITH package Door
Sample Line	VG9H	AG1H	AG1U	BG1H	BP1U	BP2U	BP3U	BP2N	BP2S	WGFU	WGKU	AG211		Comments
1	D									1,0,0	· · · · · ·	2		Comments
2	6											2		
3	6											2		
4														
5														
6														
7														
8														
9														
10														
11														
12														Trip Blank? NO
AG1H	1 liter HCL	amber g	lass			20	BP2S	500mL F	12SO4 pla	stic			JGFU	4oz unpreserved amber wide
	1liter unpre			ss				500mL u						terra core kit
	500mL H2							500mL N						Summa Can
	500mL unp			lass				250mL N						40mL HCL clear vial
	250mL H25							250mL HNO3 plastic						40mL Na Thio. clear vial
	1 liter HCL						BP3S	250mL H2SO4 plastic						40mL unpreserved clear vial
	1 liter unpre		lass					250mL unpreserved plastic						40mL glass vial preweighted (EPA 5035)
	1 liter HNO							40mL Na						Headspace septa vial & HCL
	1 liter H2SC						DG9H	40mL H	CL amber	voa vial				4oz clear soil jar
BP1U	1 liter unpre	served p	lastic				DG9M	40mL Me	OH clear	vial				4oz wide jar w/hexane wipe

DG9T 40mL Na Thio amber vial

I Wipe/Swab

DG9U 40mL unpreserved amber vial

BP1Z 1 liter NaOH, Zn, Ac

BP2N 500mL HNO3 plastic

BP2O 500mL NaOH plastic

# Sample Condition Upon Receipt

Client Name		Project # 2 5 8 7 8 1	
Courier: Fed Ex UPS USPS Clier Tracking #: 8756 1770 0538	nt Commerc	cial Pace Other	
Custody Seal on Cooler/Box Present: Yes	☐ No S	Seals intact: Yes [	□ No
Packing Material: Subble Wrap Bubble	Bags Nor	ne Other	Temp. Blank Yes / No
Thermometer Used 132013 o 101731962 pr 22609			Samples on ice, cooling process has begun
Cooler Temperature  .22 Temp should be above freezing ≤ 6°C	Biological Tis	Sue is Frozen: Yes No Comments:	Date and Initials of person examining contents: () 8 OI CW
Chain of Custody Present:	✓Yes □No □	IN/A 1.	
Chain of Custody Filled Out:	Myes ONO D	IN/A 2.	
Chain of Custody Relinquished:	Tryes No D	IN/A 3.	
Sampler Name & Signature on COC:	☐Yes ☐No ☐	INVA 4.	
Samples Arrived within Hold Time:	ØYes □No □	IN/A 5.	
Short Hold Time Analysis (<72hr):	Dyes DNo D	]N/A 6.	
Rush Turn Around Time Requested:	□Yes No □	3N/A 7.	
Follow Up / Hold Analysis Requested:	□Yes ☑No □	]N/A 8.	
Sufficient Volume:	Myes ONO C	]N/A 9.	
Correct Containers Used:	MYes □No □	IN/A 10.	
-Pace Containers Used:	Øyes □No □	]N/A	
Containers Intact:	ØYes □No □	IN/A 11.	
Filtered volume received for Dissolved tests	□Yes □No □	INA 12.	
Sample Labels match COC:	MYes □No □	IN/A 13.	
-Includes date/time/ID/Analysis Matrix:	WT		
All containers needing preservation have been checked.	□Yes □No ①	IN/A 14.	
All containers needing preservation are found to be in compliance with EPA recommendation.	□Yes □No ☑	N/A	
Exceptions VOA coliform, TOC, O&G		Initial when completed	Lot # of added preservative
Samples checked for dechlorination:	□Yes □No □	KVA 15.	
Headspace in VOA Vials ( >6mm):	□Yes ☑No □	IN/A 16.	
Trip Blanks Present:	□Yes ☑No □	IN/A 17.	8
Trip Blank Custody Seals Present	□Yes □No 🗵	IN/A	
Pace Trip Blank Lot # (if purchased):	-		
Client Notification/ Resolution:			Field Data Required? Y / N
Person Contacted:	, D	ate/Time:	
Comments/ Resolution:			
			· · · · · · · · · · · · · · · · · · ·
Project Manager Review:	R	SM	Date: 08//1///

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e. out of hold, incorrect preservative, out of temp, incorrect containers)

# Is the Data Set Valid? (circle)

Yes / No

Preservati	on Tem	pera	ture
------------	--------	------	------

(if Known): \_\_\_\_\_\_\_\_\_C

## Antea<sup>™</sup>Group Laboratory Data Validation Sheet

Pro	ject/Client: COP/ELT			
	ject #: 140251028		Circle	$\supset$
Dat	e of Validation: 9/6/2011 Date of Analysis: 8/16-20/2011	100	or liabliab	
Sar	Sample Date: 8/8/2011 Completed By: Nadine Periat		Highlight	
	Signature: Male Description		below)	
Ana	alytical Lab Used and Report # (if any): Pace Labs No. 258781		Belowy	
1.	Were the analyses the ones requested?	Yes	<b>)</b>	No
2.	Do the sample number(s) on the chain-of-custody (COC) match the one(s) that appear on the laboratory data sheet?	Yes	)	No
3.	Were samples prepared (extracted, filtered, etc.) within EPA holding times?	Yes	)	No
4.	Once prepared/extracted, were the samples analyzed within the EPA holding times?	Yes	)	No
5.	Were Laboratory blanks performed, if so, were they non-detect?	Yes	<i>v</i> -	No
6.	Are the units correct? (i.e., soil samples in mg/kg or ug/g, water samples mg/L, ug/L, and air samples in volume mg/m³,etc.)	Yes	$\int$	No
7.	Were appropriate Matrix Spike (MS) and Matrix Spike Duplicate (MSD) samples included in the laboratory batch sample?	Yes	$\subset$	No
8.	In lieu of MS/ MSD, were surrogate spike (SS) or surrogate spike duplicate (SSD) samples included in the laboratory batch samples?	Yes	<b>)</b>	No
9.	Were MS/ MSD (or SS/SSD) within the acceptable range of % recovery (i.e., approximately 80-120%, depending on the analyte)?	Yes	>	No
10.	Were MS/MSD (or SS/SSD) values used to calculate Relative Percent Difference (RPD)?	Yes	>	No
11.	Were Relative Percent Difference values within the acceptable range (i.e. ±25%)?	Yes	<i></i> -∕ <sub>6</sub>	No

If any answer is no, explain why and what corrective action was taken (use additional sheet(s), as necessary:

- 5. A method blank contained GRO and DRO above reporting limits. However, these analytes were reported in the parent samples, so the results are not affected
- 7. No MS/MSD was run on QC batch GCSV/2799 due to insufficient sample volume.